

OPERATIONS PERMIT 01-5-1263

Name: (owner) Regency Home New Installation Septic Tank
 Property Location: SR# 1115 Repairs Nitrification Line
 Subdivision Peachtree Lot # 26
 TAX ID# _____ Quadrant # _____
 Contractor: Ted Brown Registration # _____

Basement with Plumbing: Garage:
 Water Supply: Well Public Community
 Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____
 Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons
 Subsurface No. of exact length width of depth of
 Drainage Field ditches 1 of each ditch 300 ft. ditches 3 ft. ditches 18 1/4 in.
 French Drain: _____ Linear feet

PERMIT NO. 19582 Date: 02-12-03
 Inspected by: J. W. [Signature]
 Environmental Health Specialist

