

01-5-2572

No 15013

# OPERATIONS PERMIT

Name: (owner) CARMAN MAXWELL  New Installation  Septic Tank  
 Property Location: SR# 1120 OVERHILLS RD  Repairs  Nitrification Line  
 Subdivision STONE CROSS Lot # 25  
 TAX ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: CARTER Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:   
 Water Supply:  Well  Public  Community  
 Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other POLYSTYRENE AGGREGATE TRENCH  
 Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons  
 Subsurface Drainage Field: No. of ditches 3 exact length of each ditch 80 ft. width of ditches 3 ft. depth of ditches 18-20 in.  
 French Drain: \_\_\_\_\_ Linear feet

Date: 11/21/01

PERMIT NO. 18574

Inspected by: [Signature]  
 Environmental Health Specialist

