

OPERATIONS PERMIT 02-5-3894

Name: (owner) Regency Homes New Installation Septic Tank
Property Location: SR# Lemud Blk #4 Repairs Nitrification Line
Subdivision Carle Hill Lot # 16
TAX ID# _____ Quadrant # _____
Contractor: T. Brown Registration # _____

Basement with Plumbing: Garage: 3 Bedrooms
Water Supply: Well Public Community
Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____
Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons
Subsurface Drainage Field No. of ditches 1 exact length of each ditch 400 ft. width of ditches 3 ft. depth of ditches 18 in.
French Drain: _____ Linear feet

PERMIT NO. 18713 Date: 4-2-02
Inspected by: J. W. ARS
Environmental Health Specialist

