

IMPROVEMENT PERMIT

03-5-5714 Rev.

Be it ordained by the Harnett County Board of Health as follows: Section III, Item B. "No Person shall begin construction of any building at which a septic tank system is to be used for disposal of sewage without first obtaining a written permit from the Harnett County Health Department."

Name: (owner) Jimmy Pierce

New Installation

Septic Tank

Property Location: SR# 9115

Repairs

Nitrification Line

Subdivision Peachtree Lot # 47

Tax ID # _____ Quadrant # _____

Number of Bedrooms Proposed: 3 (45x54) Lot Size: .482 ac

Basement with Plumbing:

Garage:

Please note changes in side line set backs

Water Supply: Well Public Community

Distance From Well: 50 ft.

Following is the minimum specifications for sewage disposal system on above captioned property. Subject to final approval.

Type of system: Conventional Other _____

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 240 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain Required: _____ Linear feet


Date: 11-5-02

This permit is subject to revocation if site plans or intended use change.

Signed: [Signature] Environmental Health Specialist

Lot 48

223



196
 STUB out plumbing shallow - where shown Run PVC pipe From Tank towards the front where 18" pitch ditches can be started and maintained. NOTE Changes in side line set backs meet onsite before installing
 DO NOT DRIVE OR PARK ON SEPTIC SYSTEM

HARNETT COUNTY HEALTH DEPARTMENT
AUTHORIZATION TO CONSTRUCT

Authorization is hereby given to construct a wastewater system to the specifications described by Harnett County Health Department, Improvement Permit # 19794. This authorization shall be valid for a period not to exceed five (5) years from the date of issuance. This authorization will be invalid if ownership, site plans, or intended use change.

Name Jimmy Preece Telephone # 910-328-5257

Address 1115

Property Location SR# Peach Tree Road Name 47
Subdivision 47 Lot # 3(45x54) # Bedrooms Proposed 482 AC Lot size

TYPE OF SYSTEM

New Installation Repair Septic Tank Nitrification Lines

Conventional Other _____
 Basement With Plumbing Without Plumbing

Water Supply: Well Public - Minimum Well Setback: 50 Ft.
Septic Tank POPS Pump Chamber _____

NITRIFICATION FIELD SPECIFICATIONS

Number of fields 1 # of lines per field 1 Length of lines 240 Ft.

Width of ditches 3 ft. Depth of ditches 18 inches

French Drain: Linear feet required _____ Depth of gravel _____

No wastewater system shall be covered or placed into use by any person until an inspection by the Harnett County Health Department has determined that the system has been installed according to the conditions of the Improvement Permit and that a valid Operations Permit has been issued.

Signature of Authorized Agent for Harnett County [Signature] Date 11-5-02