

OPERATIONS PERMIT 03-5-6229

Name: (owner) Weaver Den New Installation Septic Tank
Property Location: SR# 1115 Repairs Nitrification Line
Subdivision Sunset Ridge Lot # 50
TAX ID# _____ Quadrant # _____
Contractor: Larry Sharpe Registration # _____

Basement with Plumbing: Garage: 3 Bedroom
Water Supply: Well Public Community
Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____
Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons
Subsurface Drainage Field: No. of ditches 1 exact length of each ditch 200 ft. width of ditches 3 ft. depth of ditches 18-24 in.
French Drain: _____ Linear feet

PERMIT NO. 19214 Date: 4-14-03
Inspected by: [Signature]
Environmental Health Specialist

