

HTE 03-5-7018

OPERATIONS PERMIT

Name: (owner) Kerth Bullock Builders Inc

New Installation Septic Tank

Property Location: SR# 1439 WED DENNING

Repairs Nitrification Line

Subdivision Adams Pointe

Lot # 184

Tax ID # _____

Quadrant # _____

Contractor: Mike Ray

Registration # 64

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50' ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 2 exact length of each ditch 150 ft. width of ditches 3 ft. depth of ditches 18-22 in.

French Drain Required: - Linear feet

Date: 10-20-03

Inspected by: James E. Markant
Environmental Health Specialist

PERMIT NO. 19997

