

HTE 03-5-7074

OPERATIONS PERMIT

Name: (owner) Russell Lamm Construction

New Installation Septic Tank

Property Location: SR# 1581 Baileys X-RDS

Repairs Nitrification Line

Subdivision Willowbrook

Lot # 3

Tax ID # _____

Quadrant # _____

Contractor: Larry Sharpe

Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50' ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 2 exact length of each ditch 150 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain Required: - Linear feet

Date: 1-7-04

Inspected by: James E. Manlove
Environmental Health Specialist

PERMIT NO. 18812

