

HTE 03-5-8022

# OPERATIONS PERMIT

Name: (owner) R. L. Properties  New Installation  Septic Tank  
 Property Location: SR# 1415  Repairs  Nitrification Line  
 Subdivision Windham Lot # 30  
 Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: Ricky Holland Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:   
 Water Supply:  Well  Public  Community  
 Distance From Well: 50 ft.

**Following are the specifications for the sewage disposal system on above captioned property.**

Type of system:  Conventional  Other Polystyrene Aggregate Trench System

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field No. of ditches 4 exact length of each ditch 60 ft. width of ditches 3 ft. depth of ditches 24 in.

French Drain Required: \_\_\_\_\_ Linear feet

Date: 3/5/2004  
 Inspected by: [Signature] Environmental Health Specialist

PERMIT NO. 20308

