

HTE 0458881

16747

OPERATIONS PERMIT

Name: (owner) CAVINOS Land Dev. New Installation Septic Tank
 Property Location: SR# 1141 Repairs Nitrification Line
 Subdivision HIGHLAND FOREST Lot # 103
 Tax ID # _____ Quadrant # _____
 Contractor: D.C. CARTER Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other 25% Reduction System Poly septic

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 2 exact length of each ditch 75 ft. width of ditches 3 ft. depth of ditches 18-24 in.

French Drain Required: _____ Linear feet

Date: 12-22-04

Inspected by: Jr WALKER
Environmental Health Specialist

PERMIT NO. 20698

MCP-1000
STB-814
9-9-04



Notes 12-22-04