

HTE 04-5-8928

17216

OPERATIONS PERMIT

Name: (owner) Caviness Land New Installation Septic Tank
 Property Location: SR# 1141 Repairs Nitrification Line
 Subdivision Highland Forest Lot # 105
 Tax ID # _____ Quadrant # _____
 Contractor: D.C. Carter Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other 25% Reduction system EEC-222 Flow

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 210 ft. width of ditches 3 ft. depth of ditches 18 1/4 in.

French Drain Required: _____ Linear feet

Date: 2-18-05

Inspected by: Joe Warr
Environmental Health Specialist

PERMIT NO. 20691

MEP-1000 SIB 814 10-21-04

