

HTE 04-5-9150

16601

# OPERATIONS PERMIT

Name: (owner) HGH Constructor  New Installation  Septic Tank  
 Property Location: SR# 1117  Repairs  Nitrification Line  
 Subdivision Woodshire Lot # 39  
 Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: O. Strickland Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 50 ft.

**Following are the specifications for the sewage disposal system on above captioned property.**

Type of system:  Conventional  Other Pump to Conventional

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 200 ft. width of ditches 3 ft. depth of ditches 18-24 in.

French Drain Required: \_\_\_\_\_ Linear feet

Date: 09-16-04

Inspected by: Jon Walters  
Environmental Health Specialist

PERMIT NO. 20432

