

HTE#08-5-20908

Harnett County Department of Public Health

25179

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: ROBERT NAYLORPROPERTY LOCATION: 401 NORTHNEW ☒ REPAIR ☐ EXPANSION ☐SUBDIVISION Lilly Pads Child Dev. Ctr. LOT #

AKA

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: DAYCARE (50'x120')Proposed Wastewater System Type: PUMP TO CONVENTIONALProjected Daily Flow: 2100 GPDNumber of bedrooms: Number of Occupants: 140 maxBasement ☐ Yes ☒ NoPump Required: ☒ Yes ☐ No ☐ May be required based on final location and elevations of facilitiesType of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well 100 feetPermit conditions: 28.9 ACRE LOTPermit valid for: ☒ Five years
☐ No expirationAuthorized State Agent: [Signature]Date: 2/11/09

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: ROBERT NAYLORPROPERTY LOCATION: 401 NORTHSUBDIVISION LOT # Facility Type: DAYCARE (50'x120') ☒ New ☐ Expansion ☐ RepairBasement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ NoType of Wastewater System** PUMP TO CONVENTIONAL (Initial) Wastewater Flow: 2100 GPD(See note below, if applicable ☐)PUMP TO CONVENTIONAL (Repair)

Installation Requirements/Conditions

Septic Tank Size 2700 gallonsPump Tank Size 2700 gallonsGREASE TRAP 1800 gallons

* ALL TANKS SHALL HAVE RISERS

Number of trenches 10Exact length of each trench 180 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 18-36 inches(Trench bottoms shall be level to $\pm 1/4"$

in all directions)

Trench Spacing: 9 Feet on CenterSoil Cover: 6-18 inches

(Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: ft. TDH vs. GPMAggregate Depth: 6 inches below pipe2 inches above pipeConditions: PRESSURE MANIFOLD OR MANHOLE REQUIRED - 3" SUPPLY LINE, 2' PRESSURE HEAD, 12 inches total10 3/4" SCH 40 TAPS. PUMP SIZE TO BE FINALIZED AFTER FINAL DRAINFIELD LAYOUT. MEET ON SITETO FINALIZE DRAINFIELD LAYOUT PRIOR TO INSTALLATION. COMMERCIAL FILTER REQUIRED IN SEPTIC TANK

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: [Signature]Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This

Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature]Date: 2/11/09Construction Authorization Expiration Date: 2/11/14

HTE# 08-5-20908

Permit # 25179

Harnett County Department of Public Health Site Sketch

ISSUED TO: ROBERT NAYLOR PROPERTY LOCATION: 401 NORTH
SUBDIVISION: Lilly Pads Child Dev. Ctr. LOT #
AKA
Authorized State Agent: ~~ES (OLIVER TOLKSON)~~ Date: 2/11/09

* 28.9 ACRE
LOT

* DRAWING
NTS

