

HARPER'S MEADOW SITE DEVELOPMENT PLANS



VICINITY MAP
NOT TO SCALE

EXISTING UTILITY OWNER

SEWER

LILLINGTON PUBLIC WORKS DEPARTMENT
PO Box 296
Lillington, North Carolina 27546
910-893-0314
Contact: Shane Cummings, PE

WATER

HARNETT REGIONAL WATER
700 McKinney Parkway
Lillington, North Carolina 27546
910-893-7575
Contact: Glenn McFadden

SOURCE OF TITLE
DB 4177, PG 1478
HARNETT COUNTY
REGISTER OF DEEDS

REZONING CONDITIONS

1. MINIMUM LOT SIZE - 20'x100'
2. FRONT SETBACK - 20', REAR SETBACK - 10',
SIDE SETBACK - 0', CORNER SIDE - 10'
3. GARAGES FOR TOWN HOMES WILL BE FRONT
ENTRY.
4. SINGLE STREET CONNECTION TO NC 210 WITH
TWO ROAD STUBS TO ADJOINING PROPERTY AS
SHOWN.

INDEX OF DRAWINGS

G1.0 - PROJECT NOTES

C1.0 - EXISTING CONDITIONS

C2.0 - SITE PLAN

C3.0 - GRADING AND EROSION CONTROL PLAN

C3.1 - DETAILED WET POND PLAN

C4.0 - UTILITY PLAN

C4.1 - STORM & SEWER STRUCTURE DATA

C5.0 - 5.5 - PROFILES

C6.0 - SITE DETAILS

C6.1 - 6.2 - EROSION CONTROL DETAILS

C6.3 - SITE & EROSION CONTROL DETAILS

C6.4 - 6.5 - STORM DETAILS

C6.6 - WATER DETAILS

C6.7 - WATER & SEWER DETAILS

C6.8 - SEWER DETAILS

C6.9 - LIFT STATION DETAILS

APPROVED

SEP 13 2024

HARNETT REGIONAL WATER
PO BOX 1119
LILLINGTON, NC 27546

REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

**HARPER'S
MEADOW**

PIN: 0651-90-8197.000
N MAIN ST/ NC HWY 210
NEILLS CREEK TOWNSHIP
TOWN OF LILLINGTON
HARNETT COUNTY
NORTH CAROLINA

CLIENT

**TRIANGLE LAND
PARTNERS, LLC**

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE

SEE SHEETS

DATE RELEASED

MARCH 22, 2024



Know what's below.
Call before you dig.

CIVIL ENGINEER


4D SITE SOLUTIONS, INC.
409 Chicago Drive - Suite 112
Fayetteville, North Carolina 28306
910-426-6777
Contact: Scott Brown, PE
email: sbrown@4dsitesolutions.com

OWNER/DEVELOPER

TRIANGLE LAND PARTNERS, LLC
PO Box 5548
Cary, North Carolina 27512
704-608-3085
Contact: Kirby LaForce
email: carolinalandgroup@outlook.com

SURVEYOR

4D SITE SOLUTIONS, INC.
409 Chicago Drive - Suite 112
Fayetteville, North Carolina 28306
910-426-6777
Contact: Jimmy Holland, PLS
email: jholland@4dsitesolutions.com



THE CONTRACTOR MUST CONTACT NORTH CAROLINA ONE CALL CENTER AT 1-800-632-4949 A MINIMUM OF 72 HOURS PRIOR TO DIGGING IN ORDER TO HAVE THE EXISTING UTILITIES LOCATED

ISSUED FOR CONSTRUCTION


HARPER'S MEADOW

**TRIANGLE LAND
PARTNERS, LLC**

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

G-1.0

\\Triangle Land Partners\1896-Harper's Meadow\CIVIL 3D\DWG\1896-DESIGN.dwg • 01 G1.0 NOTES • 3/22/2024 2:23:23 PM



- NOTES:
1. ALL DISTANCES SHOWN ARE HORIZONTAL GROUND DISTANCES UNLESS OTHERWISE NOTED.
 2. COMBINED SCALE FACTOR: 0.99987707
LOCALIZATION POINT N: 609,133.262 E: 2,060,013.076
CONTROL ESTABLISHED VIA NORTH CAROLINA GEODETIC SURVEY VIRTUAL REFERENCE SYSTEM.
 3. THE HORIZONTAL AND VERTICAL CONTROL FOR THIS SURVEY WERE ESTABLISHED USING THE NORTH CAROLINA GEODETIC SURVEY VIRTUAL REFERENCE SYSTEM.
 4. LINES NOT SURVEYED ARE SHOWN AS DASHED LINES FROM INFORMATION REFERENCED ON THE FACE OF THIS MAP.
 5. NONCONFORMING STRUCTURES HAVE NOT BEEN CREATED BY THIS SURVEY.
 6. THE SUBJECT PROPERTY IS THE SAME AS THE PROPERTY DESCRIBED IN THAT CERTAIN TITLE COMMITMENT ID. KEY2022-00197 ISSUED BY KEYSTONE TITLE, LLC WITH AN EFFECTIVE DATE OF JUNE 6, 2022, AND ALL EASEMENTS, COVENANTS AND RESTRICTIONS REFERENCED IN SAID TITLE COMMITMENT OR APPARENT FROM A PHYSICAL INSPECTION OF THE SUBJECT PROPERTY OR OTHERWISE KNOWN TO ME HAVE BEEN PLOTTED HEREON OR OTHERWISE NOTED AS TO THEIR EFFECT ON THE SUBJECT PROPERTY.
 7. LOCATIONS OF ALL UNDERGROUND UTILITIES LYING WITHIN THIS MAPPED AREA MAY NOT BE SHOWN ON THIS PLAN. DEVELOPERS OR CONTRACTORS SHOULD NOT ONLY MAKE SUBSURFACE INVESTIGATIONS BUT SHOULD ALSO ALLOW FOR CONTINGENCIES WHICH MIGHT ARISE BY REASON OF ENCOUNTERING UNRECORDED LINES OR OF LINES BEING IN DIFFERENT LOCATIONS THAN INDICATED ON THIS SURVEY.
 8. THIS PROPERTY LIES WITHIN FLOOD ZONE "X" ACCORDING TO MAP # 3720064000J OF THE FLOOD INSURANCE RATE, DATED OCTOBER 3, 2006 AND MAP # 3720066000J OF THE FLOOD INSURANCE RATE, DATED OCTOBER 3, 2006.

AREA: (BY COORDINATE COMPUTATION)
419,655 SF (9.63 AC)

PIN: 0651-90-8197.000

ZONING: CD-RMF

20' FRONT
0' SIDE
10' CORNER SIDE
10' REAR

SOURCE OF TITLE
DB 4177, PG 1478
HARNETT COUNTY
REGISTER OF DEEDS

CONTROL POINT LIST				
POINT #	NORTHING	EASTING	ELEVATION	DESCRIPTION
1	609,133.262	2,060,013.076	218.86	4D DISK
2	608,666.615	2,059,673.036	208.69	4D DISK
3	609,544.627	2,060,263.865	226.78	4D DISK

VICINITY MAP
NOT TO SCALE

- LEGEND:
- EIP - EXISTING IRON PIPE
 - EPK - EXISTING PK NAIL
 - ERB - EXISTING REBAR
 - - COMPUTED POINT
 - N/F - NOW OR FORMERLY
 - R/W - RIGHT OF WAY
 - - PROPERTY LINE
 - - ADJACENT PROPERTY LINE
 - - RIGHT-OF-WAY
 - - SETBACK LINE
 - SS - SANITARY SEWER LINE
 - SD - STORM DRAINAGE
 - W - WATER LINE
 - UGT - UNDERGROUND TELEPHONE LINE
 - - OVERHEAD UTILITY
 - - PERMANENT EASEMENT
 - - TREE LINE
 - 225 - MAJOR CONTOUR
 - 222 - MINOR CONTOUR
 - 222.47' SPOT ELEVATION
 - ⬤ - BENCHMARK
 - ☐ - SIGN
 - ☐ - MAILBOX
 - ☐ - LANDSCAPING LIGHT
 - PP - UTILITY POLE
 - - GUY WIRE
 - ☐ - TELEPHONE PEDESTAL
 - ☐ - WATER VALVE
 - ☐ - FIRE HYDRANT
 - ☐ - WATER METER
 - ☐ - SANITARY SEWER MANHOLE
 - ☐ - HARDWOOD TREE
 - ☐ - PINE TREE
 - ☐ - SHRUB
 - ☐ - RIP RAP/GRAVEL
 - ☐ - ASPHALT
 - ☐ - BUILDINGS

I, SEAN R. SEEVER, CERTIFY THAT THIS SURVEY IS OF AN EXISTING PARCEL OR PARCELS OF LAND OR ONE OR MORE EXISTING EASEMENTS AND DOES NOT CREATE A NEW STREET OR CHANGE AN EXISTING STREET.

Sean R. Seever
PROFESSIONAL LAND SURVEYOR - L-4571

I, SEAN R. SEEVER, CERTIFY THAT THIS MAP WAS DRAWN UNDER MY SUPERVISION FROM AN ACTUAL SURVEY MADE UNDER MY SUPERVISION (DEED DESCRIPTION RECORDED IN BOOK _____ PAGE _____ OR OTHER REFERENCE SOURCE _____); THAT THE BOUNDARIES NOT SURVEYED ARE INDICATED AS DRAWN FROM INFORMATION IN BOOK _____ PAGE _____ OR OTHER REFERENCE SOURCE _____; THAT THE RATIO OF PRECISION OR POSITIONAL ACCURACY IS 1:10,000+; AND THAT THIS MAP MEETS THE REQUIREMENTS OF THE STANDARDS OF PRACTICE FOR LAND SURVEYING IN NORTH CAROLINA (21 NCAC 56.1600). WITNESS MY HAND AND SEAL THIS 22 DAY OF MARCH, 2024.

Sean R. Seever
PROFESSIONAL LAND SURVEYOR - L-4571

I, SEAN R. SEEVER, CERTIFY THAT THE CONTROL FOR THIS SURVEY WAS ESTABLISHED FROM AN ACTUAL GPS SURVEY UNDER MY SUPERVISION. THIS GPS SURVEY WAS PERFORMED TO C-201 FGCC SPECIFICATIONS RTK GPS WITH VRS FIELD PROCEDURES WERE USED. THE COORDINATES WERE OBTAINED THROUGH A GRID TO GROUND ADJUSTMENT USING THE COMBINED SCALE FACTOR SHOWN HEREON. THIS SURVEY WAS PERFORMED ON MAY 5, 2022 USING TWO TRIMBLE 5700 RECEIVERS.

Sean R. Seever
PROFESSIONAL LAND SURVEYOR - L-4571

I, SEAN R. SEEVER, CERTIFY THAT THIS CLASS "C" TOPOGRAPHIC MAP WAS DRAWN FROM AN ACTUAL SURVEY PERFORMED UNDER MY DIRECT SUPERVISION AND THAT IT MEETS OR EXCEEDS THE NORTH CAROLINA ADMINISTRATIVE CODE 21.56.1605 AND 21.56.1606. WITNESS MY HAND AND SEAL THIS 22 DAY OF MARCH, A.D., 2024.

Sean R. Seever
PROFESSIONAL LAND SURVEYOR - L-4571



REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

**HARPER'S
MEADOW**

**EXISTING
CONDITIONS**

CLIENT

**TRIANGLE LAND
PARTNERS, LLC**

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

SURVEYED BY:	CLIFF
DRAWN BY:	SEAN
CHECKED BY:	JIMMY
PROJECT NUMBER:	1896

DRAWING SCALE

HORIZONTAL: 1"=50'

DATE SURVEYED

MAY 5, 2022

SHEET NUMBER

C-1.0



VICINITY MAP NOT TO SCALE

- LEGEND:
- EIP - EXISTING IRON PIPE
 - EPK - EXISTING PK NAIL
 - ERB - EXISTING REBAR
 - CP - COMPUTED POINT
 - N/F - NOW OR FORMERLY
 - R/W - RIGHT OF WAY
 - TOL - TOWN OF LILLINGTON
 - PROPERTY LINE
 - ADJACENT PROPERTY LINE
 - RIGHT-OF-WAY
 - SETBACK LINE
 - SS - SANITARY SEWER LINE
 - SD - STORM DRAINAGE
 - W - WATER LINE
 - UT - UNDERGROUND TELEPHONE LINE
 - OVERHEAD UTILITY
 - PERMANENT EASEMENT
 - TREE LINE
 - 225 - MAJOR CONTOUR
 - 222 - MINOR CONTOUR
 - X 225.47 - SPOT ELEVATION
 - BENCHMARK
 - SIGN
 - MAILBOX
 - LANDSCAPING LIGHT
 - LIGHT POLE
 - UTILITY POLE
 - GUY WIRE
 - TELEPHONE PEDESTAL
 - WATER VALVE
 - FIRE HYDRANT
 - WATER METER
 - SANITARY SEWER MANHOLE
 - HARDWOOD TREE
 - PINE TREE
 - SHRUB
 - RIP RAP/GRAVEL
 - ASPHALT
 - BUILDINGS



SITE DATA

DEVELOPER	TRIANGLE LAND PARTNERS, LLC
MAILING ADDRESS	PO BOX 5548
CITY, STATE	CARY, NORTH CAROLINA 27512
PIN NUMBER	0651-90-8197.000
TOWNSHIP	NEILLS CREEK
TOTAL SITE ACREAGE	9.63 AC
ACREAGE TO BE DEVELOPED	9.63 AC
ZONING	CD-RMF
EXISTING USE	UNDEVELOPED/RESIDENTIAL
PROPOSED USE	RESIDENTIAL
DISTURBED/DENUDED AREA	10.82 AC
SETBACKS REQUIRED:	
FRONT	20 FT
SIDE	0 FT
CORNER SIDE	10 FT
REAR	10 FT
OPEN SPACE REQUIRED:	
TOTAL REQUIRED (15%)	61,066 SF
USABLE SPACE REQUIRED (5%)	20,356 SF
TOTAL PROVIDED	75,369 SF
USABLE SPACE PROVIDED	28,342 SF
PARKING:	
REQUIRED	
2 SP/UNIT	150 SPACES
0.25 SP/UNIT (QUEST)	19 SPACES
TOTAL REQUIRED	169 SPACES
TOTAL PROVIDED	169 SPACES

ROAD NAME	TOTAL LENGTH
BRAYDENS WAY	246
HARPERS MEADOW	751
ROSE LANDING	865

CURVE	LENGTH	RADIUS	BEARING	CHORD
C1	43.45	25.00	N33°19'05"W	38.18
C2	12.18	205.00	N84°48'37"W	12.17
C3	20.03	205.00	N89°18'40"W	20.02
C4	4.84	100.00	S89°16'30"W	4.84
C5	24.48	100.00	N82°19'39"W	24.42
C6	23.47	100.00	N68°35'31"W	23.41
C7	20.04	100.00	N56°07'40"W	20.01
C8	20.34	100.00	N44°33'31"W	20.31
C9	21.61	100.00	N32°32'19"W	21.57
C10	39.07	100.00	N15°09'15"W	38.82
C11	9.75	100.00	N01°10'09"W	9.74
C12	39.27	25.00	N43°22'35"W	35.36
C13	39.27	25.00	S46°37'25"W	35.36
C14	39.27	25.00	N43°22'35"W	35.36
C15	39.27	25.00	N46°37'25"E	35.36
C16	40.90	25.00	S45°14'36"E	36.49
C17	55.37	255.00	N85°53'25"W	55.26
C18	36.59	25.00	N58°24'04"E	33.41
C19	37.64	25.00	N44°45'24"E	34.18
C20	70.23	50.00	N51°52'16"W	64.60
C21	11.57	50.00	N05°00'14"W	11.54
C22	39.27	25.00	S46°37'25"W	35.36
C23	39.27	25.00	N43°22'35"W	35.36

N/F
BRUCE JOHNSON, LLC
DB 4109, PG 436




SITE NOTES

- EXISTING UNDERGROUND UTILITIES ARE SHOWN ONLY WHERE EVIDENCE COULD BE FOUND TO VERIFY LOCATION. PRIOR TO CONSTRUCTION OR EXCAVATION OF THE SITE, THE GENERAL CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES TO VERIFY THE LOCATION OF THEIR RESPECTIVE UTILITIES. ALL DAMAGE INCURRED TO EXISTING UTILITIES DURING CONSTRUCTION SHALL BE REPAIRED AT THE GENERAL CONTRACTOR'S EXPENSE.
- ASPHALT AND BASE TYPE SHALL BE PER THE DETAILS.
- HANDICAP RAMPS, SIGNAGE AND PARKING SPACES SHALL BE PROVIDED BY THE CONTRACTOR AND INSTALLED PER FEDERAL ADA AND LOCAL REQUIREMENTS.
- ALL DIMENSIONS ARE TO THE BACK OF CURB OR TO THE FACE OF SIDEWALK UNLESS OTHERWISE NOTED.
- ALL RADI ARE 5' UNLESS OTHERWISE NOTED.
- PARKING STALLS MUST BE STRIPED WITH A 4 INCH CONTRASTING STRIPE (YELLOW ON CONCRETE AND YELLOW OR WHITE ON ASPHALT PARKING LOTS).
- HANDICAP PARKING SPACES ARE TO BE DESIGNATED BY BLUE STRIPING AND EITHER A BLUE SYMBOL ON A WHITE BACKGROUND OR A WHITE SYMBOL ON A BLUE BACKGROUND. ALL HANDICAP PARKING STALLS REQUIRE THE INSTALLATION OF THE PROPER SIGNAGE.
- ALL PARKING SPACES ARE TO BE LAID OUT IN ACCORDANCE WITH THE SITE PLAN DIMENSIONS.
- ALL WASTE MATERIAL SHALL BE DISPOSED OF OFF-SITE IN ACCORDANCE WITH STATE AND LOCAL LAWS AND REGULATIONS.
- ALL SITE IMPROVEMENTS SHALL BE INSTALLED PER TOWN OF LILLINGTON AND STATE REGULATIONS.
- LAND USE CLASS: SINGLE FAMILY RESIDENTIAL
- LOT COUNT: 75
- WATERSHED CLASSIFICATION: WS-VY-PA
- THIS PROJECT LIES WITHIN 1 MILE OF A VOLUNTARY AGRICULTURAL DISTRICT.
- NC 210N IS ON THE NCDOT THOROUGHFARE PLAN.
- FOUNDATION SURVEYS WILL BE REQUIRED FOR LOTS.
- NO PARKING WITHIN R/W WILL BE PERMITTED.
- STREET AND STORM WATER DRAINAGE IMPROVEMENTS TO BE INSTALLED IN ACCORDANCE WITH THE TOWN OF LILLINGTON STANDARD ROADWAY, SIDEWALK, CURB & GUTTER, & DRAINAGE PIPE SPECIFICATIONS.
- OPEN SPACES, SIGNAGE, MAIL KIOSK, DRAINAGE EASEMENTS, LANDSCAPING, PARKING LOTS, AND ALL OTHER ITEMS NOT UNDER TOWN PURVIEW TO BE MAINTAINED BY THE HOME OWNERS ASSOCIATION ("HOA"), PROPERTY OWNERS ASSOCIATION ("POA"), CONDOMINIUM OWNERS ASSOCIATION ("COA"), OR ANY OTHER ASSOCIATION RESPONSIBLE FOR THE MAINTENANCE AND/OR UPKEEP OF THE RESIDENTIAL COMMUNITY.

- LANDSCAPING NOTES:
- HEIGHT AND SPREAD OF TREE SPECIMEN SHALL MEET REQUIREMENTS OF THE AMERICAN ASSOCIATION OF NURSERYMEN, AMERICAN STANDARD FOR NURSERY STOCK.
 - EACH TREE MUST BE PLANTED SUCH THAT THE ROOT FLARE IS VISIBLE AT THE TOP OF THE ROOT BALL. TREES WHERE THE ROOT FLARE IS NOT VISIBLE SHALL BE REJECTED. DO NOT COVER THE ROOT FLARE WITH MULCH.
 - DO NOT PLACE MULCH IN CONTACT WITH THE TREE TRUNK. KEEP MULCH A MIN. OF 4" AWAY FROM THE TRUNK BASE.
 - STREET TREE LOCATIONS ARE FOR ILLUSTRATION PURPOSES ONLY. PLACEMENT OF TREES TO BE ADJUSTED FOR DRIVEWAYS AND UTILITIES.


*THIS LANDSCAPING PLAN IS THE MINIMUM REQUIRED TO MEET WITH THE TOWN OF LILLINGTON UDD. THE OWNER OR DEVELOPER IS ENCOURAGED TO CONSULT WITH A LANDSCAPE ARCHITECT IN ORDER TO DEVELOP A PLAN THAT IS MORE IN DEPTH THAN THE MINIMUM REQUIREMENTS. THIS PLAN IS FOR PERMITTING PURPOSES ONLY.

QTY.	TYPE	PLANTING SIZE	MIN. HEIGHT	SCIENTIFIC NAME
68	WILLOW OAK	3" CALIPER	8'	QUERCUS PHELLOS
11	FLOWERING DOGWOOD	1.5" CALIPER	8'	CORNUS FLORIDA
101	JAPANESE HOLLY	5 GAL.	18"	ILEX CRENATA



TYPICAL SECTION No. 3E

2 LANE WITH TWO WAY LEFT TURN LANE.
CURB & GUTTER, SIDEWALKS, AND SIDEPATH



REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

**HARPER'S
MEADOW**

SITE PLAN

CLIENT

**TRIANGLE LAND
PARTNERS, LLC**

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE

HORIZONTAL: 1"=40'

DATE RELEASED

MARCH 22, 2024

SHEET NUMBER

C-2.0



VICINITY MAP NOT TO SCALE

NOTIFICATION OF COMBINED SELF-MONITORING AND SELF-INSPECTION FORM:

THE SEDIMENTATION POLLUTION CONTROL ACT WAS AMENDED IN 2006 TO REQUIRE THAT PERSONS RESPONSIBLE FOR LAND-DISTURBING ACTIVITIES INSPECT A PROJECT AFTER EACH PHASE OF THE PROJECT TO MAKE SURE THAT THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN IS BEING FOLLOWED. RULES DETAILING THE DOCUMENTATION OF THESE INSPECTIONS TOOK EFFECT OCTOBER 1, 2010.

TO SIMPLIFY DOCUMENTATION OF SELF-INSPECTION REPORTS AND NPDES SELF-MONITORING REPORTS, DWO AND DEMUR DEVELOPED A COMBINED FORM. THE SELF-INSPECTION PROGRAM IS SEPARATE FROM THE WEEKLY SELF-MONITORING PROGRAM OF THE NPDES STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES. THE FOCUS OF THE SELF-INSPECTION REPORT IS THE INSTALLATION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROL MEASURES ACCORDING TO THE APPROVED PLAN. THE INSPECTIONS SHOULD BE CONDUCTED AFTER EACH PHASE OF THE PROJECT, AND CONTINUED UNTIL PERMANENT GROUND COVER IS ESTABLISHED. THE FORM CAN BE ACCESSED AT: [HTTP://PORTAL.NCDEM.ORG/WEB/LR/EROSION](http://PORTAL.NCDEM.ORG/WEB/LR/EROSION)

IF YOU HAVE QUESTIONS OR CANNOT ACCESS THE FORM, PLEASE CONTACT THE FAYETTEVILLE REGIONAL OFFICE AT (910) 433-3300.

LEGEND:
EIP - EXISTING IRON PIPE
EPK - EXISTING PK NAIL
ERB - EXISTING REBAR
C - COMPUTED POINT
N/F - NOW OR FORMERLY
R/W - RIGHT OF WAY
T - TOWN OF ULLINGTON
--- PROPERTY LINE
--- ADJACENT PROPERTY LINE
--- RIGHT-OF-WAY
--- SETBACK LINE
SS - SANITARY SEWER LINE
SD - STORM DRAINAGE
W - WATER LINE
UT - UNDERGROUND TELEPHONE LINE
// OVERHEAD UTILITY
--- PERMANENT EASEMENT
--- TREE LINE
--- MAJOR CONTOUR
--- MINOR CONTOUR
X 225.47 SPOT ELEVATION
BENCHMARK
SIGN
MAILBOX
LANDSCAPING LIGHT

PP - UTILITY POLE
GUY WIRE
TELEPHONE PEDESTAL
WATER VALVE
FIRE HYDRANT
WATER METER
SANITARY SEWER MANHOLE
HARDWOOD TREE
PINE TREE
SHRUB
RIP RAP/GRAVEL
ASPHALT
BUILDINGS
LOC - LOC
LIMITS OF CONSTRUCTION
SILT FENCE LINE
JUTE NETTING
DIV - DIVERSION BERM
INLET PROTECTION

GROUND STABILIZATION CHART


SITE AREA DESCRIPTION	STABILIZATION TIME FRAME	STABILIZATION TIME FRAME EXCEPTIONS
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HOW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED
SLOPES 3:1 OR FLATTER	14 DAYS	7-DAYS FOR SLOPES GREATER THAN 50 FEET LENGTH
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE (EXCEPT FOR PERIMETERS AND HOW ZONES)

EROSION CONTROL NOTES

- ALL INLET/OUTLET PROTECTION WILL BE CHECKED FOR MAINTENANCE AND FAILURE EACH ACTIVE DAY ON SITE. SEDIMENT WILL BE REMOVED FROM THE SEDIMENT TRAP AND INLET PROTECTION DEVICES WHEN THE STORAGE CAPACITY HAS BEEN APPROXIMATELY 50% FILLED. GRAVEL WILL BE CLEANED OR REPLACED WHEN THE SEDIMENT POOL NO LONGER DRAINS PROPERLY. SEDIMENT WILL BE REMOVED FROM BEHIND THE SEDIMENT FENCE WHEN IT BECOMES ABOUT 15' DEEP AT THE FENCE. THE SEDIMENT FENCE WILL BE REPAIRED AS NEEDED TO MAINTAIN A PROPER BARRIER.
- TEMPORARY EROSION CONTROL FACILITIES AND/OR PERMANENT FACILITIES INTENDED TO CONTROL EROSION OF AND EARTH DISTURBANCE OPERATION SHALL BE INSTALLED BEFORE ANY EARTH DISTURBANCE OPERATIONS TAKE PLACE OR AT THE EARLIEST POSSIBLE POINT DURING CONSTRUCTION.
- TEMPORARY OR PERMANENT EROSION CONTROL MEASURES SHALL BE CONSTRUCTED PER THE DETAILS HEREIN, OR SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE NORTH CAROLINA EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL.
- THE CONTRACTOR MUST NOTIFY THE APPROPRIATE NCEQ OFFICE A MINIMUM OF 48 HOURS PRIOR TO BEGINNING ANY LAND DISTURBING ACTIVITIES. 910-433-3300.
- REMOVE ALL SOILS AND SEDIMENTS TRACKED OR OTHERWISE DEPOSITED ONTO PUBLIC AND PRIVATE PAYMENT AREAS. REMOVAL SHALL BE ON A DAILY BASIS WHEN TRACKING OCCURS.
- LOCATE SOIL STOCKPILES NO LESS THAN FIFTY (50) FEET FROM ANY PUBLIC OR PRIVATE ROADWAY OR DRAINAGE CHANNEL. IF REMAINING FOR MORE THAN SEVEN DAYS, STABILIZE THE STOCKPILES BY VEGETATIVE COVER, TARPS, OR OTHER MEANS. CONTROL EROSION FROM ALL STOCKPILES BY PLACING SILT BARRIERS AROUND THE PILES. TEMPORARY STOCKPILES LOCATED ON PAVED SURFACES MUST BE NO LESS THAN FIVE FEET FROM THE DRAINAGE/GUTTER LINE AND SHALL BE COVERED IF LEFT MORE THAN 24 HOURS.
- MAINTAIN ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES IN PLACE UNTIL THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED. INSPECT TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES ON A DAILY BASIS AND REPLACE DETERIORATED, DAMAGED, OR ROTTED EROSION CONTROL DEVICES IMMEDIATELY.
- TEMPORARILY OR PERMANENTLY STABILIZE DENuded AREAS WHICH HAVE BEEN FINISH GRADED, AND ALL DENuded AREAS IN WHICH GRADING OR SITE BUILDING

- CONSTRUCTION OPERATIONS ARE NOT ACTIVELY UNDERWAY AGAINST EROSION DUE TO RAIN, WIND AND RUNNING WATER WITHIN 14 DAYS. USE SEEDING AND MULCHING, EROSION CONTROL MATTING, AND/OR SODDING AND STAKING IN GREEN SPACE AREAS AND OTHERWISE APPROPRIATE MEASURES. USE EARLY APPLICATION OF GRAVEL BASE ON AREAS TO BE PAVED.
- DO NOT REMOVE ANY EROSION AND SEDIMENT CONTROL DEVICES AFTER THE PROTECTED AREA HAS UNDERGONE FINAL STABILIZATION AND PERMANENT VEGETATION HAS BEEN ESTABLISHED. IT IS RECOMMENDED THAT NCEQ APPROVE THE ACTION PRIOR TO REMOVAL.
 - THE CONSTRUCTION ENTRANCE SHALL BE INSTALLED CONCURRENTLY WITH THE INITIATION OF CONSTRUCTION ACTIVITY.
 - THE INSTALLATION OF EROSION CONTROL MEASURES SHALL TAKE PRECEDENCE OVER ALL OTHER CONSTRUCTION ACTIVITIES.
 - THE PERMITTEE SHALL BE HELD RESPONSIBLE FOR THE ACTIONS AND PERFORMANCE OF ANY OTHER PARTIES PERFORMING WORK ON THIS PROJECT.
 - ALL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL, BUT IN NO CASE LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS WILL BE MADE IMMEDIATELY TO MAINTAIN ALL PRACTICES AS DESIGNED.
 - PURSUANT TO G.S. 113A-57(2), THE ANGLE FOR GRADED SLOPES AND FILLS SHALL BE NO GREATER THAN THE ANGLE THAT CAN BE RETAINED BY VEGETATIVE COVER OR OTHER ADEQUATE EROSION CONTROL DEVICES OR STRUCTURES. IN ANY EVENT, SLOPES LEFT EXPOSED WILL, WITHIN 7 OR 14 CALENDAR DAYS OF COMPLETION OF ANY PHASE OF GRADING, BE PLANTED OR OTHERWISE PROVIDED WITH TEMPORARY OR PERMANENT GROUND COVER, DEVICES OR STRUCTURES SUFFICIENT TO RESTRAIN EROSION. PURSUANT TO G.S. 113A-57(3), PROVISIONS FOR PERMANENT GROUND COVER SUFFICIENT TO RETAIN EROSION MUST BE ACCOMPLISHED FOR ALL DISTURBED AREAS WITHIN 90 CALENDAR DAYS FOLLOWING COMPLETION OF THE CONSTRUCTION OR DEVELOPMENT.
 - CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL EROSION CONTROL MEASURES SHOWN AND ANY ADDITIONAL MEASURES REQUIRED TO CONTROL THE SEDIMENT DURING THE COURSE OF CONSTRUCTION.
 - ALL SEEDING AREAS WILL BE FERTILIZED, RESEED AS NECESSARY, AND MULCHED ACCORDING TO THE DETAILS HEREIN.
 - THE CONTACT PERSON FOR EROSION CONTROL ISSUES THAT ARISE ON THIS SITE IS KIRBY LAFORCE. CONTACT 704-608-3085.

N/F
BRUCE JOHNSON, LLC
DB 4109, PG 436



4Dsite solutions
civil engineering | land surveying
409 Chicago Drive, Suite 112, Fayetteville, NC 28506
office | 910-426-6777 fax | 910-426-5777 license number | C-2854
www.4Dsite.com

03-22-24

REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

HARPER'S MEADOW

CLIENT

TRIANGLE LAND PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE

HORIZONTAL: 1"=40'


DATE RELEASED

MARCH 22, 2024

SHEET NUMBER

C-3.0


- LEGEND:
- EPK - EXISTING IRON PIPE
 - EPK - EXISTING PK NAIL
 - ERB - EXISTING REBAR
 - COMPUTED POINT
 - N/F - NOW OR FORMERLY
 - R/W - RIGHT OF WAY
 - TOL - TOWN OF LILLINGTON
 - PROPERTY LINE
 - ADJACENT PROPERTY LINE
 - RIGHT-OF-WAY
 - SETBACK LINE
 - SANITARY SEWER LINE
 - STORM DRAINAGE
 - WATER LINE
 - UNDERGROUND TELEPHONE LINE
 - OVERHEAD UTILITY
 - PERMANENT EASEMENT
 - TREE LINE
 - MAJOR CONTOUR
 - MINOR CONTOUR
 - SPOT ELEVATION
 - BENCHMARK
 - MAILBOX
 - LANDSCAPING LIGHT
 - UTILITY POLE
 - GUY WIRE
 - TELEPHONE PEDESTAL
 - WATER VALVE
 - FIRE HYDRANT
 - WATER METER
 - SANITARY SEWER MANHOLE
 - HARDWOOD TREE
 - SHRUB
 - RIP RAP/GRAVEL
 - ASPHALT
 - LOC - LIMITS OF CONSTRUCTION
 - SF - SILT FENCE LINE
 - JN - JUTE NETTING
 - DIV - DIVERSION BERM
 - INLET PROTECTION




WET POND #1

STORM DRAIN 9+50 TO 13+50

HORIZONTAL: 1"=40'
VERTICAL: 1"=4'




THE CONTRACTOR MUST CONTACT NORTH CAROLINA ONE CALL CENTER AT 1-800-632-4949
A MINIMUM OF 72 HOURS PRIOR TO DIGGING IN ORDER TO HAVE THE EXISTING UTILITIES LOCATED



SHALLOW WATER PLANTS		UPLANDS (ABOVE WATER SURFACE)	
COMMON NAME	BOTANICAL NAME	COMMON NAME	BOTANICAL NAME
BEAUTYBERRY	CALLICARPA AMERICANA	SWEET GRASS	MUHLENBERGIA FLIPES
RED CHOKEBERRY	ARONIA ARBUTIFOLIA	SWITCHGRASS	PANICUM VIRGATUM
VIRGINIA SWEETSPICE	ITEA VIRGINICA	RIVER OATS	CHASMANTHIUM LATIFOLIUM
SILKY DOGWOOD	CORNUS AMOMUM	LITTLE BLUESTEM	SCHIZACHYRIUM SCOPARIUM
GOLDENROD	SOLIDAGO	INDIANAGRASS	SORGHASTRUM NUTANS

- NOTES:
- PLANT SPACINGS SHALL BE A MAXIMUM OF 18 INCHES ON CENTER.
 - PLANTS CAN AND SHOULD BE MIXED MATCHED DURING THE PLANTING PROCESS.
 - SHALLOW LAND PLANTS AND SHALLOW WATER PLANTS CAN BE MIXED TOGETHER.
 - SOIL SAMPLE SHOULD BE TAKEN PRIOR TO SAMPLING AND FERTILIZE AT RECOMMENDATION FROM SOILS ANALYSIS.
 - ALL SLOPES AND AREAS ADJACENT TO THE WET POND SHALL BE SEEDED WITH BERMUDA GRASS FOR A PERMANENT GROUND COVER.
 - ALL INSTALLATIONS SHALL BE FROM A QUALIFIED PROFESSIONAL.


VEGETATED SHELF PLANTING DETAIL



- NOTES:
- THE MAXIMUM SPACING BETWEEN BARS SHALL NOT EXCEED 5.5 INCHES.
 - INSTALL A MAN ACCESS IN THE RACK FOR MAINTENANCE INSIDE THE STRUCTURE.

NTS


TRASH RACK



- SPILLWAY CROSS SECTION
- INSTALL THE EMERGENCY SPILLWAY IN UNDISTURBED SOIL. THE ACHIEVEMENT OF PLANNED ELEVATIONS, GRADE, DESIGN WIDTH, AND ENTRANCE AND EXIT CHANNEL SLOPES ARE CRITICAL TO THE SUCCESSFUL OPERATION OF THE EMERGENCY SPILLWAY.
 - ALTERNATIVE MATERIALS MAY BE USED OTHER THAN THE SPECIFIED SOD IF APPROVED BY THE DESIGN ENGINEER.
 - MAX SIDE SLOPES ARE 3:1

NTS

EMERGENCY SPILLWAY



NTS

ANTI-SEEP COLLAR


COMMON NAME	SIZE	SPACING
BEAUTYBERRY	#3 CONTAINER	48" O.C. MAXIMUM
RED CHOKEBERRY	#3 CONTAINER	48" O.C. MAXIMUM
VIRGINIA SWEETSPICE	#3 CONTAINER	36" O.C. MAXIMUM
SILKY DOGWOOD	#3 CONTAINER	60" O.C. MAXIMUM
GOLDENROD	#3 CONTAINER	48" O.C. MAXIMUM
SWEET GRASS	PLUGS	18" O.C. MAXIMUM
SWITCHGRASS	PLUGS	24" O.C. MAXIMUM
RIVER OATS	PLUGS	18" O.C. MAXIMUM
LITTLE BLUESTEM	PLUGS	18" O.C. MAXIMUM
INDIANAGRASS	PLUGS	18" O.C. MAXIMUM

PLANT SUPPLIERS:

CAROLINA GREENERY, WEST END, NC 910-947-3150
MELLOW MARSH FARM, PITTSBORO, NC 919-742-1200
PLANT DELIGHTS NURSERY, RALEIGH, NC 919-772-4794
CILL IDE NATIVE PLANT NURSERY, RALEIGH, NC 877-479-2673

**VEGETATED SHELF AND SLOPES ABOVE THE PERMANENT POOL ELEVATION SHALL HAVE A MINIMUM OF 6" TOPSOIL. SUBGRADE SHALL BE ADJUSTED TO ACCOUNT FOR ADDITION OF TOPSOIL IN THESE AREAS SUCH THAT THE ELEVATIONS SHOWN ABOVE ARE TO THE FINISHED GRADE OF THE TOPSOIL.


NTS



- NOTES:
- MIN. OUTSIDE RISER DIMENSIONS: L=4', W=32"
 - MIN. INSIDE RISER DIMENSIONS: L=3', W=22"

NTS

STORM BASIN RISER WITH ORIFICE DETAIL



FOREBAY WEIR CROSS SECTION

- ALTERNATIVE MATERIALS MAY BE USED OTHER THAN THE SPECIFIED STONE IF APPROVED BY THE DESIGN ENGINEER.
- MAX SIDE SLOPES ARE 3:1


NTS

FOREBAY WEIR



Know what's below.
Call before you dig.

GRAPHIC SCALE



REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

HARPER'S MEADOW

CLIENT

TRIANGLE LAND PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE

HORIZONTAL: 1"=40'

DATE RELEASED

MARCH 22, 2024

SHEET NUMBER

C-3.1



VICINITY MAP
NOT TO SCALE

- LEGEND:
- EP - EXISTING IRON PIPE
 - EPK - EXISTING PK NAIL
 - ERB - EXISTING REBAR
 - CP - COMPUTED POINT
 - N/F - NOW OR FORMERLY
 - R/W - RIGHT OF WAY
 - TOL - TOWN OF LILLINGTON
 - PROPERTY LINE
 - ADJACENT PROPERTY LINE
 - RIGHT-OF-WAY
 - SETBACK LINE
 - SS - SANITARY SEWER LINE
 - SD - STORM DRAINAGE
 - W - WATER LINE
 - UT - UNDERGROUND TELEPHONE LINE
 - OV - OVERHEAD UTILITY
 - PERMANENT EASEMENT
 - TREE LINE
 - 225 - MAJOR CONTOUR
 - 222 - MINOR CONTOUR
 - X 220.47 - SPOT ELEVATION
 - BENCHMARK
 - SIGN
 - MAILBOX
 - LANDSCAPING LIGHT
 - UTILITY POLE
 - GUY WIRE
 - TELEPHONE PEDESTAL
 - WATER VALVE
 - FIRE HYDRANT
 - WATER METER
 - SANITARY SEWER MANHOLE
 - HARDWOOD TREE
 - PINE TREE
 - SHRUB

- RIP RAP/GRAVEL
- ASPHALT
- BUILDINGS
- PROPOSED SANITARY SEWER MANHOLE
- PROPOSED CLEANOUT
- PROPOSED FIRE HYDRANT
- PROPOSED WATER METER
- PROPOSED TAP SLEEVE AND VALVE
- PROPOSED BLOW OFF
- PROPOSED TEE
- PROPOSED 45° BEND
- PROPOSED 22.5° BEND

*APPROVAL OF THIS PLAT/PLAN DOES NOT GUARANTEE WATER CAPACITY OR WASTEWATER CAPACITY. CURRENT/FUTURE CAPACITY MAY NOT BE AVAILABLE. THIS DEVELOPMENT MAY REQUIRE ADDITIONAL IMPROVEMENTS TO THE EXISTING WATER SYSTEM TO MEET FUTURE WATER AND WASTEWATER DEMANDS PRIOR TO A PRELIMINARY PLAT, CONSTRUCTION PLAN AND/OR FINAL PLAT APPROVAL.



**SIDEWALKS AND STREET TREES ARE TO BE MAINTAINED BY THE HOME OWNERS ASSOCIATION (HOA). PROPERTY OWNERS ASSOCIATION (POA), CONDOMINIUM OWNERS ASSOCIATION (COA), OR ANY OTHER ASSOCIATION RESPONSIBLE FOR THE MAINTENANCE AND/OR UPKEEP OF THIS RESIDENTIAL COMMUNITY. SIDEWALK OR STREET TREE INSTALLATIONS THAT ARE DAMAGED AND/OR REMOVED BY HARNETT COUNTY/DEPARTMENT OF PUBLIC UTILITIES/HARNETT REGIONAL WATER OR ITS REPRESENTATIVES, AGENTS, OR CONTRACTORS AS A RESULT OF REPAIR/MAINTENANCE OF THE PUBLIC WATER AND/OR SEWER LINE WILL BE REPLACED OR REPAIRED BY THE HOA, POA, COA, OR ANY OTHER ASSOCIATION RESPONSIBLE FOR THE MAINTENANCE AND/OR UPKEEP OF THE RESIDENTIAL COMMUNITY.

UTILITY NOTES

- THE CONTRACTOR SHALL MAINTAIN A SET OF RED LINE AS-BUILTS DURING THE CONSTRUCTION OF THE WATER LINE. ALL DEVIATIONS FROM THE PLAN SHALL BE NOTED ON THE AS-BUILT DRAWINGS. ALL VALVES AND CHANGE IN DIRECTION OF THE WATER LINE SHALL BE LOCATED WITH A MINIMUM OF TWO DISTANCES FROM A KNOWN OBJECT. THE CONTRACTOR WILL PROVIDE THE AS-BUILT DRAWINGS TO THE OWNER TO BE USED FOR THE WATER LINE CERTIFICATION AT THE COMPLETION OF THE PROJECT.
- ANY WATER ENTERING THE SANITARY SEWER SYSTEM TO BE CONSTRUCTED UNDER THE APPROVED PLANS SHALL NOT BE DISCHARGED TO THE EXISTING SEWER SYSTEM. PLUGS SHALL BE INSTALLED IN EXISTING MANHOLES AS NECESSARY TO PERMIT PUMPING THE NEW SYSTEM CLEAR OF WATER AND DEBRIS PRIOR TO ACCEPTANCE BY THE CITY. CARE SHALL BE EXERCISED IN LOCATING PLUGS TO AVOID INTERRUPTING SERVICE TO EXISTING CONNECTIONS. MECHANICAL PLUGS OR MORTAR AND BRICK MUST BE USED. INFLATABLE DEVICES ARE NOT ALLOWED.
- HORIZONTAL DIMENSIONS GIVEN FOR UNDERGROUND UTILITY TIES ARE APPROXIMATE UNLESS OTHERWISE NOTED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING ALL UTILITY COMPANIES AFFECTED BY THE PROPOSED WORK.
- THE GENERAL CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS TO COMPLETE THE PROPOSED WORK, AND SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS.
- PIPE SHALL BE LAID UPSTREAM WITH THE SPIGOT ENDS POINTING DOWNSTREAM. ALL PIPES SHALL BE PLACED TRUE TO LINE AND GRADE WITH ENDS ABUTTING CAREFULLY CENTERED, AND WITH A SMOOTH INVERT AT THE JOINT.
- LATERAL SEPARATION OF SEWERS AND WATER MAINS: WATER MAINS SHALL BE LAID AT LEAST 10 FEET LATERALLY FROM EXISTING OR PROPOSED SEWERS, UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT A 10-FOOT LATERAL SEPARATION—IN WHICH CASE:
- THE WATER MAIN IS LAID IN A SEPARATE TRENCH, WITH THE ELEVATION OF THE BOTTOM OF THE WATER MAIN AT LEAST 24 INCHES ABOVE THE TOP OF THE SEWER; OR
- THE WATER MAIN IS LAID IN THE SAME TRENCH AS THE SEWER WITH THE WATER MAIN LOCATED AT ONE SIDE ON A BENCH OF UNDISTURBED EARTH, AND WITH THE ELEVATION OF THE BOTTOM OF THE WATER MAIN AT LEAST 24 INCHES ABOVE THE TOP OF THE SEWER.

- CROSSING A WATER MAIN OVER A SEWER: WHENEVER IT IS NECESSARY FOR A WATER MAIN TO CROSS OVER A SEWER, THE WATER MAIN SHALL BE LAID AT SUCH AN ELEVATION THAT THE BOTTOM OF THE WATER MAIN IS AT LEAST 24 INCHES ABOVE THE TOP OF THE SEWER, UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT AN 24 INCH VERTICAL SEPARATION—IN WHICH CASE BOTH THE WATER MAIN AND SEWER SHALL BE CONSTRUCTED OF FERROUS MATERIALS AND WITH JOINTS THAT ARE EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING.
- CROSSING A WATER MAIN UNDER A SEWER: WHENEVER IT IS NECESSARY FOR A WATER MAIN TO CROSS UNDER A SEWER, BOTH THE WATER MAIN AND THE SEWER SHALL BE CONSTRUCTED OF FERROUS MATERIALS AND WITH JOINTS EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING. A SECTION OF WATER MAIN PIPE SHALL BE CENTERED AT THE POINT OF CROSSING.
- ALL MAINS, LATERALS AND APPURTENANCES SHALL BE TESTED IN ACCORDANCE WITH LILLINGTON PW AND NCEQ TECHNICAL SPECIFICATIONS.
- ALL MATERIALS SHALL BE APPROVED BY LILLINGTON PW BEFORE INSTALLATION.
- THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF RECORD AND LILLINGTON PW A MINIMUM OF 48 HOURS BEFORE CONSTRUCTION OF THE WATER LINE AND SANITARY SEWER LINE BEGINS. THE CONTRACTOR SHALL ALSO NOTIFY THE ENGINEER OF RECORD AND LILLINGTON PW 48 HOURS IN ADVANCE OF ALL TESTING.
- EXISTING UTILITIES NOT FOUND IN THE FIELD DURING SURVEY MAY REQUIRE DEMOLITION. NO UTILITIES SHALL BE LEFT IN PLACE THAT CROSS THE NEW UTILITIES RUNNING ALONG A LOT LINE. IF ADDITIONAL UTILITIES ARE FOUND, CONTACT ENGINEER PRIOR TO DEMOLITION.
- ALL ELEVATIONS ARE IN NAVD 88 DATUM.
- WATERLINES TO BE INSPECTED, OPERATED, AND MAINTAINED BY HRW.
- SEWER LINES TO BE INSPECTED, OPERATED, AND MAINTAINED BY THE TOWN OF LILLINGTON.
- SANITARY SEWER INSTALLATION TO BE PERFORMED IN ACCORDANCE WITH THE TOWN OF LILLINGTON DETAILED "SANITARY SEWER SPECIFICATIONS".
- SEWER CLEANOUTS GREATER THAN 6 FT IN DEPTH TO SATISFY UTILITY SEPARATION REQUIREMENTS PER TOL STANDARDS. WHERE POSSIBLE, DEEP SEWER LATERALS TO BE INSTALLED PER DETAIL S-4.1 (SEE SHEET C-6.8).

N/F
BRUCE JOHNSON, LLC
DB 4109, PG 436



THE CONTRACTOR MUST CONTACT NORTH CAROLINA ONE CALL CENTER AT 1-800-632-4949 A MINIMUM OF 72 HOURS PRIOR TO DIGGING IN ORDER TO HAVE THE EXISTING UTILITIES LOCATED

4Dsite solutions
civil engineering / land surveying
409 Chicago Drive, Suite 112, Fayetteville, NC 28406
office | 910-426-6777 fax | 910-426-5777 license number | C-2354
www.4Dsite.com

08-29-24

REVISIONS

ISSUED FOR CONSTRUCTION

08-29-24 ADDED MH-7A

PROJECT NAME

HARPER'S MEADOW

PIN:

0651-90-8197.000

CLIENT

TRIANGLE LAND PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE


HORIZONTAL: 1"=40'

DATE RELEASED

MARCH 22, 2024

SHEET NUMBER

C-4.0



4Dsite solutions
civil engineering / land surveying
409 Chicago Drive, Suite 112, Fayetteville, NC 28406
office: 910-426-6777 fax: 910-426-5777 license number: C-2354
www.4Dsite.com

SEA 027452
ENGINEER
COTT BROWN
03-22-24

REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

HARPER'S MEADOW

PIN:

0651-90-8197.000

CLIENT

TRIANGLE LAND PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE

HORIZONTAL: 1"=40'

DATE RELEASED

MARCH 22, 2024

SHEET NUMBER

C-4.0



REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

HARPER'S MEADOW

STORM & SEWER STRUCTURE DATA

CLIENT

TRIANGLE LAND PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE

HORIZONTAL: 1"=40'

DATE RELEASED

MARCH 22, 2024

SHEET NUMBER


C-4.1

SEWER STRUCTURE TABLE					
STRUCTURE	DIA	RIM EL	STRUCTURE IN	INVERT IN	INV OUT
MH-1	4'	224.46			214.50
MH-2	4'	220.97	MH-1	212.40	212.30
MH-3	4'	218.95	MH-2 LOT 51	210.05 210.70	209.95
MH-4	4'	219.11	MH-3 LOT 47 & 48	209.60 210.25	209.50
MH-5	4'	219.78	MH-4	209.20	209.10
MH-6	5'	221.08	MH-5 MH-12	208.65 208.65	208.55
MH-7	4'	217.96	MH-6 LOT 42	206.85 207.50	206.75
MH-8	8"	217.89	MH-7	206.40	
MH-9	4'	224.33			214.35
MH-10	4'	222.85	LOT 74	216.15	215.40
MH-11	4'	223.40	MH-9 MH-10	211.90 211.90	211.80
MH-12	4'	219.63	MH-11	210.50	210.40

SEWER PIPE TABLE						
UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	SIZE	LENGTH	SLOPE	UPSTREAM INVERT	DOWNSTREAM INVERT
MH-1	MH-2	8"	317.74	0.66%	214.50	212.40
MH-2	MH-3	8"	232.79	0.97%	212.30	210.05
MH-3	MH-4	8"	55.18	0.63%	209.95	209.60
MH-4	MH-5	8"	48.65	0.62%	209.50	209.20
MH-5	MH-6	8"	85.20	0.53%	209.10	208.65
MH-6	MH-7	8"	334.36	0.51%	208.55	206.85
MH-7	MH-8	8"	62.56	0.56%	206.75	206.40
MH-9	MH-11	8"	124.00	1.98%	214.35	211.90
MH-10	MH-11	8"	72.89	4.80%	215.40	211.90
MH-11	MH-12	8"	252.50	0.51%	211.80	210.50
MH-12	MH-6	8"	252.50	0.69%	210.40	208.65


STORM STRUCTURE TABLE				
STRUCTURE	TOP EL	STRUCTURE IN	INVERT IN	INV OUT
CI-3	223.51	CI-5 DI-4	218.29 (15") 219.29 (15")	218.04 (18")
CI-5	223.17	CI-6	218.47 (15")	218.47 (15")
CI-6	223.93	CI-7	219.03 (15")	219.03 (15")
CI-7	223.86			219.17 (15")
CI-9	220.96	OT-8	216.81 (24")	215.01 (30")
CI-10	219.80	CI-9 CI-47	213.85 (30") 215.15 (15")	213.85 (30")
CI-11	219.64	CI-10 CI-16 DI-44	213.58 (30") 214.58 (18") 216.03 (15")	213.58 (30")
CI-12	220.03	CI-11	213.30 (30")	213.30 (30")
CI-13	220.91	CI-12	212.15 (30")	212.00 (30")
CI-16	219.64	DI-15	214.97 (15")	214.72 (18")
CI-17	222.59	CI-35	217.42 (18")	217.42 (18")
CI-18	221.32	CI-45 CI-25	216.23 (18") 216.48 (15")	215.73 (24")
CI-19	220.04	CI-46	214.59 (24")	214.59 (24")
CI-20	219.29	CI-19	213.84 (24")	213.84 (24")
CI-21	219.24	CI-20 CI-27	213.61 (24") 214.36 (15")	213.61 (24")
CI-22	219.42	CI-21	213.39 (24")	212.99 (30")
CI-23	219.89	CI-22	212.78 (30")	212.68 (30")
CI-25	221.32			216.62 (15")
CI-26	219.29			214.59 (15")
CI-27	219.23	CI-26	214.50 (15")	214.50 (15")
CI-28	218.16			213.46 (15")
CI-29	218.16	CI-28	213.33 (15")	213.33 (15")
CI-30	219.28	CI-29 CI-49	212.78 (15") 214.68 (15")	212.78 (15")
CI-32	218.66			213.90 (18")
CI-33	218.66	CI-32 CI-30	213.75 (18") 212.45 (15")	212.20 (18")
CI-35	223.49	CI-3	217.89 (18")	217.89 (18")
CI-40	224.79	JB-39 JB-52	218.16 (30") 219.66 (15")	217.80 (36")
CI-45	222.00	CI-17	216.86 (18")	216.86 (18")
CI-46	220.72	CI-18	215.20 (24")	215.20 (24")
CI-47	219.80			215.30 (15")
CI-48	220.91	CI-13	211.85 (30")	211.50 (36")
CI-49	220.04			215.24 (15")
DI-4	222.23			219.85 (15")
DI-15	219.70			215.25 (15")
DI-44	218.80			216.20 (15")
FES-14	214.62	CI-48	211.20 (36")	
FES-24	214.88	CI-23	212.00 (30")	
FES-34	213.44	CI-33	211.65 (18")	
FES-37	214.28	RI-36	211.40 (30")	
FES-41	221.02	CI-40	217.60 (36")	
JB-39	223.98	PO-38	219.40 (30")	218.02 (30")
OT-8	221.65			217.90 (24")
RI-36	216.65			212.50 (30")

STORM PIPE TABLE						
UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	SIZE	LENGTH	SLOPE	UPSTREAM INVERT	DOWNSTREAM INVERT
		15"	12.70'	3.15%	223.70	223.30
CI-3	CI-35	18"	28.76'	0.52%	218.04	217.89
CI-5	CI-3	15"	34.56'	0.51%	218.47	218.29
CI-6	CI-5	15"	101.54'	0.55%	219.03	218.47
CI-7	CI-6	15"	26.90'	0.52%	219.17	219.03
CI-9	CI-10	30"	85.50'	1.36%	215.01	213.85
CI-10	CI-11	30"	34.50'	0.77%	213.85	213.58
CI-11	CI-12	30"	54.50'	0.51%	213.58	213.30
CI-12	CI-13	30"	225.50'	0.51%	213.30	212.15
CI-13	CI-48	30"	26.50'	0.57%	212.00	211.85
CI-16	CI-11	18"	26.50'	0.53%	214.72	214.58
CI-17	CI-45	18"	65.10'	0.85%	217.42	216.86
CI-18	CI-46	24"	65.50'	0.81%	215.73	215.20
CI-19	CI-20	24"	85.17"	0.88%	214.59	213.84
CI-20	CI-21	24"	24.94'	0.93%	213.84	213.61
CI-21	CI-22	24"	43.68'	0.50%	213.61	213.39
CI-22	CI-23	30"	41.55'	0.51%	212.99	212.78
CI-23	FES-24	30"	77.00'	0.88%	212.68	212.00
CI-25	CI-18	15"	26.50'	0.53%	216.62	216.48
CI-26	CI-27	15"	17.45'	0.53%	214.59	214.50
CI-27	CI-21	15"	26.50'	0.53%	214.50	214.36
CI-28	CI-29	15"	26.50'	0.50%	213.46	213.33
CI-29	CI-30	15"	110.00'	0.50%	213.33	212.78
CI-30	CI-33	15"	68.81'	0.48%	212.78	212.45
CI-32	CI-33	18"	22.50'	0.67%	213.90	213.75
CI-33	FES-34	18"	106.00'	0.52%	212.20	211.65
CI-35	CI-17	18"	94.90'	0.50%	217.89	217.42
CI-40	FES-41	36"	44.00'	0.45%	217.80	217.60
CI-45	CI-18	18"	74.50'	0.85%	216.86	216.23
CI-46	CI-19	24"	74.50'	0.81%	215.20	214.59
CI-47	CI-10	15"	26.50'	0.57%	215.30	215.15
CI-48	FES-14	36"	60.00'	0.50%	211.50	211.20
CI-49	CI-30	15"	74.50'	0.75%	215.24	214.68
CI-50	CI-53	15"	72.29'	0.82%	221.76	221.16
CI-51	JB-52	15"	44.00'	0.50%	220.57	220.35
CI-53	CI-51	15"	72.29'	0.82%	221.16	220.57
DI-4	CI-3	15"	28.19'	1.99%	219.85	219.29
DI-15	CI-16	15"	50.29'	0.56%	215.25	214.97
DI-44	CI-11	15"	16.75'	1.01%	216.20	216.03
JB-39	CI-40	30"	41.74'	-0.34%	218.02	218.16
JB-52	CI-40	15"	138.61'	0.50%	220.35	219.66
OT-8	CI-9	24"	111.75'	0.97%	217.90	216.81
PO-38	JB-39	30"	5.00'	2.00%	219.50	219.40
RI-36	FES-37	30"	56.61'	1.94%	212.50	211.40



HARPERS MEADOW STREET

50' R/W (PUBLIC STREET)
ROADWAY PROFILE 9+50 TO 18+50



GRAPHIC SCALE



(IN FEET)
1 inch = 40 ft.



REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

HARPER'S
MEADOW

ROSE LANDING
STREET PROFILE

CLIENT

TRIANGLE LAND
PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE


HORIZONTAL: 1"=40'
VERTICAL: 1"=4'

DATE RELEASED

MARCH 22, 2024


SHEET NUMBER

C-5.1




ROSE LANDING STREET

50' R/W (PUBLIC STREET)
ROADWAY PROFILE 9+50 TO 19+00



- EXISTING GRADE
FINISHED GRADE
- 4" CO STORM CROSSING
4" CO WATER CROSSING
- NOTE:
- ALL STORM PIPE BELOW THE 10-YR STORM HIGH WATER ELEVATION SHALL HAVE RUBBER GASKET JOINTS THAT CONFORM TO ASTM C 443.
 - 30" MINIMUM COVER FROM STREET SUB-GRADE TO TOP OF WATER LINE. 36" MINIMUM COVER ALL OTHER AREAS.
 - ALL STORM PIPE TO BE CLASS III RCP UNLESS OTHERWISE NOTED.





REVISIONS
ISSUED FOR CONSTRUCTION

PROJECT NAME

**HARPER'S
MEADOW**

**BRAYDENS WAY
& STORM
PROFILES**

CLIENT

**TRIANGLE LAND
PARTNERS, LLC**

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE


HORIZONTAL: 1"=40'
VERTICAL: 1"=4'

DATE RELEASED

MARCH 22, 2024


SHEET NUMBER

C-5.2




BRAYDENS WAY

50' R/W (PUBLIC STREET)
ROADWAY PROFILE 9+50 TO 13+00







ROAD STUB

50' R/W (PUBLIC STREET)
ROADWAY PROFILE 9+50 TO 11+00




WET POND #1

STORM DRAIN 9+50 TO 13+50





I:\Triangle Land Partners\1896\Harper's Meadow\DWG\SDW\1896-Harper's Meadow-C-5.3.DWG • C-5.3.DWG • 12/28/22 2:52:27 PM





DI-4 TO CI-5

STORM DRAIN 9+50 TO 11+00





OT-8 TO CI-9

STORM DRAIN 9+50 TO 11+50





DI-15 TO CI-16

STORM DRAIN 9+50 TO 11+00



CI-13 TO FES-14

STORM DRAIN 9+50 TO 11+00



REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

**HARPER'S
MEADOW**

STORM PROFILE

CLIENT

**TRIANGLE LAND
PARTNERS, LLC**

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE

HORIZONTAL: 1"=40'
VERTICAL: 1"=4'

DATE RELEASED

MARCH 22, 2024

SHEET NUMBER

C-5.3



REVISIONS

ISSUED FOR CONSTRUCTION

08-29-24 ADDED MH-7A

PROJECT NAME

**HARPER'S
MEADOW**

**STORM &
SEWER
PROFILES**

CLIENT

**TRIANGLE LAND
PARTNERS, LLC**

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE


HORIZONTAL: 1"=40'
VERTICAL: 1"=4'

DATE RELEASED

MARCH 22, 2024



SHEET NUMBER

C-5.4




CI-33 TO FES-34

STORM DRAIN 9+50 TO 11+00





CI-23 TO FES-24

STORM DRAIN 9+50 TO 11+00





PO-38 TO FES-41

STORM DRAIN 9+50 TO 11+50





DI-44 TO CI-11

STORM DRAIN 9+50 TO 10+50



MH-7 TO MH-8

SANITARY SEWER 9+50 TO 11+00





REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

HARPER'S
MEADOW

NORTH MAIN
STREET - NC
HWY 210
PROFILE

CLIENT

TRIANGLE LAND
PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE


HORIZONTAL: 1"=40'
VERTICAL: 1"=4'

DATE RELEASED

MARCH 22, 2024



SHEET NUMBER

C-5.5



NORTH MAIN STREET - NC HWY 210 WIDENING

60' R/W (PUBLIC STREET)
ROADWAY PROFILE 11+50 TO 22+50





REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

**HARPER'S
MEADOW**

SITE DETAILS

CLIENT

**TRIANGLE LAND
PARTNERS, LLC**

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE

NOT TO SCALE


DATE RELEASED

MARCH 22, 2024

SHEET NUMBER

C-6.0


*STREET TREES TO BE
SPACED 30 FT O.C.
EXCLUDING DRIVEWAYS &
TRAFFIC VISIBILITY ZONES




NOTES

- SECTION SHOWN TO DEPICT TYPICAL CUT & FILL CONDITIONS ONLY. GRADING PLAN SHOWS WHETHER SECTION IS IN CUT, FILL OR BOTH.
- A 5' SIDEWALK IS REQUIRED ON BOTH SIDE OF EACH STREET. SEE PLANS FOR LOCATION OF SIDEWALK.
- SIDEWALK SHALL HAVE A MAXIMUM CROSS-SLOPE OF 2% FROM BACK EDGE OF SIDEWALK TOWARD BACK OF CURB.

NTS




NTS



CURB AND GUTTER TO BE POURED
IN 10' SECTIONS WITH EXPANSION
JOINTS EVERY 50'
(90' IF MACHINE PLACED)

NTS

1 ROADWAY TYPICAL SECTION




NTS

4 ASPHALT PAVEMENT

- 0.33% (12:1) MAX RAMP SLOPE
- CURB RAMP REQUIRE A (4'-0") MINIMUM LANDING WITH A MAXIMUM CROSS SLOPE AND LONGITUDINAL SLOPE OF 2.00% WHERE PEDESTRIANS PERFORM TURNING MANEUVERS. SLOPE TO DRAIN TO CURB.


PAY LIMITS FOR 1 CURB RAMP



TYPE 1

NTS

7 TYPE 1 CURB RAMP



NOTES

- THE MAXIMUM SPACING BETWEEN BARS SHALL NOT EXCEED 5.5 INCHES.
- INSTALL A WALK ACCESS IN THE RACK FOR MAINTENANCE INSIDE THE STRUCTURE.

NTS



11 TRASH RACK

ACCESSIBLE PARKING REQUIREMENTS		
TOTAL PARKING SPACES PROVIDED	MINIMUM NUMBER OF ACCESSIBLE SPACES REQUIRED	MINIMUM NUMBER OF ACCESSIBLE SPACES REQUIRED TO BE VAN ACCESSIBLE
1 TO 25	1	1
26 TO 50	2	1
51 TO 75	3	1
76 TO 100	4	1
101 TO 150	5	1
151 TO 200	6	1
201 TO 300	7	1
301 TO 400	8	1
401 TO 500	9	2
501 TO 1000	2% OF TOTAL	1 IN EVERY 8 ACCESSIBLE SPACES
1001 AND OVER	20 PLUS 1 FOR EACH 100 OVER 1000	1 IN EVERY 8 ACCESSIBLE SPACES

SECTION 4.1.2 (3) OF THE AMERICANS WITH DISABILITIES ACT (ADA). SEE 4.1.2 (3) (5) FOR MEDICAL CARE FACILITIES.

NOTES:

- ALL 12'x18' ACCESSIBLE SPACES (R7-B & R7-1) SHALL BE MOUNTED AT 7 FEET FROM GRADE TO BOTTOM EDGE OF SIGN PANEL (MUTCD). MOUNTING HEIGHT CAN BE REDUCED TO 5 FEET IF PLACED IN AN AREA BETWEEN SIDEWALK AND BUILDING FACE IN WHICH PEDESTRIANS ARE NOT EXPECTED TO USE.
- REFER TO MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (MUTCD) U.S. DEPARTMENT OF TRANSPORTATION AND NORTH CAROLINA DEPARTMENT OF TRANSPORTATION SIGNAGE.
- IF ACCESSIBLE ROUTE IS A RAISED SIDEWALK AREA, THEN RAMP ARE REQUIRED AT LOADING ZONE AREA.
- ALL DIMENSIONS, PAVEMENT MARKINGS AND SIGNAGE SHALL COMPLY WITH CURRENT ADA REQUIREMENTS.




ACCESSIBLE ROUTE
(SEE NOTE 3)

ONE OUT OF EVERY EIGHT (8) ACCESSIBLE SPACES, BUT NOT LESS THAN ONE, IS REQUIRED TO BE VAN ACCESSIBLE.

PARKING SPACE PAVEMENT MARKINGS

NTS

5 HANDICAP SIGNAGE AND PAVEMENT MARKINGS




NOTE:

- PROVIDE CONTROL JOINTS AT DISTANCE EQUAL TO WIDTH OF SIDEWALK, PROVIDE 1/2" EXP. JOINTS WITH PRE-MOLDED E.J. FILLER AT MAX. 30' O.C.
- CONCRETE COMPRESSIVE STRENGTH SHALL BE 3000 PSI. IN 28 DAYS.

NTS

8 SIDEWALK WITH CURB




NOTES

- MIN. OUTSIDE Riser DIMENSIONS: L=4', W=3'2" MIN. INSIDE Riser DIMENSIONS: L=3', W=2'2"

NTS

12 STORM BASIN RISER WITH ORIFICE DETAIL


9 SHRUB PLANTING



NTS

13 REDUCED LENGTH CURB TRANSITION

10 TREE PLANTING



ROAD WIDENING NOTES:

- ALL PAVEMENT MARKINGS SHALL BE IN ACCORDANCE WITH POLICY ON STREET AND DRIVEWAY ACCESS TO NORTH CAROLINA HIGHWAY MANUAL AND NCDOT STANDARD DRAWING 1205.04 AND 1205.05.
- CONTRACTOR SHALL COORDINATE ALL ROAD WIDENING AND PAVEMENT MARKINGS WITH THE NCDOT DISTRICT OFFICE PRIOR TO CONSTRUCTION. CONTACT INFORMATION: FRANK WEST (910) 364-0606
- CONTRACTOR IS RESPONSIBLE FOR ALL TRAFFIC CONTROL DURING THE ROAD WIDENING OPERATIONS.
- CONTRACTOR SHALL NOTIFY ALL PROPERTY OWNERS THAT ARE AFFECTED BY THE ROAD WIDENING INCLUDING BUT NOT LIMITED TO DRIVEWAY REPAIR.
- CONTRACTOR IS RESPONSIBLE FOR RELOCATING ALL UTILITIES AND INFRASTRUCTURE AFFECTED BY THE WIDENING TO INCLUDE BUT NOT LIMITED TO SIGNS, MAILBOXES, POWER POLES, ETC. CONTRACTOR SHALL REPAIR ANY DAMAGE TO EXISTING PROPERTY RESULTING FROM CONSTRUCTION OF THE IMPROVEMENTS.

NTS

14 PAVEMENT WIDENING SECTION

I:\Projects\Land\Permit\1086\1086-Design\1086-Design.dwg, 25/04/2024 2:22:07 PM, PLOT: 1, 25/04/2024 2:22:07 PM

TEMPORARY SEEDING/MULCHING SPECIFICATIONS (FOR LATE WINTER AND EARLY SPRING)
SEEDING MIXTURE:
SPECIES **RATE (LB./ACRE)**
RYE (GRAIN) 120
ANNUAL KOBE LESPEDEZA 50
OMIT ANNUAL LESPEDEZA WHEN DURATION OF TEMPORARY COVER IS NOT EXTEND BEYOND JUNE.

SEEDING DATES:
JANUARY 1 - MAY 1

SOIL AMENDMENTS:
FOLLOW RECOMMENDATIONS OF SOIL TESTS OR APPLY 2,000 LB./ACRE GROUND AGRICULTURAL LIMESTONE AND 750 LB./ACRE 10-10-10 FERTILIZER.

MULCH:
APPLY 4,000 LB./ACRE STRAW, ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.

MAINTENANCE:
REFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED, REFERTILIZE AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE.

TEMPORARY SEEDING/MULCHING SPECIFICATIONS (FOR SUMMER)
SEEDING MIXTURE:
SPECIES **RATE (LB./ACRE)**

GERMAN MILLET 40

A SMALL-STEMMED SUDAGRASS MAY BE SUBSTITUTED AT A RATE OF 50 LB./ACRE.

SEEDING DATES:
MAY 1 - AUGUST 15

SOIL AMENDMENTS:
FOLLOW RECOMMENDATIONS OF SOIL TESTS OR APPLY 2,000 LB./ACRE GROUND AGRICULTURAL LIMESTONE AND 750 LB./ACRE 10-10-10 FERTILIZER.

MULCH:
APPLY 4,000 LB./ACRE STRAW, ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.

MAINTENANCE:
REFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED, REFERTILIZE AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE.

TEMPORARY SEEDING/MULCHING SPECIFICATIONS (FOR FALL)

SEEDING MIXTURE:
SPECIES **RATE (LB./ACRE)**

RYE (GRAIN) 120


SEEDING DATES:
AUGUST 15 - DECEMBER 30

SOIL AMENDMENTS:
FOLLOW RECOMMENDATIONS OF SOIL TESTS OR APPLY 2,000 LB./ACRE GROUND AGRICULTURAL LIMESTONE AND 1,000 LB./ACRE 10-10-10 FERTILIZER.


MULCH:
APPLY 4,000 LB./ACRE STRAW, ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.

MAINTENANCE:
REPAIR AND REFERTILIZE DAMAGED AREAS IMMEDIATELY. TOP DRESS WITH 50 LB./ACRE OF NITROGEN IN MARCH. IF IT IS NECESSARY TO EXTEND TEMPORARY COVER BEYOND JUNE 15, OVERSEED WITH 50 LB./ACRE KOBE LESPEDEZA IN LATE OR EARLY MARCH.


1 TEMPORARY SEEDING SPECIFICATIONS



NTS




2 PERMANENT SEEDING SPECIFICATIONS



NTS


POROUS BAFFLES



NTS


- UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL, EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE MINIMUM STANDARDS AND SPECIFICATIONS OF THE NORTH CAROLINA EROSION AND SEDIMENT CONTROL HANDBOOK.
- THE CONTRACTOR SHALL NOTIFY PLAN APPROVING AUTHORITY ONE WEEK PRIOR TO THE PRECONSTRUCTION CONFERENCE. ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO FINAL INSPECTION.
- IF POSSIBLE ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO CLEARING AND/OR LAND DISTURBANCE.
- A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN AND PERMIT SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS, STAGING OR STORAGE AREAS), THE CONTRACTOR SHALL PREPARE AND SUBMIT A SUPPLEMENTARY EROSION CONTROL PLAN TO THE OWNER FOR REVIEW AND TO NCDEM REGIONAL OFFICE FOR APPROVAL. THE CONTRACTOR SHALL PAY ALL FEES REQUIRED AND SHALL INSTALL NECESSARY MEASURES AT NO SEPARATE PAYMENT. THE CONTRACTOR SHALL PROVIDE THE OWNER AND THE ENGINEER A COPY OF THE AMENDED PERMIT.
- THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY EITHER NCDEM OR THE ENGINEER.
- ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.
- ALL AREAS DISTURBED BY CONSTRUCTION UNLESS OTHERWISE IMPROVED SHALL BE SOODED OR SEEDED AS INDICATED AND STABILIZED.
- DURING DEWATERING OPERATIONS, WATER SHALL BE PUMPED INTO AN APPROVED FILTERING DEVICE PRIOR TO DISCHARGE TO RECEIVING OUTLET.
- THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES WEEKLY AND AFTER EACH RUNOFF-PRODUCING EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.
- ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED BY CONTRACTOR ONCE STABILIZATION OR A SUFFICIENT GROUND COVER HAS BEEN ESTABLISHED OR AS DIRECTED BY THE ENGINEER. NCDEM'S FINAL APPROVAL IS REQUIRED.
- TEMPORARY GRAVEL CONSTRUCTION ENTRANCE SHALL BE REQUIRED AT ALL CONSTRUCTION STAGING AREA ENTRANCES AND ALL CONSTRUCTION ACCESS LOCATIONS INTO NON-PAVED AREA.
- WHEN CROSSING CREEK OR DRAINAGE WAY, THE CONTRACTOR SHALL RIP-RAP WITH FABRIC DISTURBED BANKS AND CHANNEL, AND RESTORE SLOPES TO ORIGINAL CONTOURS, BUT NOT STEEPER THAN 2:1 MAXIMUM. DISTURBED CREEK AREA SHALL BE STABILIZED IMMEDIATELY.

3 GENERAL EROSION AND SEDIMENT CONTROL NOTES




NTS

5 TEMPORARY DIVERSION BERM



NTS


POROUS BAFFLES



NTS


10 ANTI-SEEP COLLAR

NTS




NTS

4 TEMPORARY GRAVEL CONSTRUCTION ENTRANCE



NTS

6 HARDWARE CLOTH & GRAVEL INLET PROTECTION



11 TYPICAL RIP RAP APRON

NTS

4Dsite solutions
civil engineering | land surveying
409 Chicago Drive, Suite 112, Fayetteville, NC 28306
office | 910-426-6777 fax | 910-426-5777 license number | C-2354
www.4Dsite.com

REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

HARPER'S MEADOW

NTS

EROSION CONTROL DETAILS

CLIENT

TRIANGLE LAND PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE

NOT TO SCALE

DATE RELEASED

MARCH 22, 2024

SHEET NUMBER

NTS

C-6.1

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION		
Required Ground Stabilization Timeframes		
Site Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a) Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b) High Quality Water (HQW) Zones	7	None
(c) Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d) Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope
(e) Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION	
Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:	
Temporary Stabilization	Permanent Stabilization
- Temporary grass seed covered with straw or other mulches and tackifiers - Hydroseeding - Rollled erosion control products with or without temporary grass seed - Appropriately applied straw or other mulch - Plastic sheeting	- Permanent grass seed covered with straw or other mulches and tackifiers - Geotextile fabrics such as permanent soil reinforcement matting - Hydroseeding - Shrubs or other permanent plantings covered with mulch - Uniform and evenly distributed ground cover sufficient to restrain erosion - Structural methods such as concrete, asphalt or retaining walls - Rollled erosion control products with grass seed

- POLYACRYLAMIDES (PAMS) AND FLOCCULANTS**
- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the *NC DWR List of Approved PAMS/Flocculants*.
 - Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
 - Apply flocculants at the concentrations specified in the *NC DWR List of Approved PAMS/Flocculants* and in accordance with the manufacturer's instructions.
 - Provide ponding area for containment of treated Stormwater before discharging offsite.
 - Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.


- EQUIPMENT AND VEHICLE MAINTENANCE**
- Maintain vehicles and equipment to prevent discharge of fluids.
 - Provide drip pans under any stored equipment.
 - Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
 - Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
 - Remove leaking vehicles and construction equipment from service until the problem has been corrected.
 - Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

- LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE**
- Never bury or burn waste. Place litter and debris in approved waste containers.
 - Provide a sufficient number and size of waste containers (e.g. dumpster, trash receptacle) on site to contain construction and domestic wastes.
 - Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
 - Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
 - Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
 - Anchor all lightweight items in waste containers during times of high winds.
 - Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
 - Dispose waste off-site at an approved disposal facility.
 - On business days, clean up and dispose of waste in designated waste containers.

- PAINT AND OTHER LIQUID WASTE**
- Do not dump paint and other liquid waste into storm drains, streams or wetlands.
 - Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
 - Contain liquid wastes in a controlled area.
 - Containment must be labeled, sized and placed appropriately for the needs of site.
 - Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

- PORTABLE TOILETS**
- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
 - Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
 - Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

- EARTHEN STOCKPILE MANAGEMENT**
- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
 - Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
 - Provide stable stone access point when feasible.
 - Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plans and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.



- CONCRETE WASHOUTS**
- Do not discharge concrete or cement slurry from the site.
 - Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
 - Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
 - Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
 - Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
 - Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
 - Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
 - Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
 - Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
 - At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

- HERBICIDES, PESTICIDES AND RODENTICIDES**
- Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
 - Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
 - Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
 - Do not stockpile these materials on-site.

- HAZARDOUS AND TOXIC WASTE**
- Create designated hazardous waste collection areas on-site.
 - Place hazardous waste containers under secondary containment.
 - Do not store hazardous chemicals, drums or bagged materials directly on the ground.

Outdoor Lighting

Mitchell LED Series

Mitchell LED
Mitchell Top Hat LED
Mitchell LED with ribs, bands and medallions
Mitchell Open LED
Mitchell Top Hat LED with ribs, bands and medallions

The energy-efficient fixtures in the Mitchell LED Series enhance the character and prestige of streetscapes and parking lots, as well as pedestrian areas and greenways. These fixtures provide safety and security in commercial settings and complement any neighborhood with their classic, elegant design.

LED (Light Emitting Diode)	50 watts, 75 watts (Mitchell Open)
Mounting heights	12', 13', 16'
Color	Black
Poles	Fiberglass Smooth round concrete Style V Style VI Style VII

For additional information, visit us at duke-energy.com/OutdoorLighting or call us toll free at 866.769.6417.

©2015 Duke Energy Corporation 150282 2/15

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

EFFECTIVE: 04/01/19

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING		
SECTION A: SELF-INSPECTION		
Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.		
Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hour	1. Identification of the measures inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Indication of whether the measures were operating properly, 5. Description of maintenance needs for the measure, 6. Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDOs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the discharge outfalls inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 5. Indication of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit of this permit.
(6) Ground stabilization measures	After each phase of grading	1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land disturbing activity, construction or redevelopment, permanent ground cover). 2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.



NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/19

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING	
SECTION B: RECORDKEEPING	
1. E&SC Plan Documentation The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be documented in the manner described:	
Item to Document	Documentation Requirements
(a) Each E&SC Measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC Plan.	Initial and date each E&SC Measure on a copy of the approved E&SC Plan or complete, date and sign an inspection report that lists each E&SC Measure shown on the approved E&SC Plan. This documentation is required upon the initial installation of the E&SC Measures or if the E&SC Measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC Plan.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&SC Measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&SC Measures.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

2. Additional Documentation
In addition to the E&SC Plan documents above, the following items shall be kept on the site and available for agency inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

- This general permit as well as the certificate of coverage, after it is received.
- Records of inspections made during the previous 30 days. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.
- All data used to complete the Notice of Intent and other inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING	
SECTION C: REPORTING	
1. Occurrences that must be reported Permittees shall report the following occurrences: (a) Visible sediment deposition in a stream or wetland. (b) Oil spills if: - They are 25 gallons or more, - They are less than 25 gallons but cannot be cleaned up within 24 hours, - They cause sheen on surface waters (regardless of volume), or - They are within 100 feet of surface waters (regardless of volume). (c) Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85. (d) Anticipated bypasses and unanticipated bypasses. (e) Noncompliance with the conditions of this permit that may endanger health or the environment.	
2. Reporting Timeframes and Other Requirements After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Division's Emergency Response personnel at (800) 662-7956, (800) 858-0368 or (919) 733-3300.	
Occurrence	Reporting Timeframes (After Discovery) and Other Requirements
(a) Visible sediment deposition in a stream or wetland	Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. - If the stream is named on the NC 303(d) list as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired waters conditions. Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.
(b) Oil spills and release of hazardous substances per Item 1(b)(1) above	A report at least ten days before the date of the bypass, if possible. The report shall include an evaluation of the anticipated quality and effect of the bypass. Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass. Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(i)(6)]. - Division staff may waive the requirement for a written report on a case-by-case basis.
(c) Anticipated bypasses [40 CFR 122.41(m)(3)]	
(d) Unanticipated bypasses [40 CFR 122.41(m)(3)]	
(e) Noncompliance with the conditions of this permit that may endanger health or the environment [40 CFR 122.41(i)(7)]	

Outdoor Lighting

Mitchell LED Series

Light source: LED (white)
Lumens: 4,332 – 5,678 (fixture dependent)
Color temperature: 4,000K

	Wattage	Light Pattern	IESNA Backlight – Uplight – Glare (BUG) Rating
Mitchell LED	50	IESNA Type V	B3-U4-G3
Mitchell Top Hat LED	50	IESNA Type V	B3-U3-G3
Mitchell Open LED	75	IESNA Type III	B1-U0-G1
Mitchell LED with Ribs, Bands and Medallions	50	IESNA Type V	B3-U4-G3
Mitchell Top Hat LED with Ribs, Bands and Medallions	50	IESNA Type V	B3-G3-U3

Poles available:

Name	Mounting height	Color
Smooth concrete	12', 16'	Black
Fiberglass	16'	Black
Style V	12', 16'	Black
Style VI	12'	Black
Style VII	13'	Black

©2015 Duke Energy Corporation 151307 7/15



REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

HARPER'S MEADOW

SITE & EROSION CONTROL DETAILS

CLIENT

TRIANGLE LAND PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE


NOT TO SCALE

DATE RELEASED

MARCH 22, 2024

SHEET NUMBER


C-6.3



STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR
 CONCRETE CATCH BASIN
 12" THRU 54" PIPE


SHEET 1 OF 2
 840.02



STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR
 FRAME, GRATES, AND HOOD
 FOR USE ON STANDARD CATCH BASIN


SHEET 1 OF 2
 840.03



STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR
 CONCRETE DROP INLET
 12" THRU 30" PIPE


SHEET 1 OF 1
 840.14



STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR
 CONCRETE CATCH BASIN
 12" THRU 54" PIPE


SHEET 2 OF 2
 840.02



STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR
 FRAME, GRATES, AND HOOD
 FOR USE ON STANDARD CATCH BASIN

SHEET 2 OF 2
 840.03



STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR
 DROP INLET FRAME AND GRATES
 FOR USE WITH STD. DWG. S 840.14 AND 840.15

SHEET 1 OF 1
 840.16



REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

HARPER'S MEADOW

STORM DETAILS

CLIENT

TRIANGLE LAND PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE

NOT TO SCALE

DATE RELEASED

MARCH 22, 2024

SHEET NUMBER

C-6.5

GENERAL NOTES:
CHAMFER ALL EXPOSED CORNERS 1".
USE CLASS "B" CONCRETE THROUGHOUT.
OPTIONAL CONSTRUCTION - MONOLITHIC POUR, 2" KEYWAY, OR #4 BAR DOWELS AT 12" CENTERS AS DIRECTED BY THE ENGINEER.
USE FORMS TO CONSTRUCT THE BOTTOM SLAB.
IF REINFORCED CONCRETE PIPE IS SET IN BASE SLAB OF BOX, ADD TO BASE AS SHOWN ON STANDARD NO. 840.00.
PROVIDE ALL JUNCTION BOXES OVER 3'-6" IN DEPTH WITH STEPS 12" ON CENTERS IN ACCORDANCE WITH STD. NO. 840.06.
ADJUST THE STEEL, CONCRETE AND BRICK MASONRY QUANTITIES TO INCLUDE THE ADDITION OF THE MANHOLE (I.E. DIAGONAL BARS SHORTENED AROUND OPENING IN TOP SLAB, ADDITIONAL VARIABLE HEIGHT BRICK MASONRY, OPENING IN TOP SLAB.)
MAX. DEPTH OF THIS STRUCTURE FROM TOP OF BOTTOM SLAB TO TOP ELEVATION IS 12 FEET.

DIMENSIONS AND QUANTITIES FOR CONCRETE JUNCTION BOXES

DIMENSIONS OF BOX AND PIPE				REINFORCEMENT BARS "A"		TOP SLAB DIMENSIONS		CUBIC YARDS IN BOX		TOTAL QUANTITIES BOX AND SLAB		DEDUCTIONS FOR ONE PIPE CULVERT	
PIPE	SPAN	WIDTH	HEIGHT	NO.	LENGTH	E	F	TOP SLAB	BOTTOM SLAB	WALL/ FT. OF HT.	LBS. REINF. "H"	CU. YDS. MIN.	C.S. R.C.
12"	2'-0"	2'-0"	2'-3"	12	2'-9"	3'-0"	3'-0"	0.167	0.167	0.185	22	0.750	0.015
15"	2'-3"	2'-3"	2'-6"	12	3'-0"	3'-3"	3'-3"	0.196	0.196	0.204	24	0.902	0.023
18"	2'-6"	2'-6"	2'-9"	14	3'-3"	3'-6"	3'-6"	0.227	0.227	0.222	30	1.065	0.033
24"	3'-0"	3'-0"	3'-3"	16	3'-9"	4'-0"	4'-0"	0.296	0.296	0.259	40	1.434	0.059
30"	3'-6"	3'-6"	3'-9"	18	4'-3"	4'-6"	4'-6"	0.375	0.375	0.296	51	1.860	0.092
36"	4'-0"	4'-0"	4'-3"	20	4'-9"	5'-0"	5'-0"	0.463	0.463	0.333	64	2.341	0.132
42"	4'-6"	4'-6"	4'-9"	22	5'-3"	5'-6"	5'-6"	0.560	0.560	0.370	77	2.878	0.180
48"	5'-0"	5'-0"	5'-3"	24	5'-9"	6'-0"	6'-0"	0.667	0.667	0.407	111	3.823	0.235
54"	5'-6"	5'-6"	5'-9"	26	6'-3"	6'-6"	6'-6"	0.783	0.783	0.444	128	4.283	0.297
60"	6'-0"	6'-0"	6'-3"	30	7'-3"	7'-6"	7'-6"	1.042	1.042	0.481	145	5.090	0.367
66"	7'-0"	7'-0"	7'-3"	32	7'-9"	8'-0"	8'-0"	1.210	1.210	0.518	169	5.917	0.444

ROADWAY STANDARD DRAWING FOR CONCRETE JUNCTION BOX (WITH OPTIONAL MANHOLE) 12" THRU 66" PIPE

SHEET 1 OF 1
840.31

GENERAL NOTES:
I.D. = THE MAXIMUM HORIZONTAL INSIDE DIAMETER DIMENSION.
O.D. = THE MAXIMUM HORIZONTAL OUTSIDE DIAMETER DIMENSION.
H = THE FILL HEIGHT MEASURED VERTICALLY AT ANY POINT ALONG THE PIPE FROM THE TOP OF THE PIPE TO THE TOP OF THE EMBANKMENT AT THAT POINT.
DO NOT OPERATE HEAVY EQUIPMENT OVER ANY PIPE CULVERT UNTIL THE PIPE CULVERT HAS BEEN PROPERLY BACKFILLED AND COVERED WITH AT LEAST 3 FEET OF APPROVED MATERIAL.
--- SPRINGLINE OF PIPE
SELECT BACKFILL MATERIAL CLASS III OR CLASS II, TYPE 1 ABOVE AND BELOW SPRINGLINE.
APPROVED SUITABLE LOCAL MATERIAL.
UNDISTURBED EARTH MATERIAL.
SELECT MATERIAL CLASS V OR VI FOR FOUNDATION CONDITIONING. ENCAPSULATE WITH TYPE 2 GEOTEXTILE AS DIRECTED BY THE ENGINEER.

ROADWAY STANDARD DRAWING FOR METHOD OF PIPE INSTALLATION FLEXIBLE PIPE

SHEET 1 OF 3
300.01

FLEXIBLE PIPE

Round Corrugated Steel Pipe 2 2/3 x 1/2 corrugation **					
Diameter (Inches)	Minimum cover (Inches)	Maximum Height of Cover (feet)			
		12	14	16	18
12	12	123	155	216	281
15	12	162	204	274	344
18	12	195	249	329	414
21	12	228	294	384	484
24	12	261	339	434	544
30	12	324	414	524	664
36	12	384	494	614	774
42	12	444	574	694	874
48	12	504	654	774	974
54	12	564	734	854	1074
60	12	624	814	934	1174
66	12	684	894	1014	1274
72	12	744	974	1094	1374
78	12	804	1054	1174	1474
84	12	864	1134	1254	1574

RIGID PIPE

Round Corrugated Aluminum Pipe 2 2/3 x 1/2 corrugation **					
Diameter (Inches)	Minimum cover (Inches)	Maximum Height of Cover (feet)			
		12	14	16	18
12	12	123	155	216	281
15	12	162	204	274	344
18	12	195	249	329	414
21	12	228	294	384	484
24	12	261	339	434	544
30	12	324	414	524	664
36	12	384	494	614	774
42	12	444	574	694	874
48	12	504	654	774	974
54	12	564	734	854	1074
60	12	624	814	934	1174
66	12	684	894	1014	1274
72	12	744	974	1094	1374
78	12	804	1054	1174	1474
84	12	864	1134	1254	1574

ROADWAY STANDARD DRAWING FOR METHOD OF PIPE INSTALLATION RIGID PIPE

SHEET 3 OF 3
300.01

GENERAL NOTES:
SOLID COVER SHOWN PERFORATED. PERFORATED AVAILABLE IF SPECIFIED.
STATE USE OF SYSTEM ON COVER (I.E.: SEWER, STORM DRAIN, ELECTRICAL)
TOP OF COVER
BOTTOM OF COVER
MINIMUM WEIGHTS - LBS.
FRAME - 180
COVER - 120
TOTAL - 300

ROADWAY STANDARD DRAWING FOR MANHOLE FRAME AND COVER

SHEET 1 OF 1
840.54

GENERAL NOTES:
I.D. = THE MAXIMUM HORIZONTAL INSIDE DIAMETER DIMENSION.
O.D. = THE MAXIMUM HORIZONTAL OUTSIDE DIAMETER DIMENSION.
H = THE FILL HEIGHT MEASURED VERTICALLY AT ANY POINT ALONG THE PIPE FROM THE TOP OF THE PIPE TO THE TOP OF THE EMBANKMENT AT THAT POINT.
DO NOT OPERATE HEAVY EQUIPMENT OVER ANY PIPE CULVERT UNTIL THE PIPE CULVERT HAS BEEN PROPERLY BACKFILLED AND COVERED WITH AT LEAST 3 FEET OF APPROVED MATERIAL.
--- SPRINGLINE OF PIPE
SELECT BACKFILL MATERIAL CLASS III OR CLASS II, TYPE 1 ABOVE AND BELOW SPRINGLINE.
APPROVED SUITABLE LOCAL MATERIAL ABOVE SPRINGLINE.
UNDISTURBED EARTH MATERIAL.
SELECT MATERIAL CLASS V OR VI FOR FOUNDATION CONDITIONING. ENCAPSULATE WITH TYPE 2 GEOTEXTILE AS DIRECTED BY THE ENGINEER.

ROADWAY STANDARD DRAWING FOR METHOD OF PIPE INSTALLATION RIGID PIPE


SHEET 2 OF 3
300.01

TYPE 1 OR TYPE 3 MARKERS FOR OBSTRUCTIONS WITHIN THE ROADWAY


TYPE 2 OR TYPE 3 MARKERS FOR OBSTRUCTIONS ADJACENT TO THE ROADWAY

TYPE 4 MARKERS FOR END OF ROADWAY


LEGEND
- OBJECT MARKER
- DIRECTION OF TRAFFIC FLOW



1 PERMANENT BLOW-OFF ASSEMBLY




7 METER BOX DETAIL FOR 3/4" SERVICE




9 TYPICAL 3/4" METER BOX INSTALLATION

LAYING CONDITIONS	DESCRIPTION	PROJECT USE
	FLAT BOTTOM UNDISTURBED EARTH TRENCH, LOOSE BACKFILL	NOT USED.
	FLAT BOTTOMED UNDISTURBED EARTH TRENCH, BACKFILL LIGHTLY CONSOLIDATED TO CENTERLINE OF PIPE.	NOT USED.
	PIPE BEDDED IN 4" MINIMUM JOB EXCAVATED MATERIAL, BACKFILL LIGHTLY CONSOLIDATED TO TOP OF PIPE.	ALL DUCTILE IRON GRAVITY SEWER LINE.
	PIPE BEDDED IN SAND, GRANULAR MATERIAL OR GRADED GRAVEL TO THE DEPTH OF 1/8 PIPE DIAMETER, 4" MIN. JOB EXCAVATED MATERIAL COMPACTED TO 4" ABOVE TOP OF PIPE. (APPROX. 95% STANDARD PROCTOR, AASHTO T-99)	ALL PVC WATER LINE AND PVC FORCE MAIN.
	PIPE BEDDED TO ITS CENTERLINE IN COMPACTED GRANULAR MATERIAL 4" MIN. UNDER PIPE. COMPACTED GRANULAR OR SAND MATERIAL TO 4" ABOVE TOP OF PIPE. (APPROX. 95% STANDARD PROCTOR, AASHTO T-99)	ALL PVC GRAVITY SEWER LINE.


4 TYPICAL LAYING CONDITIONS




8 TYP. TAPPING SLEEVE & VALVE ASSEMBLY




10 TYPICAL TRACER WIRE INSTALLATION




2 TYPICAL WATER SERVICE CONNECTION




5 METER BOX AMR LID




11 THRUST BLOCK DETAIL



3 TYPICAL VALVE BOX DETAIL



6 FIRE HYDRANT ASSEMBLY INSTALLATION



12 TYP. DOMESTIC WATER SERVICE DETAIL

4Dsite solutions
civil engineering | land surveying
409 Chicago Drive, Suite 112, Fayetteville, NC 28554
office | 910-426-6777 fax | 910-426-5777 license number | C-2354
www.4Dsite.com

03-22-24

REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

HARPER'S MEADOW

CLIENT

TRIANGLE LAND PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE

NOT TO SCALE








DATE RELEASED

MARCH 22, 2024

SHEET NUMBER

C-6.6

I:\Projects\Land Parcel\1806\Harper's Meadow\DWG\SDW\01-1806-SEC04.dwg • 03/12/2024 2:10 PM



REVISIONS
ISSUED FOR CONSTRUCTION

PROJECT NAME

HARPER'S MEADOW

WATER & SEWER DETAILS

CLIENT

TRIANGLE LAND PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE





NOT TO SCALE

DATE RELEASED


MARCH 22, 2024

SHEET NUMBER

C-6.7



CHAIN LINK FENCE AND GATE



REVISIONS

ISSUED FOR CONSTRUCTION

PROJECT NAME

HARPER'S MEADOW

CLIENT

TRIANGLE LAND PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

DRAWING SCALE


NOT TO SCALE

DATE RELEASED



MARCH 22, 2024

SHEET NUMBER


C-6.8



PUMP SPECIFICATIONS:
HYDROMATIC
MODEL: S4MVXP
SET POINT: 80 GPM, 23.6' TDH



- TOWN OF LILLINGTON LIFT STATION REQUIREMENTS
1. WET WELL SHALL BE INTERNALLY LINED WITH RAVEN 405 OR APPROVED EQUAL IN ACCORDANCE WITH "SEWER MATERIAL STANDARDS" SECTION 2,F,7.
 2. ALL BOLTS, MOUNTING BRACKETS, PUMP LIFTING CHAINS, ETC. SHALL BE STAINLESS STEEL AND SIZED AND MOUNTED TO SUPPORT APPLICABLE LOADS.
 3. ANCHOR POINTS FOR 5,000 LB RATING FALL PROTECTION AND SHALL HAVE TWO, ONE ON EACH SIDE OR ATOP OF THE WET WELL.
 4. LIFT STATION INSTALLATION SHALL FOLLOW ALL STANDARDS IN SECTION 6 OF THE TOWN OF LILLINGTON DETAILED SANITARY SEWER SPECIFICATIONS.



REVISIONS
ISSUED FOR CONSTRUCTION

PROJECT NAME

HARPER'S MEADOW

LIFT STATION DETAILS

CLIENT


TRIANGLE LAND PARTNERS, LLC

PO Box 5548
Cary, North Carolina 27512
Phone: (704) 608-3085

PROJECT INFORMATION

DESIGNED BY:	CALEB
DRAWN BY:	CALEB
CHECKED BY:	SCOTT
PROJECT NUMBER:	1896

LUMINAIRE SCHEDULE							
CALLOUT	SYMBOL	LAMP	DESCRIPTION	BALLAST	MOUNTING	MODEL	VOLTS
A		(1) LED	8' LED STRIP WET LOCATION SUITABLE	ELECTRONIC	SURFACE		120V 1P 2W




1 SITE ELECTRICAL PLAN
E1 N.T.S.

NOTE: ALL WIRES (TO INCLUDE FLOATS) LEAVING THE WET WELL SHALL BE SPLICED INSIDE AN ELECTRICAL JUNCTION BOX JUST OUTSIDE THE WET WELL AND PROPERLY LABELED ON BOTH ENDS BEFORE CONTINUING TO THE CONTROL BOX.

ALL ELECTRICAL WORK MUST MEET TOWN OF LILLINGTON STANDARDS

120 V.A.C. FLASHING RED ALARM LIGHT (DAYTIME VISIBLE) & ALARM BELL, WP. BENJAMIN FARADAY OR EQUAL.



5 CONTROL RACK SIDE VIEW
E1 N.T.S.

NOTE: SEE ONE LINE DIAGRAM THIS SHEET


ELECTRICAL NOTES:

1. INCLUDE 120 V SERVICE OUTLET IN PUMP CONTROL PANEL.
2. WIRE SIZE AND CONDUIT SIZE MAY VARY DEPENDING UPON PUMP REQUIREMENTS.
3. RUN FLOAT WIRES FROM WETWELL THROUGH TERMINAL STRIP IN JUNCTION BOX TO PANEL.
4. ALL ENCLOSURES SHALL BE NEMA 4X STAINLESS STEEL.


NOTES

1. BACKING PLATE TO BE 1/4" ALUMINUM. MOUNT TO "I" BEAM POSTS WITH STAINLESS STEEL NUT, BOLTS, AND WASHERS.
2. ALL ELECTRICAL WORK SHALL CONFORM TO LATEST NATIONAL, STATE AND LOCAL CODES AND REQUIREMENTS.
3. SHOW CONDUIT SIZE AND RUNS WITH WIRE SIZE AND NUMBER ON PUMP STATION PLANS.
4. PANEL LAYOUT IS SCHEMATIC ONLY. ADJUST AS NEEDED TO ACCOMMODATE EQUIPMENT. MAINTAIN 4" MIN. CLEARANCE BETWEEN PANELS AND SIDE SHIELDS.
5. ALL ENCLOSURES SHALL BE NEMA 4X RATED AND LOCKABLE.
6. ENCLOSURES SHALL BE MOUNTED TO ALUMINUM BACKING PLATE WITH NYLON SPACERS & STAINLESS STEEL NUTS BOLTS & WASHERS.
7. CONDUIT SHALL BE RIDGID ALUMINUM OR GALVANIZED. MEYERS HUBS SHALL BE USED AT ALL PANEL CONNECTIONS.
8. NO EQUIPMENT SHALL BE MOUNTED LESS THAN 36" ABOVE FINISHED GRADE. MIN. CLEARANCE FROM WORK LIGHT TO STANDING RAIN SHALL BE 6' 6".
9. FOR RAIN HOOD DETAIL SEE 3/E1.

6 CONTROL RACK DETAIL
E1 N.T.S.



3 RAIN HOOD DETAILS
E1 N.T.S.




2 EXTERIOR POLE LIGHT
E1 N.T.S.

GROUNDING ELECTRODE DETAILS

- GROUNDING ELECTRODE CONDUCTORS SHALL BE #8 BARE COPPER. OTHER MATERIAL AND INSTALLATION PER NEC 250
1. #8 CONNECT TO METALLIC WATER PIPE AS REQ'D.
 2. #8 TO BUILDING STEEL OR FOUNDATION REBAR
 3. 3/4"x10' LONG COPPER CLAD GROUNDING ROD W/ #6 COPPER GROUND.

4 ELEC. RISER DETAIL
E1 N.T.S.



Aug 24, 2023



Coastal Plains Engineering, P.A.

280 Locklear Rd
P.O. Box 1117
Pembroke, NC 28572
Tel: 252-338-1117
www.coastalplainseng.com

HARPERS MEADOW
LIFT STATION

LILLINGTON, NC 27546


DRAWINGS AND THE DESIGN ARE THE PROPERTY OF THE ENGINEER. WHETHER THE PROJECT FOR WHICH THEY ARE PREPARED IS EXECUTED OR NOT, THE DRAWINGS SHALL NOT BE USED BY THE PROJECT OWNER OR ANYONE ELSE FOR ANY OTHER PROJECT.

ADA AND LEGAL DISCLAIMER
THIS DOCUMENT IS INTENDED TO COMPLY WITH THE REQUIREMENTS OF THE AMERICANS WITH DISABILITIES ACT (ADA). ARCHITECTS AND ENGINEERS ARE NOT LICENSED TO INTERPRET LAWS OR GIVE ADVICE CONCERNING LAWS OR LEGAL MATTERS. THE OWNER SHOULD HAVE THIS DOCUMENT REVIEWED BY HIS ATTORNEY TO DETERMINE IF IT COMPLEYS ADA AND OTHER LAWS.

PROJECT NO	2023-025
DRAWN BY	WJ
CHECKED BY	CSL
DATE	02-20-23
REVISIONS	REVIEW COMMENTS

SHEET NO:

E-1



PP1

ROOM		VOLTS 240/120V 2P 3W				AIC 22,000			
MOUNTING SURFACE		BUS AMPS 60				MAIN BKR 60			
FED FROM UTILITY		NEUTRAL 100%				LUGS STANDARD			
NOTE									
CKT #	CKT BKR	CIRCUIT DESCRIPTION	LOAD KVA		CKT #	CKT BKR	CIRCUIT DESCRIPTION	LOAD KVA	
			A	B				A	B
1	20/1	ELECTRICAL RACK WPGFCI RECEPTACLE	0.54		2	20/1	REMOTE TERMINAL UNIT	0.42	
3	20/1	ELECTRICAL RACK LIGHTING	0.1	0.03	4	20/1	HOT BOX	1.5	0.18
5	20/1	POLE LIGHT		6	20/1	BATTERY CHARGER			
7	20/1	PUMP STATION WPGFCI RECEPTACLE	0	0.18	8	20/1	BLOCK HEATER	0	1.5
9	20/1	SPACE		10	20/1	SPACE			
11	20/1	SPACE		12	20/1	SPACE			
					TOTAL CONNECTED KVA BY PHASE			2.56	1.89
		CONN KVA	CALC KVA				CONN KVA	CALC KVA	
LIGHTING		0.03	0.038	(125%)	CONTINUOUS		0.52	0.65	(125%)
RECEPTACLES		0.72	0.72	(50%>10)	NONCONTINUOUS		3.18	3.18	(100%)
					TOTAL LOAD		4.59		
					BALANCED LOAD		19.1 A		

PC

ROOM		VOLTS 480V 3P 3W		AIC 22,000	
MOUNTING SURFACE		BUS AMPS 60		MAIN BKR MLO	
FED FROM UTILITY		NEUTRAL NONE		LUGS STANDARD	
NOTE					

CKT #	CKT BKR	CIRCUIT DESCRIPTION	LOAD KVA			CKT #	CKT BKR	CIRCUIT DESCRIPTION	LOAD KVA		
			A	B	C				A	B	C
1	20/3	PUMP #1	2.11			2	20/3	PUMP #2	2.11		
3				2.11		4					2.11
5					2.11	6					2.11
TOTAL CONNECTED KVA BY PHASE									4.21	4.21	4.21

	CONN KVA	CALC KVA		CALC KVA
LARGEST MOTOR	6.32	1.58	(25%)	TOTAL LOAD
MOTORS	12.6	12.6	(100%)	BALANCED 3-PHASE LOAD
				14.2
				17.1 A

Aug 24, 2023

NORTH CAROLINA

PROFESSIONAL

SEAL

2018S

ENGINEER

CHRISTOPHER S. LOCKLEAR

Coastal Plains Engineering, P.A.

280 Locklear Rd
P.O. Box 1117
Pembroke, NC 28572
Phone: 252-338-1117
www.coastalplainseng.com

License No: C-3090

HARPERS MEADOW

LIFT STATION

LILLINGTON, NC 27546

DRAWINGS AND THE DESIGN ARE THE PROPERTY OF THE ENGINEER. WHETHER THE PROJECT FOR WHICH THEY ARE PREPARED IS EXECUTED OR NOT, THE DRAWINGS SHALL NOT BE USED BY THE PROJECT OWNER OR ANYONE ELSE FOR ANY OTHER PROJECT.

ADA AND LEGAL DISCLAIMER
THIS DOCUMENT IS INTENDED TO COMPLY WITH THE REQUIREMENTS OF THE AMERICANS WITH DISABILITIES ACT (ADA). ARCHITECTS AND ENGINEERS ARE NOT LICENSED TO INTERPRET LAWS OR GIVE ADVICE CONCERNING LAWS OR LEGAL MATTERS. THE OWNER SHOULD HAVE THIS DOCUMENT REVIEWED BY HIS ATTORNEY TO DETERMINE IF IT COMPLES ADA AND OTHER LAWS.

PROJECT NO 2023-025

DRAWN BY WJ

CHECKED BY CSL

DATE 02-20-23

REVISIONS
B-24-23
COMMENTS

SHEET NO:

E-2

