

AIR 6472 B77G B77M

Product Specification

• TRX Branches	64T64R
• Antenna Elements	256
• Antenna configuration	(4x1)x(4x8)
• Operation band	B77G (3450-3550 MHz), B77M(3840-3980 MHz)
• IBW	530 MHz
• TCBW	200 MHz
• Output Power	400 W, max 4W/MHz PSD
• EIRP (Average)	80.8 dBm
• Supported RAT	NR
• Weight	67.2 lb(36.3"x15.83"x7.4")
• Size	~ 70 L
• eCPRI link	2x 25G
• Operating Temperature	-40 to +55°C, nature convection cooling
• Power Supply	-48VDC 3-wires, single connector
• Power Consumption	~ 760W, ETSI Avg.
• Multi-layer MU MIMO	16/8 DL/UL layer

