

CUSTOMER INSTALLATION

- 1. CUSTOMER WILL FURNISH AND INSTALL:
 - (A) ONE 4" X 6", 6" X 6" OR TWO 4" X 4" TREATED POSTS SUITABLE TO COMPANY.*
 - (B) SERVICE GROUND IN ACCORDANCE WITH N.E.C.
 - (C) ALL EQUIPMENT, MOUNTING HEIGHTS, AND CLEARANCES BEYOND THE METER SOCKET IN ACCORDANCE WITH N.E.C.
 - (D) ALL CONNECTIONS IN ACCORDANCE WITH N.E.C.
 - (E) MOBILE HOME SERVICES POSTS SHALL BE INSTALLED 18" MIN. FROM THE MOBILE HOME FOR MOUNTING THE SERVICE RISER, METER SOCKET, AND SERVICE EQUIPMENT. METERING EQUIPMENT SHALL FACE AWAY FROM MOBILE HOME SUCH THAT METER IS EASILY READABLE AND ACCESSIBLE. OTHER CONSTRUCTION IS PERMISSIBLE WITH LOCAL ENGINEER'S APPROVAL.
- 2. CUSTOMER WILL FURNISH, INSTALL, AND OWN METER SOCKET. TOP OF SOCKET MUST BE LEVEL FRONT TO FRONT TO BACK AND SIDE TO SIDE.

COMPANY INSTALLATION

- 3. COMPANY WILL PROVIDE AND INSTALL THE UNDERGROUND SERVICE LATERAL ACCORDING TO COMPANY'S STANDARD PRACTICES.
- 4. BOTTOM OF TRENCH MUST BE FIRMLY TAMPED NEAR POST. CABLE MUST BE POSITIONED FIRMLY AGAINST TAMPED EARTH DURING BACKFILLING. BEFORE CABLE IS CUT AFTER BACK-FILLING, PUSH CABLE DOWN IN CONDUIT TO PROVIDE AS MUCH SLACK AS POSSIBLE. THIS IS NECESSARY TO PREVENT SETTLING OF EARTH FROM PULLING ON CABLE AND DAMAGING METER BASE TERMINALS.
- 5. POINT OF DELIVERY IS WHERE COMPANY'S CONDUCTORS ATTACH TO METER SOCKET.

*SOME COUNTIES WITHIN COMPANY'S SERVICE AREA REQUIRE THE USE OF (ONE) SINGLE

	OR 6" X 6" POST.						ENERGY.			
	9/10/20	EANES	FLETCHER	GRAHAM	UNDERGROUND PERMANENT SERVICE	DEC	DEM	DEP	DEF	
	2/28/20	EANES	FLETCHER	GRAHAM						
	10/30/17	EANES	EANES	ADCOCK		Х		Х		
	2/1/16	SIMPSON	MEDLIN	CHANDLER	POST MOUNTED	FIG 4A				
VISED		BY	CHK'D	APPR.		1	LIG	44		

A DUKE