

HTE# E11808-0008

Harnett County Department of Public Health

30453

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Kodiak Industries PROPERTY LOCATION: 27 Dulness Ct. (NC 210 N.)
 SUBDIVISION Stockton LOT # 30
 NEW REPAIR EXPANSION
 Type of Structure: 302 52'x34' SFD Site Improvements required prior to Construction Authorization Issuance:
 Proposed Wastewater System Type: Pump to 25% Red.
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: C max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well NA feet Permit valid for: Five years
 Permit conditions: _____ No expiration

Authorized State Agent: [Signature] Date: 01/30/2019 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Kodiak Industries PROPERTY LOCATION: 27 Dulness Ct. (NC 210 N.)
 SUBDIVISION Stockton LOT # 30
 Facility Type: 302 52'x34' SFD New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** Pump to 25% reduction (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable
50% R.R.B.S Repair (Repair)

Installation Requirements/Conditions

Septic Tank Size <u>1000</u> gallons	Number of trenches <u>1</u>	Trench Spacing: <u>9</u> Feet on Center
Pump Tank Size <u>1000</u> gallons	Exact length of each trench <u>225</u> feet	Soil Cover: <u>8</u> inches
	Trenches shall be installed on contour at a Maximum Trench Depth of: <u>20</u> inches (Trench bottoms shall be level to +1-1/4" in all directions)	(Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM _____ inches below pipe
 Aggregate Depth: _____ inches above pipe _____ inches total
 Conditions: SYS SHALL BE INSTALLED AS TIGHT TO SFD AS CONTOUR WILL ALLOW [MAXIMIZE REPAIR]

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
 NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 01/30/2019
 Construction Authorization Expiration Date: 01/30/2024

HTE# EH1808-008

Permit # 30453

Harnett County Department of Public Health Site Sketch

ISSUED TO: Kodiak Industries PROPERTY LOCATION: 27 Duchess Ct. (NW 210 N.)
SUBDIVISION: Stockton LOT # 30

Authorized State Agent: *Andrew Curran* Date: 01/30/2019

