
## Harnett County Department of Public Health

### Improvement Permit

A building permit cannot be issued with only an Improvement Permit 7450 NC PROPERTY LOCATION: ISSUED TO: JOHN ROBERTS/DILLARS ENTERPUS TERMISON EXPANSION \_\_\_\_ TELECATION Assists Improvements required prior to Construction Authorization Issuance: NEW REPAIR Type of Structure: EXT, COMMERCIAL BUISINES Proposed Wastewater System Type: PUMP TO 25% NEONTON 150 GPD - 6 EMPLOYEES MAX Projected Daily Flow: 150 Number of Occupants: Na max Number of bedrooms: NA Basement Yes No May be required based on final location and elevations of facilities ☐ No Pump Required: Yes Type of Water Supply: Community Public Well Distance from well A feet Five years Permit valid for: No expiration Permit conditions: 09/20/2021 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules . 1950, . 1952, . 1954, . 1955, . 1956, . 1957, . 1958, and . 1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. PROPERTY LOCATION: 7450 NC 210 N. ISSUED TO: JOHN ROBERS/DILLAND ENTERPRISE SUBDIVISION Facility Type: EXT. COMM. BUISNESS Expansion Repair Basement? Yes No Basement Fixtures? Yes 25% NEDOCTIONS (Initial) Wastewater Flow: GPD Type of Wastewater System\*\* (See note below, if applicable ) TS-1 SUBSULFACE DUP Number of trenches 2 Installation Requirements/Conditions Exact length of each trench \_\_\_\_ Septic Tank Size \ \ \ \ \ \ \ \ \ \ gallons Pump Tank Size 1000 gallons Trenches shall be installed on contour at a Maximum Trench Depth of: 16 (Maximum soil cover shall not exceed [ IF NEGULED] (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) inches below pipe Pump Requirements: ft. TDH vs. \_ Aggregate Depth: ~A inches above pipe nches total Conditions: PUMP TO MEDIUM D-BOX EGUAL TYS recurred WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. \*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This SEE ATTACHED SITE SKETCH of the laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. Construction Authorization is subject to compliance with the provisions Authorized State Agent: ANDREW CORR

### Harnett County Department of Public Health Site Sketch



# Residential Subsurface Wastewater Treatment and Disposal System Proposal

NCDOT Parcel 112 PIN: 0673-14-4234.000 7450 NC 210 N Angier, NC Ground Truth Job # 21-147

Prepared For:

Dwight Dillard 3250 Campbell Road Raleigh, NC 27606

Prepared By:



Ground Truth Soil Consulting, PLLC 1302 Roberts Road Newport, NC 28570

(252) 725-1320

August 17, 2021

John C. Roberts

#### INTRODUCTION & SITE DESCRIPTION

A Soil & Site Evaluation was performed for the tract located at 7450 NC 210 N, Angier, NC (PIN: 0673-14-4234.000). Ground Truth Soil Consulting, PLLC (Ground Truth) was retained to prepare a proposal for an on-site wastewater treatment and disposal system that would allow for the construction of a commercial facility with 6 employees and a daily wastewater flow of 150 GPD. The lot was evaluated in accordance with North Carolina statutes for waste disposal ("Laws and Rules for Sewage Treatment and Disposal Systems", amended December 6, 2018").

The NCDOT project R5705A is proposed to impact the existing drainfield. A relocation permit is requested to relocate the septic drainfield.

The field survey was conducted in June through August 2021 by John C. Roberts, LSS. Soil borings were advanced via a hand auger and evaluated under moist conditions using procedures listed in the *Field book for Describing and Sampling Soils, Version 3.0*. Soil color was determined using a Munsell Soil Color Chart. Observations of the landscape as well as soil properties (depth, texture, structure, soil wetness, restrictive horizons, etc.) were recorded. It was determined sufficient amount of Provisionally Suitable Group III soils are available within the project area for installation of a Low-Pressure Pipe (LPP) System initial system for the facility. Sufficient area of Provisionally Suitable soils also exists to support a pretreated subsurface drip system.

#### **LOCATION**

The lot is located at 7450 NC 210 N, Angier, NC.

#### PLANS AND SPECIFICATIONS

#### A. Septic Tank

- 1. A septic tank may be needed. If so, the septic tank shall be State approved (Section .1953 of 15A NCAC 18A), watertight, structurally sound, and 900 gallons in capacity (at minimum).
- 2. The septic tank shall be fitted with an approved effluent filter.
- 3. It is the responsibility of the septic contractor to thoroughly inspect the septic tank prior to accepting delivery to assure that the tanks have had time to properly cure and are free of cracks or other structural deficiencies.

#### B. Pipes and Fittings

- 1. All discharge piping, connectors and supply lines should be made of SCH 40 PVC.
- 2. All joints must be properly "welded" utilizing the appropriate PVC cement for each application.
- 3. The supply line will be approximately 320 feet long from the septic tank to the upper septic drainline.
- 4. Supply line must be installed under driveways must be installed greater than 30 inches under or sleeved in ductile iron, or equivalent.

#### C. Distribution Method

1. Drainlines will be fed via LPP distribution.

#### D. Drainfield Installation-Initial

- 1. The drainfield has been previously laid out on-site utilizing metal stemmed flags. The property owner/builder should mark this area and isolate it as much as possible from construction traffic.
- 2. Under no circumstances shall any construction take place within the drainfield area while the soil is in a wet condition.
- 2. The specified system is a LPP system. Drainlines shall be installed no deeper than 12 inches.
- 3. The drainfield consists of two (4) LPP lateral trenches to be constructed 18-inches wide by 38 feet in length. Total drainline length is 152 feet.
- 5. The maximum trench depth for this system shall be 12 inches.
- 6. The laterals are to be installed keeping the individual trench bottoms level from beginning to end.
- 7. The trenches should be left open for the final inspection by the HCEH.
- 8. Laterals will consist of 1  $\frac{1}{4}$  inch Sch 40 PVC installed in 4 inch perforated pipe sleeve with rows of holes. Holes shall be between  $\frac{1}{2}$  and  $\frac{3}{4}$  inch diameter located approximately 120 degrees apart in downward position.
- 9. Orifice holes of 5/32 inch are to be drilled in  $1\,\frac{1}{4}$  inch lateral lines as listed in the appended LPP Summary sheet. The first and last hole is to be turned downward with remaining holes facing upward.

#### E. Final Landscaping

- 1. Final cover over the drainfield shall be at least 6 inches deep. If additional cover is needed, Group II (sandy loam) or Group III (sandy clay loam) soil shall be utilized.
- 2. The drainfield shall be shaped to shed rainwater and be free from low spots.
- 3. The drainfield area should be planted with grass as soon as possible to prevent erosion. The soil should be limed (if necessary) and fertilized prior to planting. After applying grass seed, the area should be heavily mulched with straw or other suitable material.

#### F. Utility Conflicts

- 1. The builder and property owner must take special care in planning for water, power, gas, telephone and cable lines. These utilities shall be kept clear of all parts of the septic system and its proposed repair area. Improper planning for underground utilities can negatively impact the installation and, in some cases, cause irreparable damage and permit revocation. If there are any questions regarding preferred routes, contact the HCEH as soon as possible.
- 2. Lawn irrigation should not be placed over the drainfield area.

#### MAINTENANCE

#### G. In General

- 1. The owner must maintain the drainfield area through periodic mowing. The drainfield must not be allowed to become overgrown.
- 2. The septic tank should be pumped every 4 years or when the solids within the septic tank reach an elevation that is equivalent to 25 percent of the volume of the tank. In some situations, the tanks may need to be pumped more frequently. If using a garbage disposal, it is recommended that the homeowner has the septic and pump tanks cleaned out annually.
- 3. When it becomes necessary to clean the effluent filter, the filter should be removed and the accumulated debris washed back into the septic tank not onto the lawn.
- 4. Any damp areas, leakages or malfunctions in the drainfield area should be addressed immediately.

5. Divert gutter downspouts and surface water runoff away from the septic tanks and septic drainfield.

#### **DESIGN SPECIFICS**

Initial System

Daily Design Flow:

150 GPD - 6 employees (25 gallon per employee)

Septic Tank Size:

900 Gallons (minimum, if needed)

Effluent Loading Rate:

0.2 GPD per sq. ft.

Drainfield Type:

LPP

Distribution Method:

Distribution Box

Number of Drainlines:

(4) 1.5' Wide x 38' Long

Total Trench Length:

152 Linear Feet

Maximum Trench Depth: Final Cover Requirement:

12 inches 6 Inches

Repair Specifics

Effluent Loading Rate:

0.4 GPD per sq. ft.

Drainfield Type:

TS-I Subsurface Drip

Distribution Method:

Drip disposal

Total Repair Area:

375 sq. ft.

Total Trench Length:


188'

Maximum Trench Depth:

6 Inches

Final Cover Requirement:

6 Inches



### Low Pressure Pipe Summary Sheet for 7450 NC 210 HWY

Name: Dwight Dilliard

P.I.N.#: <u>0673-14-4234.0</u>00

D#:

Address: 7450 NC 210 N

Subdivision:

Lot#:

Number of Employees: 6

Daily Flow:

150

L.T.A.R: 0.2 gal/d/sqft

Septic Tank:

900 gals Pump Tank:

900

gals

Square Footage:

750 sqft Total Lateral Length:

150 ft

Number of Laterals: 4

Width of Trenches:

18 in

Depth of Trenches: 12 in

Depth of Stone:

12 in

Lateral Pipe Size:

1 1/4

2

# Of Subfields:

1 1

(Up Hill Includes ST)

# of Gatevalves: Manifold Diameter:

3 in sch40pvc

Manifold Length:

# of Checkvalves:

12

ft

Supply Line Diameter:

2 in Sch40pvc

Length:

317 ft

Design Head:

3.00 ft

**Elevation Head:** 

-0.46 ft

**Friction Head:** 

2.54 ft

(Supply line length + 70' for fittings in pump tank)

TDH:

5.08 ft

(Design head+Elevation Head+Friction Head)

Pump to Deliver:

16.06 gal/min at

5.08 ft of head

Pipe Volumes:

ft manifold x 12

38.4 gal/100ft=

7.8 gal/100ft=

4.608 gals

317 <u>150</u>

ft supply line x total lateral lengthx

17.4

55.158

11.7 gals

gals

Lateral Dosing Volume:

11.7

gal x  $\frac{7}{}$  (5 to 10x)=

gal/100ft=

81.9

141.666 gals Dosing Volume

Draining Volume: 59.766 gals + Lateral Dosing Vol. =

gals

Drawdown: 141.666 gals divided by 20

gals/in =

7.0833 inches


Pump Run Time: 8.822548 minutes

7450 NC 210	LPP DESIGN

_													
	is = 100.00 s	set at	PumpT	ank elev		104.75	Pump	99.75		Manifold	d Elevation	99.29	
color	rod read	elev.	elev. dif.	head	length	hole size	flow/hole	spacing	# holes	1st/last	flow/lat	inst. flow rate	
		98.29	0.00	3.00	38	5/32	0.4986	4.00	9	3.00	4.49	0.1181	
		97.66	-0.63	3.00	38	5/32	0.4986	4.57	8	3.00	3.99	0.1050	
		97.29	-1.00	4.00	38	5/32	0.5757	5.33	7	3.00	4.03	0.1060	
		97.06	-1.23	4.23	38	5/32	0.5920	6.40	6	3.00	3.55	0.0935	
			total	feet =	152					gal/min =	16.06		
			<b>Total Fee</b>	t =	152				Total g	al/min =	16.06		
		is = 100.00 s	is = 100.00 set at  color rod read elev. 98.29 97.66 97.29	is = 100.00 set at PumpT  color rod read elev. elev. dif. 98.29 0.00 97.66 -0.63 97.29 -1.00 97.06 -1.23 total	color rod read elev. elev. dif. head 98.29 0.00 3.00 97.66 -0.63 3.00 97.29 -1.00 4.00 97.06 -1.23 4.23	color rod read elev. elev. dif. head length 98.29 0.00 3.00 38 97.66 -0.63 3.00 38 97.29 -1.00 4.00 38 97.06 -1.23 4.23 38 total feet = 152	color     rod read     elev.     elev. dif.     head length     hole size       98.29     0.00     3.00     38     5/32       97.66     -0.63     3.00     38     5/32       97.29     -1.00     4.00     38     5/32       97.06     -1.23     4.23     38     5/32       total     feet =     152	color         rod read         elev.         elev. dif.         head length         hole size         flow/hole           98.29         0.00         3.00         38         5/32         0.4986           97.66         -0.63         3.00         38         5/32         0.4986           97.29         -1.00         4.00         38         5/32         0.5757           97.06         -1.23         4.23         38         5/32         0.5920           total         feet =         152	color rod read elev. elev. dif. head length hole size flow/hole spacing 98.29 0.00 3.00 38 5/32 0.4986 4.00 97.66 -0.63 3.00 38 5/32 0.4986 4.57 97.29 -1.00 4.00 38 5/32 0.5757 5.33 97.06 -1.23 4.23 38 5/32 0.5920 6.40 total feet = 152	color         rod read         elev.         elev. dif.         head         length         hole size         flow/hole         spacing         # holes           98.29         0.00         3.00         38         5/32         0.4986         4.00         9           97.66         -0.63         3.00         38         5/32         0.4986         4.57         8           97.29         -1.00         4.00         38         5/32         0.5757         5.33         7           97.06         -1.23         4.23         38         5/32         0.5920         6.40         6           total         feet =         152	color rod read elev. elev. dif. head length hole size flow/hole spacing # holes 1st/last 98.29 0.00 3.00 38 5/32 0.4986 4.00 9 3.00 97.66 -0.63 3.00 38 5/32 0.4986 4.57 8 3.00 97.29 -1.00 4.00 38 5/32 0.5757 5.33 7 3.00 97.06 -1.23 4.23 38 5/32 0.5920 6.40 6 3.00 total feet = 152 gal/min =	color         rod read         elev.         elev. dif. bead 98.29         hole size 0.00         flow/hole 38.29         4.00         9 3.00         4.49           97.66         -0.63         3.00         38         5/32         0.4986         4.57         8         3.00         3.99           97.29         -1.00         4.00         38         5/32         0.5757         5.33         7         3.00         4.03           97.06         -1.23         4.23         38         5/32         0.5920         6.40         6         3.00         3.55           total         feet =         152         52         52         52         52         52         52         6.40         6         3.00         3.55	color         rod read         elev. 98.29         elev. 0.63         hole size 3.00         flow/hole 3.00         4.00         9         3.00         4.49         0.1181           97.29         -1.00         4.00         38         5/32         0.4986         4.57         8         3.00         3.99         0.1050           97.29         -1.00         4.00         38         5/32         0.4986         4.57         8         3.00         3.99         0.1050           97.29         -1.00         4.00         38         5/32         0.5757         5.33         7         3.00         4.03         0.1060           97.06         -1.23         4.23         38         5/32         0.5920         6.40         6         3.00         3.55         0.0935           total         feet =         152         5         5         5         6         6         3.00         3.55         0.0935

## **Typical LPP Trench and Manifold Details**

Figure 1: Manifold, Lateral, and Trench



<sup>\*\*</sup> Hole orientation should be upward except for a hole 1/3 and 2/3 the distance from the manifold which should face down for drainage of pipe between pump cycles.

Figure 2: Cross Section of Trench







Figure 3: Manifold Side Profile








## **MODEL 112 Control Panel**

#### Single phase, simplex motor contactor control.


The Model 112 control panel provides a reliable means of controlling one 120, 208, or 240 VAC single-phase pump in pump chambers, sump pump basins, irrigation systems and lift stations. Two control switches activate a magnetic motor contactor to turn the pump on and off. If an alarm condition occurs, an additional alarm switch activates the audio/visual alarm system.



- Enclosure measures 8 x 8 x 4 inches (20.32 X 20.32 X 10.16 cm). Choice of NEMA 1 (steel for indoor use), or NEMA 4X (ultraviolet stabilized thermoplastic with removable flanges for outdoor or indoor use).
  - \* Options selected may increase enclosure size and change component layout.
- 2. Magnetic Motor Contactor controls pump by switching hot electrical lines.
- 3. HOA Switch for manual pump control (mounted on circuit board).
- 4. Green Pump Run Indicator Light (mounted on circuit board).
- 5. Float Switch Terminal Block (mounted on circuit board).
- 6. Alarm and Control Fuses (mounted on circuit board).
- 7. Alarm and Control Power Indicators (mounted on circuit board).
- 8. Pump Input Power and Pump Connection Terminal Block
- 9. Ground Lug
- 10. Terminal Block Installation Label
- 11. Circuit Breaker (optional) provides pump disconnect and branch circuit protection. required (2X)

#### STANDARD ALARM PACKAGE (other options available)

- Red Alarm Beacon provides 360° visual check of alarm condition.
   Note: NEMA 1 style utilizes a door mounted indicator in lieu of a beacon.
- Alarm Horn provides audio warning of alarm condition (83 to 85 decibel rating).
  - Note: NEMA 1 style utilizes an internally mounted buzzer (83 to 85 decibel) in lieu of horn.
- Exterior Horn Test/Normal/Silence Switch allows alarm horn to be silenced and testing of horn and light to ensure proper operation of alarm system.
- Horn Silence Relay automatically resets alarm after alarm condition has been resolved (mounted on circuit board).



indoor

indoor/outdoor

#### **FEATURES**

- Entire control system (panel and switches) is UL Listed to meet and/or exceed industry safety standards
- Dual safety certification for the United States and Canada
- Standard package includes three 20' Sensor Float<sup>®</sup> control switches
- Complete with step-by-step installation instructions
- Three-year limited warranty





PO Box 1708, Detroit Lakes, MN 56502 1-888-DIAL-SJE • 1-218-847-1317 1-218-847-4617 Fax

email: sje@sjerhombus.com www.sierhombus.com

112 1 W 1 1/2 4 H 8	A, 8C, 15A
MODEL 112	
ALARMPACKAGE —	
0 = select options or no alarm package	
1 = alarm package (includes test/normal/silence switch, fuse, red light, horn & float)	
ENCLOSURE RATING ————————————————————————————————————	
= Indoor, NEMA 1 (metal)	
STARTING DEVICE	
1 = magnetic motor contactor 120/208/240V	
9 = magnetic motor contactor 120V only	!
0 = 0-7 FLA	
1 =8-15FLA	
2 = 16-20 FLA 3 = 21-30 FLA	
PUMP DISCONNECTS	
0 = no pump disconnect	i
1 = pull-out with safety deadfront in a 10"x8" enclosure	
FLOATSWITCHAPPLICATION	
H or L = pump down or pump up	
X = no floats	
OPTIONS	1
OPTIONS Listed below —	
TOptions selected may increase enclosure size and change component layout.	
If additional features are required, call the factory for a quote on either a Pro-Line or Engineered Custom control panel system.	
CODE DESCRIPTION CODE DESCRIPTION	
1 A Red beacon only / no audio 11C NEMA 1 alarm panel must select option 6A	
must select 1E if floats included11D NEMA 4X alarm panel must select option 6A	
L Horn only / no visual L 15A Control / alarm circuit breaker  must select 1E if floats included  Does not include the circuit board as in sta	adard
☐ 1E Alarm float ☐ 16A 10' cord in lieu of 20'	nuaro.
3A Alarm flasher 16B 15' cord in lieu of 20'	
★ 4A Low level cutout  16C 30' cord in lieu of 20'	
select option 4D if floats included 16D 40' cord in lieu of 20'	
★ 4B Red low-level indicator & alarm      ■ 17A SJE SignalMaster® / mounting strap ●      ■ 17B SJE SignalMaster® / externally weighted ●	
must select 4A also 17B SJE SignalMaster® / externally weighted ●  4D Low-level float17C Sensor Float® / internally weighted ▲	
6A Auxiliary alarm contact, form C type 17D Sensor Float® / externally weighted ▲	
★ 8A Elapsed time meter 17E Sensor Float® Mini / pipe clamp ▲	
★ 8C Event (cycle) counter 17F Sensor Float® Mini / externally weighted ▲	
10E Lockable latch - NEMA 4X	
★10F Lightning arrester 21B PumpMaster Plus in lieu of on/off switches	•
★10K Anti-condensation heater 21C Super Single® in lieu of on/off switches ▲	35 f
21D Double Float™ in lieu of on/off switches ▲	
● Mechanically-activated ▲ Mercury	-activated
SAMPLE	
MODEL 112 1 W 9 1 4 H 3A 8A	
Alarm Package —	
Enclosure Rating ————————————————————————————————————	- 1
Pump Full Load Amps ————————————————————————————————————	- 1
Pump Disconnect  Float Switch Application	- 1
Options: Alarm Flasher, Elapsed Time Meter	- 1
	1

