

## Harnett County Department of Public Health Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: 184 Deer Run Ct. (NC 210 N.)

ISSUED TO: Jeffrey Short SUBDIVISION Deer Run LOT # 14

NEW  REPAIR  EXPANSION  Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: Ext. 3-Bedroom SFD

Proposed Wastewater System Type: Conventional Sys.

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement  Yes  No

Pump Required:  Yes  No  May be required based on final location and elevations of facilities

Type of Water Supply:  Community  Public  Well Distance from well NA feet

Permit valid for:  Five years  
 No expiration

Permit conditions: \_\_\_\_\_

Authorized State Agent: [Signature] Date: 2-10-22 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

### Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, 1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Jeffrey Short PROPERTY LOCATION: 184 Deer Run Ct. (NC 210 N.)

SUBDIVISION Deer Run LOT # 14

Facility Type: Ext. 3-Bedroom SFD  New  Expansion  Repair

Basement?  Yes  No Basement Fixtures?  Yes  No

Type of Wastewater System\*\* Convnetional System (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable )

50% Reduction PPBPS Sys. (Repair)

Installation Requirements/Conditions

Septic Tank Size Ext. gallons

Pump Tank Size \_\_\_\_\_ gallons

Number of trenches MULTI  
Exact length of each trench 145 [SEED] feet

Trenches shall be installed on contour at a  
Maximum Trench Depth of: 18 inches  
(Trench bottoms shall be level to +/-1/4"  
in all directions)

Trench Spacing: 9 Feet on Center

Soil Cover: 6 inches  
(Maximum soil cover shall not exceed  
36" above the trench bottom)

Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM \* MEET ONSITE \*

Aggregate Depth: 6 inches below pipe  
2 inches above pipe

Conditions: SEE SITE PLAN PLAT TO INSTALL \_\_\_\_\_ 12 inches total

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.  
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 2-10-22  
[Signature] Construction Authorization Expiration Date: 2-10-27

