

# Harnett County Environmental Health

File/Permit Number: EH2406-0005

## CONSTRUCTION AUTHORIZATION

County: Harnett PIN/Lot Identifier: 0598-91-9885.000  
Owner: MILLER MARVIN RAY & MILLER WILMA L Applicant: MILLER MARVIN RAY & MILLER WILMA L  
Property Location: 90 SCRAMBLE RD ERWIN, NC 28339  
Facility Type: Ex. SFD

Number of bedrooms: 3 Number of Occupants: 6 Other: \_\_\_\_\_

New  Expansion  Repair  System Relocation  Change of Use

Basement?  Yes  No Basement Fixtures?  Yes  No

Crawl Space?  Yes  No Slab Foundation?  Yes  No

Type of Wastewater System\* 25% Reduction System (Initial) 25% Reduction System (Repair)

*\*Please include system classification for proposed wastewater system types in accordance with Rule .1301 Table XXXII*

Design Daily Flow: 360 GPD Wastewater Strength:  Domestic  High Strength  Industrial Process Wastewater

Rule .0403(e) Engineering Design Utilizing Low-flow Fixtures and Low-flow Technologies (S.L. 2013-413 and 2014-120)?  Yes  No  
(if yes, please provide engineering documentation)

Effluent Standard:  DSE  HSE  NSF/ANSI 40  TS-I  TS-II  RCW

Type of Water Supply:  Private well  Public well  Shared well  Municipal Supply  Spring  Other: \_\_\_\_\_

### Installation Requirements/Conditions

Septic Tank Size: 1,000 gallons Total Trench/Bed Length: 200' feet Trench/Bed Spacing: 9' feet on center

Trench/Bed Width: 36" inches LTAR: .45 gpd/ft<sup>2</sup> Usable Depth to LC (Initial)\*: 36" <sup>Limiting condition</sup>

Soil Cover: 6" inches Slope Corrected Maximum Trench/Bed Depth†: 18" - 24" inches <sup>Measured on the downhill side of the trench</sup>

Pump Tank Size (if applicable): \_\_\_\_\_ gallons Requires more than one pump?  Yes  No

Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM Grease Trap Size (if applicable): \_\_\_\_\_ gallons

Distribution Method:  Serial  D-Box or Parallel  Pressure Manifold(s)  LPP  Other: 2 - 100' Lines

Artificial Drainage Required: Yes  No  If yes, please specify details: \_\_\_\_\_

**Legal Agreements** (If the answer is "Yes" to any type of legal agreements, please attach a copy of the agreement.)

Multi-party Agreement Required [Rule .0204(g)]:  Yes  No

Easement, Right-of-Way, or Encroachment Agreement Required [Rule .0204(d)]:  Yes  No

Declaration of Restrictive Covenants:  Yes  No Pre-Construction Conference Required: Yes  No

Management Entity Required:  Yes  No Minimum O&M Requirements: \_\_\_\_\_

Conditions: No Foundation or Gutter Drains to be Directed Towards Septic System.

No Cutting or Grading of Septic or Septic Repair Area.

Septic Contractor to Install New Tank and Septic Drain Lines as seen on Site Plan.

The requirements of 15A NCAC 18E are incorporated by reference into this permit and shall be met. Systems shall be installed in accordance with the attached site sketch. ***This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes.*** The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of 15A NCAC 18E, or 15A NCAC 18A .1900, as applicable, and to the conditions of this permit.

Authorized Agent's Printed Name: Ren Levocz

Expiration Date: 6-21-29

Authorized Agent's Signature: 

Date: 6-21-24

**\*See attached site sketch\***

