

Harnett County Environmental Health

File/Permit Number: EH2408-0014

CONSTRUCTION AUTHORIZATION

County: Harnett PIN/Lot Identifier: 0665-60-6587.000 Lot 1
Owner: MURIEL LEONEL Applicant: MURIEL LEONEL
Property Location: 1501 ATKINS RD FUQUAY VARINA, NC 27526
Facility Type: Ex. SFD

Number of bedrooms: 3 Number of Occupants: 6 Other: _____

New Expansion Repair System Relocation Change of Use
Basement? Yes No Basement Fixtures? Yes No
Crawl Space? Yes No Slab Foundation? Yes No

Type of Wastewater System* _____ (Initial) 25% Reduction System (Repair)

**Please include system classification for proposed wastewater system types in accordance with Rule .1301 Table XXXII*

Design Daily Flow: 360 GPD Wastewater Strength: Domestic High Strength Industrial Process Wastewater

Rule .0403(e) Engineering Design Utilizing Low-flow Fixtures and Low-flow Technologies (S.L. 2013-413 and 2014-120)? Yes No
(if yes, please provide engineering documentation)

Effluent Standard: DSE HSE NSF/ANSI 40 TS-I TS-II RCW

Type of Water Supply: Private well Public well Shared well Municipal Supply Spring Other: _____

Installation Requirements/Conditions

Septic Tank Size: 1,000 gallons Total Trench/Bed Length: 300' feet Trench/Bed Spacing: 9 feet on center
Trench/Bed Width: 36" inches LTAR: .3 gpd/ft² Usable Depth to LC (Initial)*: 30" **Limiting condition*
Soil Cover: 6" inches Slope Corrected Maximum Trench/Bed Depth*: 18" inches ** Measured on the downhill side of the trench*

Pump Tank Size (if applicable): _____ gallons Requires more than one pump? Yes No

Pump Requirements: _____ ft. TDH vs. _____ GPM Grease Trap Size (if applicable): _____ gallons

Distribution Method: Serial D-Box or Parallel Pressure Manifold(s) LPP Other: Use Chambers due to setbacks

Artificial Drainage Required: Yes No If yes, please specify details: _____

Legal Agreements (If the answer is "Yes" to any type of legal agreements, please attach a copy of the agreement.)

Multi-party Agreement Required [Rule .0204(g)]: Yes No

Easement, Right-of-Way, or Encroachment Agreement Required [Rule .0204(d)]: Yes No

Declaration of Restrictive Covenants: Yes No Pre-Construction Conference Required: Yes No

Management Entity Required: Yes No Minimum O&M Requirements: _____

Conditions: Follow Site Sketch for All Septic System Requirements. 1. reroute all foundation and gutter drains to the side of property line and directed towards back of property away from septic system.

2. No Cutting or Grading of soil in septic area. 3. No Driving in septic system area. 4. Reroute plumbing to accommodate tank placement if needed.

5. Must Follow all setbacks on site sketch.

The requirements of 15A NCAC 18E are incorporated by reference into this permit and shall be met. Systems shall be installed in accordance with the attached site sketch. ***This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes.*** The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of 15A NCAC 18E, or 15A NCAC 18A .1900, as applicable, and to the conditions of this permit.

Authorized Agent's Printed Name: Ren Levocz Expiration Date: 9-20-29

Authorized Agent's Signature:  Date: 9-20-24

See attached site sketch

