

Harnett County Environmental Health

File/Permit Number: EH2503-0010

CONSTRUCTION AUTHORIZATION

County: Harnett PIN/Lot Identifier: 1610-38-9389.000
Owner: FLORES-GARCIA LIZZETE & GARCIA DANIELA FLORES Applicant: FLORES-GARCIA LIZZETE & GARCIA DANIELA FLORES
Property Location: 2373 BAILEY RD COATS, NC 27521
Facility Type: EX SFD

Number of bedrooms: 3 Number of Occupants: 6 Other: _____
☐ New ☐ Expansion ☒ Repair ☐ System Relocation ☐ Change of Use
Basement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ No
Crawl Space? ☒ Yes ☐ No Slab Foundation? ☐ Yes ☒ No
Type of Wastewater System* Ex. (Initial) 25% Reduction System (Repair)

*Please include system classification for proposed wastewater system types in accordance with Rule .1301 Table XXXII

Design Daily Flow: 360 GPD Wastewater Strength: ☒ Domestic ☐ High Strength ☐ Industrial Process Wastewater

Rule .0403(e) Engineering Design Utilizing Low-flow Fixtures and Low-flow Technologies (S.L. 2013-413 and 2014-120)? ☐ Yes ☐ No
(if yes, please provide engineering documentation)

Effluent Standard: ☒ DSE ☐ HSE ☐ NSF/ANSI 40 ☐ TS-I ☐ TS-II ☐ RCW

Type of Water Supply: ☐ Private well ☐ Public well ☐ Shared well ☒ Municipal Supply ☐ Spring ☐ Other: _____

Installation Requirements/Conditions

Septic Tank Size: 1,000 Ex. gallons Total Trench/Bed Length: 225' feet Trench/Bed Spacing: 9' feet on center
Trench/Bed Width: 36" inches LTAR: .4 gpd/ft² Usable Depth to LC (Initial)*: 42" *Limiting condition
Soil Cover: 6" inches Slope Corrected Maximum Trench/Bed Depth†: 18"-28" inches *Measured on the downhill side of the trench

Pump Tank Size (if applicable): _____ gallons Requires more than one pump? ☐ Yes ☐ No

Pump Requirements: _____ ft. TDH vs. _____ GPM Grease Trap Size (if applicable): _____ gallons

Distribution Method: ☒ Serial ☐ D-Box or Parallel ☐ Pressure Manifold(s) ☐ LPP ☐ Other: _____

Artificial Drainage Required: Yes ☐ No ☒ If yes, please specify details: _____

Legal Agreements (If the answer is "Yes" to any type of legal agreements, please attach a copy of the agreement.)

Multi-party Agreement Required [Rule .0204(g)]: ☐ Yes ☐ No

Easement, Right-of-Way, or Encroachment Agreement Required [Rule .0204(d)]: ☐ Yes ☐ No

Declaration of Restrictive Covenants: ☐ Yes ☐ No Pre-Construction Conference Required: Yes ☐ No ☒

Management Entity Required: ☐ Yes ☐ No Minimum O&M Requirements: _____

Conditions: Must Stay 15' Off power Line with septic system. (Hard Pipe) using ductile iron or double walled corrugated pipe under power line to reach septic lines.

Replace Filter, D-Box, and Install New Lines

The requirements of 15A NCAC 18E are incorporated by reference into this permit and shall be met. Systems shall be installed in accordance with the attached site sketch. This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of 15A NCAC 18E, or 15A NCAC 18A .1900, as applicable, and to the conditions of this permit.

Authorized Agent's Printed Name: Ren Levocz

Expiration Date: 3-27-30

Authorized Agent's Signature: [Signature]

Date: 3-27-25

See attached site sketch

