

PHYSICALLY HANDICAPPED NOTES

ACCESSIBLE ROUTES:

1. WHERE REQUIRED:

ACCESSIBLE ROUTES SHALL BE PROVIDED TO THE FACILITY PER C.B.C. 11B-206.

2. SITE ARRIVAL POINTS:

AT LEAST ONE ACCESSIBLE ROUTE SHALL BE PROVIDED WITHIN THE SITE FROM ACCESSIBLE PARKING SPACES AND ACCESSIBLE PASSENGER LOADING ZONES, PUBLIC STREETS AND SIDEWALKS, AND PUBLIC TRANSPORTATION STOPS TO THE ACCESSIBLE BUILDING OR FACILITY ENTRANCES THEY SERVE. WHERE MORE THAN ONE ROUTE IS PROVIDED, ALL ROUTES MUST BE ACCESSIBLE.

Exception:

AN ACCESSIBLE ROUTE SHALL BE REQUIRED BETWEEN SITE ARRIVAL POINTS AND THE BUILDING OR FACILITY ENTRANCES IF THE ONLY MEANS OF ACCESS BETWEEN THEM IS A VEHICULAR WAY NOT PROVIDING PEDESTRIAN ACCESS.

GENERAL CIRCULATION PATHS SHALL BE PERMITTED WHEN LOCATED IN CLOSE PROXIMITY TO AN ACCESSIBLE ROUTE.

3. WITHIN THE SITE:

AT LEAST ONE ACCESSIBLE ROUTE SHALL CONNECT ACCESSIBLE BUILDINGS, ACCESSIBLE FACILITIES, ACCESSIBLE ELEMENTS, AND ACCESSIBLE SPACES THAT ARE ON THE SAME SITE.

Exception:

AN ACCESSIBLE ROUTE SHALL NOT BE REQUIRED BETWEEN ACCESSIBLE BUILDINGS, ACCESSIBLE FACILITIES, ACCESSIBLE ELEMENTS, AND ACCESSIBLE SPACES IF THE ONLY MEANS OF ACCESS BETWEEN THEM IS VEHICULAR WAY NOT PROVIDING PEDESTRIAN ACCESS.

Spaces and Elements:

AT LEAST ONE ACCESSIBLE ROUTE SHALL CONNECT ACCESSIBLE BUILDINGS OR FACILITY ENTRANCES WITH ALL ACCESSIBLE SPACES AND ELEMENTS WITHIN THE BUILDING OR FACILITY, INCLUDING MEZZANINES, WHICH ARE OTHERWISE CONNECTED BY A CIRCULATION PATH UNLESS EXEMPTED BY SECTION 11B-206.23 EXCEPTIONS THROUGH T.

Exception:

IN ASSEMBLY AREAS WITH FIXED SEATING REQUIRED TO COMPLY WITH SECTION 11B-211 AN ACCESSIBLE ROUTE SHALL NOT BE REQUIRED TO SERVE FIXED SEATING WHERE WHEELCHAIR SPACES REQUIRED TO BE ON AN ACCESSIBLE ROUTE ARE NOT PROVIDED.

Employee Work Areas:

COMMON USE CIRCULATION PATHS WITHIN EMPLOYEE WORK AREAS SHALL COMPLY.

Exception:

COMMON USE CIRCULATION PATHS LOCATED WITHIN EMPLOYEE WORK AREAS THAT ARE AN INTEGRAL COMPONENT OF WORK AREA EQUIPMENT SHALL NOT BE REQUIRED TO COMPLY WITH AN ACCESSIBLE ROUTE.

COMMON USE CIRCULATION PATHS LOCATED WITH EXTERIOR EMPLOYEE WORK AREAS THAT ARE FULLY EXPOSED TO THE WEATHER SHALL NOT BE REQUIRED TO COMPLY WITH AN ACCESSIBLE ROUTE.

4. LOCATION:

ACCESSIBLE ROUTES SHALL COINCIDE WITH OR BE LOCATED IN THE SAME AREA AS GENERAL CIRCULATION PATHS. WHERE CIRCULATION PATHS ARE INTERIOR, REQUIRED ACCESSIBLE ROUTES SHALL ALSO BE INTERIOR.

5. ENTRANCES:

ENTRANCES SHALL BE PROVIDED IN ACCORDANCE WITH C.B.C. CHAPTER 11B-206.A. ENTRANCE DOORS, DOORWAYS, AND GATES SHALL COMPLY WITH SECTION 11B-404 AND SHALL BE ON AN ACCESSIBLE ROUTE COMPLYING WITH SECTION 11B-402.

ALL ENTRANCES AND EXTERIOR GROUND FLOOR EXITS TO BUILDINGS AND FACILITIES SHALL COMPLY WITH SECTION 11B-404.

Exceptions:

EXTERIOR GROUND FLOOR EXITS SERVING SMOKE-PROOF ENCLOSURES, STAIRWELLS, AND EXIT DOORS SERVING STAIR ONLY SHALL NOT BE REQUIRED TO COMPLY WITH SECTION 11B-404.

EXITS IN EXCESS OF THOSE REQUIRED BY CHAPTER 10, AND WHICH ARE MORE THAN 24 INCHES ABOVE GRADE SHALL NOT BE REQUIRED TO COMPLY WITH SECTION 11B-404. SUCH DOORS SHALL HAVE WARNING SIGNS COMPLYING WITH SECTION 11B-1035, STATING THAT THEY ARE NOT ACCESSIBLE.

Tenant Spaces:

ALL ENTRANCES TO EACH TENANCY IN A FACILITY SHALL COMPLY WITH SECTION 11B-404.

Exception:

SELF SERVICE STORAGE FACILITIES NOT REQUIRED TO COMPLY WITH SECTION 11B-225.3 SHALL NOT BE REQUIRED TO BE ON AN ACCESSIBLE ROUTE.

Restricted Entrances:

WHERE RESTRICTED ENTRANCES ARE PROVIDED TO A BUILDING OR FACILITY, ALL RESTRICTED ENTRANCES TO THE BUILDING OR FACILITY SHALL COMPLY WITH SECTION 11B-404.

Service Entrances:

IF A SERVICE ENTRANCE IS THE ONLY ENTRANCE TO A BUILDING OR TO A TENANCY IN A FACILITY, THAT ENTRANCE SHALL COMPLY WITH SECTION 11B-404. IN EXISTING BUILDINGS AND FACILITIES, A SERVICE ENTRANCE SHALL NOT BE THE SOLE ACCESSIBLE ENTRANCE UNLESS IT IS THE ONLY ENTRANCE TO A BUILDING OR FACILITY.

6. DOORS, DOORWAYS, AND GATES:

DOORS, DOORWAYS AND GATES PROVIDING USER PASSAGE SHALL BE PROVIDED IN ACCORDANCE WITH SECTION 11B-206.5.

Entrances:

EACH ENTRANCE TO A BUILDING OR FACILITY REQUIRED TO COMPLY WITH SECTION 11B-206.A SHALL COMPLY WITH SECTION 11B-404.

Rooms and Spaces:

WITHIN A BUILDING OR FACILITY, EVERY DOOR, DOORWAY OR GATE SERVING ROOMS AND SPACES COMPLYING WITH CHAPTER 11B-206 SHALL COMPLY WITH SECTION 11B-404.

ACCESSIBLE ROUTES:

1. ELEVATORS:

ELEVATORS PROVIDED FOR PASSENGERS SHALL COMPLY WITH SECTION 11B-407. WHERE MULTIPLE ELEVATORS ARE PROVIDED, EACH ELEVATOR SHALL COMPLY WITH SECTION 11B-407.

Exception:

IN A BUILDING OR FACILITY PERMITTED TO USE THE EXCEPTIONS TO SECTION 11B-206.23, AS PERMITTED BY SECTION 11B-206.1 TO USE A PLATFORM LIFT, ELEVATORS COMPLYING WITH SECTION 11B-408 SHALL BE PERMITTED.

ELEVATORS COMPLYING WITH SECTION 11B-408 OR 11B-409 SHALL BE PERMITTED IN MULTI-STORY RESIDENTIAL DWELLING UNITS. ELEVATORS PROVIDED AS MEANS OF ACCESS WITHIN A PRIVATE RESIDENCE SHALL BE INSTALLED SO THAT THEY ARE NOT ACCESSIBLE TO THE GENERAL PUBLIC OR TO OTHER OCCUPANTS OF THE BUILDING.

8. EXISTING ELEVATORS:

WHERE ELEMENTS OF EXISTING ELEVATORS ARE ALTERED, THE SAME ELEMENT SHALL ALSO BE ALTERED IN ALL ELEVATORS THAT ARE PROGRAMMED TO RESPOND TO THE SAME HALL CALL CONTROL. AS THE ALTERED ELEVATOR AND SHALL COMPLY WITH THE REQUIREMENTS OF SECTION 11B-407 FOR THE ALTERED ELEMENT.

9. SECURITY BARRIERS:

SECURITY BARRIERS, INCLUDING BUT NOT LIMITED TO, SECURITY BOLLARDS AND SECURITY CHECK POINTS, SHALL NOT OBSTRUCT A REQUIRED ACCESSIBLE ROUTE OR ACCESSIBLE MEANS OF EGRESS.

Exception:

WHERE SECURITY BARRIERS INCORPORATE ELEMENTS THAT CANNOT COMPLY WITH THESE REQUIREMENTS SUCH AS CERTAIN METAL DETECTORS, FLUOROSCOPES, OR OTHER SIMILAR DEVICES, THE ACCESSIBLE ROUTE SHALL BE PERMITTED TO BE LOCATED ADJACENT TO SECURITY SCREENING DEVICES. THE ACCESSIBLE ROUTE SHALL PERMIT PERSONS WITH DISABILITIES PASSING AROUND SECURITY BARRIERS TO MAINTAIN VISUAL CONTACT WITH THEIR PERSONAL ITEMS TO THE SAME EXTENT PROVIDED OTHERS PASSING THROUGH THE SECURITY BARRIER.

ACCESSIBLE MEANS OF EGRESS:

1. PARKING SPACES:

WHERE PARKING SPACES ARE PROVIDED, PARKING SPACES SHALL BE PROVIDED IN ACCORDANCE WITH SECTION 11B-208.

Exception:

PARKING SPACES USED EXCLUSIVELY FOR BUSES, TRUCKS, OTHER DELIVERY VEHICLES, OR VEHICULAR IMPOUND SHALL NOT BE REQUIRED TO COMPLY WITH SECTION 11B-208 PROVIDED THAT LOTS ACCESSIBLE BY THE PUBLIC ARE PROVIDED WITH A PASSENGER LOADING ZONE COMPLYING WITH SECTION 11B-503.

Minimum Number:

PARKING SPACES COMPLYING WITH SECTION 11B-502 SHALL BE PROVIDED IN ACCORDANCE WITH TABLE 11B-208.2 EXCEPT AS REQUIRED BY SECTION 11B-208.21, 11B-208.22 AND 11B-208.23. WHERE PROVIDED AT LEAST ONE PARKING FACILITY IS PROVIDED ON A SITE, THE NUMBER OF ACCESSIBLE SPACES PROVIDED ON THE SITE SHALL BE CALCULATED ACCORDING TO THE NUMBER OF SPACES REQUIRED FOR EACH PARKING FACILITY.

TABLE 11B-208.2 - PARKING SPACES

TOTAL NUMBER OF PARKING SPACES PROVIDED IN PARKING FACILITY.	MINIMUM NUMBER OF REQUIRED ACCESSIBLE PARKING SPACES
1 to 25	1
26 to 50	2
51 to 75	3
76 to 100	4
101 to 150	5
151 to 200	6
201 to 300	7
301 to 400	8
401 to 500	9
501 to 1000	2% OF TOTAL
1001 and over	20, plus 1 FOR EACH 100 OR FRACTION THEREOF, OVER 1000

Van Parking Spaces:

FOR EVERY SIX OR FRACTION OF SIX PARKING SPACES REQUIRED BY SECTION 11B-208.2, TO COMPLY WITH SECTION 11B-502, AT LEAST ONE SHALL BE A VAN PARKING SPACE COMPLYING WITH SECTION 11B-502.

2. LOCATION:

PARKING FACILITIES SHALL COMPLY WITH SECTION 11B-208.3

General:

PARKING SPACES COMPLYING WITH SECTION 11B-502 THAT SERVE A PARTICULAR BUILDING OR FACILITY SHALL BE LOCATED ON THE SHORTEST ACCESSIBLE ROUTE FROM PARKING TO AN ENTRANCE COMPLYING WITH SECTION 11B-206.A. WHERE PARKING SERVES MORE THAN ONE ACCESSIBLE ENTRANCE, PARKING SPACES COMPLYING WITH SECTION 11B-502 SHALL BE DISPERSED AND LOCATED ON THE SHORTEST ACCESSIBLE ROUTE TO THE ACCESSIBLE ENTRANCES. IN PARKING FACILITIES THAT DO NOT SERVE A PARTICULAR BUILDING OR FACILITY, PARKING SPACES COMPLYING WITH SECTION 11B-502 SHALL BE LOCATED ON THE SHORTEST ACCESSIBLE ROUTE TO AN ACCESSIBLE PEDESTRIAN ENTRANCE OF THE PARKING FACILITY.

Exception:

ALL VAN PARKING SPACES SHALL BE PERMITTED TO BE GROUPED ON ONE LEVEL WITHIN A MULTI-STORY PARKING FACILITY.

PARKING SPACES SHALL BE PERMITTED TO BE LOCATED IN DIFFERENT PARKING FACILITIES IF SUBSTANTIALLY EQUIVALENT OR GREATER ACCESSIBILITY IS PROVIDED IN TERMS OF DISTANCE FROM AN ACCESSIBLE ENTRANCE OR ENTRANCES, PARKING FEE, AND USER CONVENIENCE.

3. PASSENGER LOADING ZONES:

PASSENGER LOADING ZONES, EXCEPT THOSE REQUIRED TO COMPLY WITH SECTION 11B-209.22 AND 11B-209.23, SHALL PROVIDE AT LEAST ONE PASSENGER LOADING ZONE COMPLYING WITH SECTION 11B-503 IN EVERY CONTINUOUS 100 LINEAR FEET OF LOADING ZONE SPACE, OR FRACTION THEREOF.

STAIRWAYS:

1. GENERAL:

INTERIOR AND EXTERIOR STAIRS SHALL COMPLY WITH SECTION 11B-504.

Exceptions:

IN ALTERATIONS, STAIRS BETWEEN LEVELS THAT ARE CONNECTED BY AN ACCESSIBLE ROUTE SHALL NOT BE REQUIRED TO COMPLY WITH SECTION 11B-504, EXCEPT THAT STRIPING COMPLYING WITH SECTION 11B-504 AND HANDRAILS COMPLYING WITH SECTION 11B-505 SHALL BE PROVIDED WHEN THE STAIRS ARE ALTERED.

IN ASSEMBLY AREAS, ASBLE STAIRS SHALL NOT BE REQUIRED TO COMPLY WITH SECTION 11B-504 EXCEPT THAT STRIPING COMPLYING WITH SECTION 11B-504(A) SHALL BE PROVIDED.

STAIRS THAT CONNECT PLAY COMPONENTS SHALL NOT BE REQUIRED TO COMPLY WITH SECTION 11B-504 EXCEPT THAT STRIPING COMPLYING WITH SECTION 11B-504(A) SHALL BE PROVIDED.

DRINKING FOUNTAINS:

1. GENERAL:

WHERE DRINKING FOUNTAINS ARE PROVIDED ON AN EXTERIOR SITE, ON A FLOOR OR WITHIN A SECURED AREA THEY SHALL BE PROVIDED IN ACCORDANCE WITH SECTION 11B-211

2. MINIMUM NUMBER:

NO FEWER THAN TWO DRINKING FOUNTAINS SHALL BE PROVIDED. ONE DRINKING FOUNTAIN SHALL COMPLY WITH SECTION 11B-602J THROUGH 11B-602.6 AND ONE DRINKING FOUNTAIN SHALL COMPLY WITH SECTION 11B-602.7.

Exception:

WHERE A SINGLE DRINKING FOUNTAIN COMPLIES WITH SECTIONS 11B-602J THROUGH 11B-602.6 AND 11B-602.7, IT SHALL BE PERMITTED TO BE SUBSTITUTED FOR TWO SEPARATED DRINKING FOUNTAINS.

3. MORE THAN MINIMUM NUMBER:

WHERE MORE THAN THE MINIMUM NUMBER OF DRINKING FOUNTAINS SPECIFIED IN SECTION 11B-212 ARE PROVIDED, 50 PERCENT OF THE TOTAL NUMBER OF DRINKING FOUNTAINS PROVIDED SHALL COMPLY WITH SECTION 11B-602J THROUGH 11B-602.6, AND 50 PERCENT OF THE TOTAL NUMBER OF DRINKING FOUNTAINS PROVIDED SHALL COMPLY WITH SECTION 11B-602.7.

Exception:

WHERE 50 PERCENT OF THE DRINKING FOUNTAINS YIELDS A FRACTION, 50 PERCENT SHALL BE PERMITTED TO BE ROUNDED UP OR DOWN PROVIDED THAT THE TOTAL NUMBER OF DRINKING FOUNTAINS COMPLYING WITH SECTION 11B-211 EQUALS 100 PERCENT OF DRINKING FOUNTAINS.

KITCHENS, KITCHENETTES, WET BARS & SINKS:

KITCHENS, KITCHENETTES, AND WET BARS SHALL COMPLY WITH SECTION 11B-604.

WHERE SINKS ARE PROVIDED, AT LEAST 5 PERCENT, BUT NO FEWER THAN ONE, OF EACH TYPE PROVIDED IN EACH ACCESSIBLE ROOM OR SPACE SHALL COMPLY WITH SECTION 11B-606.

Exception:

MOP, SERVICE OR SCULLERY SINKS SHALL NOT BE REQUIRED TO COMPLY WITH SECTION 11B-213

SCRUB SINKS, AS DEFINED IN CALIFORNIA PLUMBING CODE SECTION 210, SHALL NOT BE REQUIRED TO COMPLY WITH SECTION 11B-606.

TOILET FACILITIES:

1. GENERAL:

WHERE TOILET FACILITIES AND BATHING FACILITIES ARE PROVIDED, THEY SHALL COMPLY WITH SECTION 11B-213. WHERE TOILET FACILITIES AND BATHING FACILITIES ARE PROVIDED IN FACILITIES PERMITTED BY SECTION 11B-206.23 EXCEPTION 1 NOT TO CONNECT STORIES BY AN ACCESSIBLE ROUTE, TOILET FACILITIES AND BATHING FACILITIES SHALL BE PROVIDED ON A STORY CONNECTED BY AN ACCESSIBLE ROUTE TO AN ACCESSIBLE ENTRANCE.

2. Toilet Facilities for Designated User Groups:

WHERE SEPARATE TOILET FACILITIES ARE PROVIDED FOR THE EXCLUSIVE USE OF SEPARATE USER GROUPS, THE TOILET FACILITIES SERVING EACH USER GROUP SHALL COMPLY WITH SECTION 11B-213.

3. Toilet Rooms & Bathing Rooms:

WHERE TOILET ROOMS ARE PROVIDED, EACH TOILET ROOM SHALL COMPLY WITH SECTION 11B-603. WHERE BATHING ROOMS ARE PROVIDED, EACH BATHING ROOM SHALL COMPLY WITH SECTION 11B-603.

Exceptions:

IN ALTERATIONS WHERE IT IS TECHNICALLY INFEASIBLE TO COMPLY WITH SECTION 11B-603, ALTERING EXISTING TOILET OR BATHING ROOMS SHALL NOT BE REQUIRED WHERE A SINGLE UNISEX TOILET ROOM OR BATHING ROOM COMPLYING WITH SECTION 11B-213 IS PROVIDED AND LOCATED IN THE SAME AREA AND ON THE SAME FLOOR AS EXISTING INACCESSIBLE TOILET OR BATHING ROOMS.

WHERE MULTIPLE SINGLE USER PORTABLE TOILET OR BATHING UNITS ARE CLUSTERED AT A SINGLE LOCATION 5 PERCENT, BUT NO FEWER THAN ONE, OF THE TOILET UNITS AND BATHING UNITS AT EACH CLUSTER SHALL COMPLY WITH SECTION 11B-603. PORTABLE TOILET UNITS AND BATHING UNITS COMPLYING WITH SECTION 11B-603 SHALL BE IDENTIFIED BY THE INTERNATIONAL SYMBOL OF ACCESSIBILITY COMPLYING WITH SECTION 11B-1031.21.

WHERE MULTIPLE SINGLE USER TOILET ROOMS ARE CLUSTERED AT A SINGLE LOCATION, 50 PERCENT, BUT NO FEWER THAN ONE, OF THE SINGLE USER TOILET ROOMS FOR EACH USE AT EACH CLUSTER SHALL COMPLY WITH SECTION 11B-603.

WHERE TOILET AND BATHING ROOMS ARE PROVIDED IN GUEST ROOMS THAT ARE NOT REQUIRED TO PROVIDE MOBILITY FEATURES COMPLYING WITH SECTION 11B-806.2, TOILET AND BATHING FIXTURES SHALL ONLY BE REQUIRED TO COMPLY WITH SECTION 11B-603.6.

4. UNISEX-SINGLE USE TOILET ROOMS

UNISEX TOILET ROOMS SHALL CONTAIN NOT MORE THAN ONE LAVATORY, AND NOT MORE THAN TWO WATER CLOSETS WITHOUT URINALS OR ONE WATER CLOSET AND ONE URINAL. UNISEX BATHING ROOMS SHALL CONTAIN ONE SHOWER OR ONE SHOWER AND ONE BATHUB, ONE LAVATORY AND ONE WATER CLOSET. DOORS TO UNISEX TOILET ROOMS AND UNISEX BATHING ROOMS SHALL HAVE PRIVACY LATCHES.

TOILET FACILITIES:

1. PLUMBING FIXTURES & ACCESSORIES:

PLUMBING FIXTURES AND ACCESSORIES PROVIDED IN A TOILET ROOM OR BATHING ROOM REQUIRED TO COMPLY WITH SECTION 11B-213 SHALL COMPLY WITH SECTION 11B-213.3.

Toilet Compartments:

WHERE TOILET COMPARTMENTS ARE PROVIDED, AT LEAST ONE TOILET COMPARTMENT SHALL COMPLY WITH SECTION 11B-604.21. IN ADDITION TO THE COMPARTMENT REQUIRED TO COMPLY WITH SECTION 11B-604.1, AT LEAST ONE COMPARTMENT SHALL COMPLY WITH SECTION 11B-6-4.8.2 WHERE SIX OR MORE TOILET COMPARTMENTS ARE PROVIDED, OR WHERE THE COMBINATION OF URINALS AND WATER CLOSETS TOTAL SIX OR MORE FIXTURES.

Water Closets:

WHERE WATER CLOSETS ARE PROVIDED, AT LEAST ONE SHALL COMPLY WITH SECTION 11B-604.

Urinals:

WHERE ONE OR MORE URINALS ARE PROVIDED, AT LEAST ONE SHALL COMPLY WITH SECTION 11B-605.

Lavatories:

WHERE LAVATORIES ARE PROVIDED, AT LEAST FIVE PERCENT BUT NO FEWER THAN ONE SHALL COMPLY WITH SECTION 11B-606 AND SHALL NOT BE LOCATED IN A TOILET COMPARTMENT.

Mirrors:

WHERE MIRRORS ARE PROVIDED, AT LEAST ONE SHALL COMPLY WITH SECTION 11B-603.3.

Bathing Facilities:

WHERE BATHUBS OR SHOWERS ARE PROVIDED, AT LEAST ONE BATHUB COMPLYING WITH SECTION 11B-607 OR AT LEAST ONE SHOWER COMPLYING WITH SECTION 11B-608 SHALL BE PROVIDED. WHERE TWO OR MORE ACCESSIBLE SHOWERS ARE PROVIDED WITHIN THE SAME LOCATION AREA, AT LEAST ONE SHOWER SHALL BE OPPOSITE HAND FROM THE OTHER OR OTHERS THAT IS, ONE LEFT HAND CONTROLS VERSUS RIGHT HAND CONTROLS.

Coat Hooks & Shelves:

WHERE COAT HOOKS OR SHELVES ARE PROVIDED IN TOILET ROOMS WITHOUT TOILET COMPARTMENTS, AT LEAST ONE OF EACH TYPE SHALL COMPLY WITH SECTION 11B-603.4. WHERE COAT HOOKS OR SHELVES ARE PROVIDED IN TOILET COMPARTMENTS, AT LEAST ONE OF EACH TYPE COMPLYING WITH SECTION 11B-604.8.3 SHALL BE PROVIDED IN TOILET COMPARTMENTS REQUIRED TO COMPLY WITH SECTION 11B-213.3. WHERE COAT HOOKS OR SHELVES ARE PROVIDED IN BATHING FACILITIES, AT LEAST ONE OF EACH TYPE COMPLYING WITH SECTION 11B-603.4 SHALL SERVE FIXTURES REQUIRED TO COMPLY WITH SECTION 11B-213.6.

FIRE ALARMS:

1. GENERAL:

WHERE FIRE ALARM SYSTEMS PROVIDED AUDIBLE ALARM COVERAGE, ALARMS SHALL COMPLY WITH SECTION 11B-25.

Exception:

IN EXISTING FACILITIES, VISIBLE ALARMS SHALL NOT BE REQUIRED EXCEPT WHERE AN EXISTING FIRE ALARM SYSTEM IS UPGRADED OR REPLACED, OR A NEW FIRE ALARM SYSTEM IS INSTALLED.

2. Public and Common Use Areas:

ALARMS IN PUBLIC USE AREAS AND COMMON USE AREAS SHALL COMPLY WITH CHAPTER 9, SECTION 9075.23.1.

Employee Work Areas:

WHERE EMPLOYEE WORK AREAS HAVE AUDIBLE ALARM COVERAGE, THE WIRING SYSTEM SHALL BE DESIGNED SO THAT VISIBLE ALARMS COMPLYING WITH CHAPTER 9, SECTION 9075.23.2 CAN BE INTEGRATED INTO THE ALARM SYSTEM.

SIGNS:

GENERAL:

NEW OR ALTERED SIGNS SHALL BE PROVIDED IN ACCORDANCE WITH SECTION 11B-216 AND SHALL COMPLY WITH SECTION 11B-103. THE ADDITION OF OR REPLACEMENT OF SIGNS SHALL NOT TRIGGER ANY ADDITIONAL PATH OF TRAVEL REQUIREMENTS.

Exception:

BUILDING DIRECTORIES, MENUS, SEAT AND ROW DESIGNATIONS IN ASSEMBLY AREAS, OCCUPANT NAMES, BUILDING ADDRESSES, AND COMPANY NAMES AND LOGOS SHALL NOT BE REQUIRED TO COMPLY WITH SECTION 11B-216.

IN PARKING FACILITIES, SIGNS PROVIDED SOLELY FOR THE OPERATION OF VEHICLES SHALL NOT BE REQUIRED TO COMPLY WITH SECTIONS 11B-216.2, 11B-216.3 AND 11B-216.6 THROUGH 11B-216.2.

TEMPORARY, 7 DAYS OR LESS, SIGNS SHALL NOT BE REQUIRED TO COMPLY WITH SECTION 11B-216.

1. Designations:

INTERIOR AND EXTERIOR SIGNS IDENTIFYING PERMANENT ROOMS AND SPACES SHALL COMPLY WITH SECTIONS 11B-1031, 11B-1032, 11B-1033 AND 11B-1035. WHERE PICTOGRAMS ARE PROVIDED AS DESIGNATIONS OF PERMANENT ROOMS AND SPACES, THE PICTOGRAMS SHALL COMPLY WITH SECTION 11B-1031.6 AND SHALL HAVE TEXT DESCRIPTORS COMPLYING WITH SECTIONS 11B-1032 AND 11B-1035.

Exception:

EXTERIOR SIGNS THAT ARE NOT LOCATED AT THE DOOR TO THE SPACE THEY SERVE SHALL NOT BE REQUIRED TO COMPLY WITH SECTION 11B-1032.

2. Directional and Informational Signs:

SIGNS THAT PROVIDE DIRECTION TO OR INFORMATION ABOUT INTERIOR AND EXTERIOR SPACES AND FACILITIES OF THE SITE SHALL COMPLY WITH SECTION 11B-1033.

3. Means of Egress:

SIGNS FOR MEANS OF EGRESS SHALL COMPLY WITH SECTION 11B-216.4.

4. Exit Doors:

SIGNS REQUIRED BY CHAPTER 10, SECTION 10014 AT DOORS TO EXIT PASSAGEWAYS, EXIT DISCHARGE, AND EXIT STAIRWAYS SHALL COMPLY WITH SECTIONS 11B-1031, 11B-1032, 11B-1033 AND 11B-1035.

5. Areas of Refuge & Exterior Areas for Assisted Rescue:

SIGNS REQUIRED BY CHAPTER 10, SECTION 10018 TO PROVIDE INSTRUCTIONS IN AREAS OF REFUGE SHALL COMPLY WITH SECTION 11B-1033. SIGNS REQUIRED BY CHAPTER 10, SECTION 10019 AT DOORS TO AREAS OF REFUGE AND EXTERIOR AREAS FOR ASSISTED RESCUE SHALL COMPLY WITH SECTIONS 11B-1031, 11B-1032, 11B-1033 AND 11B-1035 AND INCLUDE AN INTERNATIONAL SYMBOL OF ACCESSIBILITY COMPLYING WITH SECTION 11B-1031.21.

Signs:

6. Directional Signs:

SIGNS REQUIRED BY CHAPTER 10, SECTION 10018 TO PROVIDE DIRECTIONS TO ACCESSIBLE MEANS OF EGRESS SHALL COMPLY WITH SECTION 11B-1035

7. Parking:

PARKING SPACES COMPLYING WITH SECTION 11B-502 SHALL BE IDENTIFIED BY SIGNS COMPLYING WITH SECTION 11B-502.6.

8. Entrances:

IN EXISTING BUILDINGS AND FACILITIES WHERE NOT ALL ENTRANCES COMPLY WITH SECTION 11B-404, ENTRANCES COMPLYING WITH SECTION 11B-404 SHALL BE IDENTIFIED BY THE INTERNATIONAL SYMBOL OF ACCESSIBILITY COMPLYING WITH SECTION 11B-1031.21. DIRECTIONAL SIGNS COMPLYING WITH SECTION 11B-1035 THAT INDICATE THE LOCATION OF THE NEAREST ENTRANCE COM