

**VGBA COMPLIANCE DATA SHEET (Pool Drain Safety Compliance Data Form)**

*Circulation*

Name and address of pool: The Grove at 421 1585 E Cornelius Harnett Blvd Lillington, NC 27546

Pool location:  Indoor  Outdoor

Pool type:  Swimming Pool  Wading Pool  Spa  Other \_\_\_\_\_

Volume of pool (gallons) 30,145

**Pump information:** (MULTIPLE PUMPS REQUIRE INDIVIDUAL DATA SHEETS)

Pump Type:  Recirculation(Filtration)  Hydrotherapy  Feature (Slide, Waterfall, Bubblers, etc)

Manufacturer Pentair Make Intelliflo VSF Model Number 011056

HP of Pump 3 Maximum Flow Rate (gpm) (Maximum flow from pump curve) 159

**Drain cover information:**

Manufacturer Aquastar Make Moflow Model Number 12MF101

Date Installed TBD Expiration Date of Drain Covers 5 years later

Flow rate of drain cover in gallons per minute (gpm) 274 Location of installation:  Floor or  Wall

Dimensions of Drain Cover (inches) 12" x 12" Shape (round, rectangular, square, etc.) Square

Drain cover conforms to ASME/ANSI A112.19.8-2007 or newer standard:  Yes  No

Single Main Drain:  Yes  No

If Yes, is this drain larger than 18"x23"  Yes  No  N/A (If No, complete Secondary Back up System below)

Multi-drain system:  Yes  No

Distance between pipes (pipe center to pipe center) (inches) 42"

(If less than 36", complete Secondary Back up System below)

**Secondary Back up System - Safety Vacuum Release System (SVRS) compliant with ASME/ANSI A112.19.17 or ASTM-F2387.**

Make and Model Number: N/A

**Sump information:**

Manufacturer A.S.A. Mfg. Inc. Make Fiberglass Field Built Sump Model FBS-50-812-4

Length (inches) 12 Width (inches) 12 Depth (inches) 12

Sump Construction:  Field Fabricated or  Manufactured

Date sump installed TBD Size of suction pipe (inches) 4

Clearance between the bottom of the drain cover and the opening of suction pipe (inches) 6.5

**Vacuum Line: Choose One**

No Vacuum Line in Pool

Protective cover on vacuum lines installed before May 1, 2010

Self-closing, self latching cover designed to be opened with a tool on vacuum lines installed after May 1,2010

**Equalizer line cover information:**

Pool Exempt:  No Equalizers  Gutter  Spray Pad  Plugged If Plugged, How/When? \_\_\_\_\_

Number of operable skimmer equalizers \_\_\_\_\_

Manufacturer \_\_\_\_\_ Make \_\_\_\_\_ Model # \_\_\_\_\_

Maximum Flow Rate (gpm) \_\_\_\_\_  floor or  wall Size of Equalizer lines \_\_\_\_\_ (inches)

Equalizer line cover installation date \_\_\_\_\_ Expiration Date \_\_\_\_\_

Owner/Operator/PE (title) Signature Christine Cox Date 7/7/2022

*"Healthy People, Safe Environment, Strong Community"*