



Item #: 460EC1872KIT Project: _____

Qty: _____ Date: _____ Approval: _____



Regency 18" x 72" NSF Chrome 4-Shelf Kit with 74" Posts

Item #460EC1872KIT



Technical Data

Length	72 Inches
Width	18 Inches
Height	74 Inches
Assembled	Assembly Required
Capacity	1800 lb.
Casters	Without Casters
Color	Silver
Features	NSF Listed
Finish	Chrome
Individual Shelf Capacity	450 lb.
Installation Type	Stationary
Material	Steel
Number of Shelves	4 Shelves
Style	Adjustable Vented
Type	Office Shelving Shelving Kits
Usage	Dry Environments Office Retail

Features

- 18" x 72" shelves
- (4) 74" stationary knock-down posts ship unassembled to reduce freight cost
- Recommended for use in dry environments
- Built to accommodate up to 450 lb. per shelf of evenly distributed weight
- High-quality, commercial-grade construction

Certifications



Notes & Details

Save space and organize your storage area with the Regency 18" x 72" NSF chrome shelf kit! You can optimize the space in your food storage area, janitorial closet, and more with (4) 18" x 72" shelves and (4) 74" posts. The chrome construction gives this shelving kit excellent durability in dry areas, and it is easy to keep clean and sanitary, while the open grid design allows for excellent air circulation. The space between the shelves is adjustable, giving you the flexibility to store items of varying heights, such as ingredient bins, boxes, cleaning supplies, and anything else that you want to be able to see and grab quickly when you need it.

Each shelf can hold a maximum of 450 lb. each of evenly distributed weight. Plus, the unit's high-quality design is commercial grade and delivers the reliable performance every business expects and needs.

9 Racks

9 5'

Regency Space Solutions



DI / DIL Series

Drop-in Beverage Dispensers and Accessories

DI-1522
DI-2323
DIL-2323

DI-1522/2323 features McCann's Carbonator Probe Technology

DI / DIL Series

- Maximum beverage cooling capacity in post-mix models
- Quick, easy install cold plate inlets and drain connections simplify pre-plumbing and installation
- Flomatic 464GP valves available in sanitary lever, push button, portion control and automatic fill valves. Valve lockout switch on ice bin door available*
- Options: Drop-in tower light box and splash guards, 23 x 23 stainless steel countertop adapter for 1522 models, stainless steel cabinet stand, backroom installation components/accessories

* Other valves available, contact factory for more details.



DI-2323-8-SL

Standard Features

- Dual-view merchandiser
- LED light kit
- Pepsi graphics
- Key switch
- Drain kit

Model	Ice Capacity	Dimensions (W x D x H**)	Under countertop	Shipping Weight	Electrical Requirements*
DI-1522	Up to 250 lbs/ 114 kg	15.00" x 22.00" x 16.38" (22.38") 38.10 x 55.88 x 41.61 (56.85) cm	23.54" 59.79 cm	168 lbs/ 76.2 kg	Dispenser: 120V/60Hz/2.42FLA Pump Deck: 120V/60Hz/8FLA
DI-2323	Up to 80 lbs/ 36 kg	23.00" x 23.00" x 16.88" (22.75") 58.40 x 58.40 x 42.86 (57.79) cm	18.00" 45.72 cm	206lbs/ 93.4 kg	Dispenser: 120V/60Hz/3.2FLA Pump Deck: 120V/60Hz/8FLA
DIL-2323	Up to 100 lbs/ 45.4 kg	23.00" x 23.00" x 16.88" (22.75") 58.40 x 58.40 x 42.86 (57.79) cm	21.50" 54.61 cm	190lbs/ 86.2 kg	Dispenser: 120V/60Hz/3.2FLA Pump Deck: 120V/60Hz/8FLA

* 220-240V/50Hz/1 also available, ** Height with merchandise

Item #: 600B11014 Project: _____

Qty: _____ Date: _____ Approval: _____

REGENCY
Tables and Sinks

Regency 1 Bowl Underbar Hand Sink with Swivel Faucet - 14 1/2" x 18 3/4"

Item #600B11014



Technical Data

Length	14 1/2 Inches
Width	18 3/4 Inches
Height	33 Inches
Bowl Depth	5 Inches
Backsplash Height	3 Inches
Backsplash	With Backsplash
Bowl Front to Back	14 Inches
Bowl Left to Right	10 Inches
Faucet Centers	4 Inches
Features	Faucet Included NSF Listed
Flow Rate	2 GPM
Gauge	18 Gauge
Leg Construction	Galvanized Steel
Material	Stainless Steel
Number of Bowls	1 Bowl
Number of Compartments	1 Compartments
Number of Drainboards	None
Stainless Steel Type	Type 304
Type	Hand Sinks

Features

- Includes 6" swivel faucet with 4" centers
- 2" drain (1 1/2" IPS) with drain basket included
- Durable stainless steel construction with galvanized legs and bullet feet
- Perfect for bars or prep areas
- Backsplash limits messes

Certifications



Notes & Details

Add a reliable sink to your business with this Regency one bowl underbar hand sink. It's made of durable, 18-gauge type 304-series stainless steel, making it great for busy prep areas and bars.

This underbar sink comes standard with a 3" high backsplash to help prevent messes. Two holes are punched on 4" centers for the included 6" swivel faucet, while the galvanized legs and bullet feet provide additional stability for reliable use on a daily basis.

WARNING: This product can expose you to chemicals including Nickel and Lead, which are known to the State of California to cause cancer, birth defects, or other reproductive harm. For more information, go to www.p65warnings.ca.gov.

Regency Tables & Sinks