

Donald Young

Subject: FW: Daniel Brooks

From: Donald Young

Date: 08/17/2020

To: Harnett County Inspections

Re: Customer Address
1346 Cypress Rd.
Cameron, NC 28326

Please be advised we hereby certify that the 15FT of LP gas line was buried at or below the minimum per North Carolina Code#404.12. Minimum Burial Depth. In Addition, we also hereby certify approved materials were used when connecting to tank, generator, and tying into existing gas logs LP Line in basement. LP line was pressurized to 50LBS for 60 Minutes on high pressure. Also, held pressure at 9 Inches for 15 Minutes on whole system for low pressure. Our Documentation for the safety check will also be forwarded with this Affidavit.

Thank you,
Don Young
East Region Operations Manager
EnergyUnited Propane
Durham, Creedmoor, Warrenton, Carthage
1-800-822-0197 EXT. 8241

PROPANE SAFETY CHECK

Propane!

Date of Service Call: 8/17/20

Customer Name: Daniel Brooks Time of Service Call: Arrived _____ Departed _____

Address: 1346 Cypress Rd City/St: Cameron NC Phone: 910 638 1910

Purpose: New Customer _____ Change of Occupancy _____ Out of Gas _____ Leak Complaint _____ Driver Request _____ Other X

Appliance	Central Heating	Space Heater	Water Heater	Range	Fireplace	Other
Manufacturer					Heat Glow	Generator
Model No.					25,000	222
Man Shut off (Installed/Existing)					YES	YES
Red Tagged (yes/no)					NO	NO

TANK/CYLINDER

Size	Serial #	MFR	Date	Last Test Date	Location	Tank	Paint	Pigtail	Fittings	Gauge	Relief Valve Condition	Valve Date	Cap	Fittings Leak Test
500	438837	Chem	89	89	Left	OK	OK	NEW	OK	590	OK	89	OK	OK

PIPING/REGULATOR OPERATION/CONDITION

	MFR	Model	Reg Date	Reg Condition	Reg Vent Position	Flow Pressure	Lock up Pressure
Twin Stage						In w.c.	In w.c.
Two Stage	1 st	REGO	LV4033TR	17	NEW	DOWN	10.5 Psig
	2 nd	REGO	LV4034YGR	18	NEW	DOWN	13.0 In w.c.

PIPING LEAK CHECK

Pressure prior to starting leak check	Start Pressure	End Pressure	Start Time	End Time	Pressure Held (Yes/No)
13.0	9.0	9.0	1:00	1:20	YES
—	—	—	—	—	—

PRESSURE TEST (New Piping Only)

	High Pressure	Low Pressure
Pressure Held	50 lbs	50 lbs
Time Held	60 Min	60 Min

COMMENTS: Install Generator

This inspection covers (propane/LP Gas) items and equipment visible and accessible to the service technician and represents the conditions existing on the date of inspection. It does not cover latent or manufacturing defects, and the internal working of sealed equipment, or structural components and cannot be construed to cover future defects or unforeseen happenings.

Daniel A Brooks
(Customer Name / Print)

S. Cal
(Service Technician Name / Print)

I have been told what to do if I smell a gas odor or otherwise suspect a gas leak and have been told where to shut the gas supply off at the tank.

I have performed an odor test and have detected the odor of propane at the tank.

I have smelled the propane gas and can detect its odor.

I have received the Consumer Safety Information and have been told to read and share with all family members and/or others living in the home.

I had gas system deficiencies and/or corrections, if any clearly explained to me. I am satisfied with the service work performed.

I currently own or have been provided with a Carbon Monoxide Detector and have been informed of the requirements as stated in NC Building Code: Residential Code section 315.2 of owning one. (NC customer only)

Daniel Brooks
(Customer Signature)

S. Cal
(Service Technician's Signature)