

01-2 0000 094

No 13388

# OPERATIONS PERMIT

Name: (owner) Hester Courts  New Installation  Septic Tank  
 Property Location: SR# \_\_\_\_\_  Repairs  Nitrification Line  
 Subdivision Chicom Country Club Lot # 1B+2B  
 TAX ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: Gerald Temple Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:   
 Water Supply:  Well  Public  Community  
 Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other Polystyrene Aggregate Trench System IWW 595-32  
 Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons  
 Subsurface Drainage Field: No. of ditches 4 exact length of each ditch 100 ft. width of ditches 3 ft. depth of ditches 18-30 in.  
 French Drain: \_\_\_\_\_ Linear feet

Date: 4/23/2001

PERMIT NO. 17582

Inspected by: Dwight M. Jewin R. S.  
Environmental Health Specialist

