

OPERATIONS PERMIT

Name: (owner) Terrri Cieri New Installation Septic Tank
Property Location: SR# NC 24/27 Repairs Nitrification Line
Subdivision Sherwood Forest Lot # 18 Phase 2
TAX ID# _____ Quadrant # _____
Contractor: U. Shapec Registration # _____

Basement with Plumbing: Garage:
Water Supply: Well Public Community
Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____
Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons
Subsurface No. of exact length width of depth of
Drainage Field ditches 2 of each ditch 120 ft. ditches 3 ft. ditches 18.25 in.
French Drain: _____ Linear feet

Date: 5-11-99
Inspected by: [Signature]
Environmental Health Specialist

PERMIT NO. 15580

