

OPERATIONS PERMIT

Name: (owner) MAK DEV CO LLC New Installation Septic Tank
Property Location: SR# N.C. 27 Repairs Nitrification Line
Subdivision ARBOR CREST Lot # 2
TAX ID# _____ Quadrant # _____
Contractor: MEKERA Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50' ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 4 exact length of each ditch 75 ft. width of ditches 3 ft. depth of ditches 15-24 in.

French Drain: — Linear feet

Date: 9-18-98

PERMIT NO. 14376

Inspected by: James E. Mantel
Environmental Health Specialist

