

# OPERATIONS PERMIT

Name: (owner) William Evers  New Installation  Septic Tank  
Property Location: SR# 1111  Repairs  Nitrification Line  
Subdivision Sev Oak Lot # 13  
TAX ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_  
Contractor: Digit Beckler Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:   
Water Supply:  Well  Public  Community  
Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other \_\_\_\_\_

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field: No. of ditches 2 exact length of each ditch 75 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain: \_\_\_\_\_ Linear feet

Date: 5/27/98  
Inspected by: Bryan M. Lewis, P.E.  
Environmental Health Specialist

PERMIT NO. 14774

