

OPERATIONS PERMIT

Name: (owner) Pine Grove Development New Installation Septic Tank
 Property Location: SR# 1115 Repairs Nitrification Line
 Subdivision Overview Est Lot # 138
 TAX ID# _____ Quadrant # _____
 Contractor: T. Brown Registration # _____

Basement with Plumbing: Garage:
 Water Supply: Well Public Community
 Distance From Well: 50 m ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other AT-GRADE
 Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons
 Subsurface Drainage Field: No. of ditches 1 exact length of each ditch 400 ft. width of ditches 3 ft. depth of ditches 12 in.
 French Drain: _____ Linear feet

Date: 2-20-97

PERMIT NO. 10421

Inspected by: J. W. [Signature]
Environmental Health Specialist

