

# OPERATIONS PERMIT

Name: (owner) Jason Jones

New Installation  Septic Tank

Property Location: SR# 1705 NO FAYGROUND

Repairs  Nitrification Line

Subdivision Forest Lee

Lot # 1-C

TAX ID# \_\_\_\_\_

Quadrant # \_\_\_\_\_

Contractor: CBE

Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 50' ft.

**Following are the specifications for the sewage disposal system on above captioned property.**

Type of system:  Conventional  Other EEE-ZZZ LAY IN WS-55-BR

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field No. of ditches 3 exact length of each ditch 100 ft. width of ditches 3 ft. depth of ditches 18-20 in.

French Drain: - Linear feet

Date: 5-21-01

PERMIT NO. 17119

Inspected by: James E. Mauldin  
Environmental Health Specialist

