

OPERATIONS PERMIT

Name: (owner) Matthew Nibe New Installation Septic Tank
 Property Location: SR# 2016 Repairs Nitrification Line
 Subdivision _____ Lot # _____
 TAX ID# _____ Quadrant # _____
 Contractor: Ralph Brown Registration # _____
 Basement with Plumbing: Garage:
 Water Supply: Well Public Community
 Distance From Well: 100+ ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other Pump to Chamber System ^{1 WWS-93-R1-2}
 Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons
 Subsurface Drainage Field No. of ditches 4 exact length of each ditch 75 ft. width of ditches 3 ft. depth of ditches 18 in.
 French Drain: _____ Linear feet

Date: 11-12-97
 Inspected by: Thomas J. Boyce R.S.
 Environmental Health Specialist

PERMIT NO. 10332

