

# OPERATIONS PERMIT

Name: (owner) Cumberland Homes  New Installation  Septic Tank  
 Property Location: SR# 210 towards Angier  Repairs  Nitrification Line  
 Subdivision Stockton Lot # 3  
 TAX ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: Ted Brown Registration # 12

Basement with Plumbing:  Garage:   
 Water Supply:  Well  Public  Community  
 Distance From Well: 50' ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other \_\_\_\_\_  
 Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons  
 Subsurface Drainage Field: No. of ditches 2 exact length of each ditch 150 ft. width of ditches 3 ft. depth of ditches 18.25 in.  
 French Drain: \_\_\_\_\_ Linear feet

Date: 8-20-96

PERMIT NO. 10479

Inspected by: James E. Marshall II  
Environmental Health Specialist

