

OPERATIONS PERMIT

Name: (owner) WS Parker Builders Inc New Installation Septic Tank
 Property Location: SR# 210N Repairs Nitrification Line
 Subdivision Stockton Lot # 5
 TAX ID# _____ Quadrant # _____
 Contractor: Ricky Holland Registration # _____

Basement with Plumbing: Garage:
 Water Supply: Well Public Community
 Distance From Well: 50' ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other Pump to Conventional
 Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons
 Subsurface No. of exact length width of depth of
 Drainage Field ditches 3 of each ditch 70 ft. ditches 3 ft. ditches 24 in.
 French Drain: — Linear feet

Date: 5-9-97

PERMIT NO. 10547

Inspected by: James E. Markate
Environmental Health Specialist

