

OPERATIONS PERMIT

Name: (owner) Michael David Batts

New Installation Septic Tank

Property Location: SR# 4215

Repairs Nitrification Line

Subdivision _____ Lot # _____

TAX ID# _____ Quadrant # _____

Contractor: Gerald Tempel

Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 3 exact length of each ditch 90 ft. width of ditches 3 ft. depth of ditches 18-24 in.

French Drain: _____ Linear feet

Date: 6/23/88

PERMIT NO. 10267

Inspected by: Bryan McQuinn P.E.
Environmental Health Specialist

