

# OPERATIONS PERMIT

Name: (owner) James Brafford  New Installation  Septic Tank  
 Property Location: SR# 1141  Repairs  Nitrification Line  
 Subdivision Heather Brook Lot # 9  
 TAX ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: L. Sharpe Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:   
 Water Supply:  Well  Public  Community  
 Distance From Well: 50m ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other \_\_\_\_\_  
 Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons  
 Subsurface Drainage Field No. of ditches 2 exact length of each ditch 100 ft. width of ditches 3 ft. depth of ditches 24 in.  
 French Drain: \_\_\_\_\_ Linear feet

Date: 4-3-97

PERMIT NO. 10991

Inspected by: J. W. [Signature]  
Environmental Health Specialist

