

CN: LARRY WADE

Mike Eaker Environmental Consulting

MEADOWBROOK LOT 11

Certified Professional Soil Scientist #78

(SECT 3)

P.O. Box 336
Linden, NC 28356

(910) 822-4540


NC HWY 210

ADDITIONAL R/W

* NOTES

- ① Typical Soil Profile
 0-10 LOAMY SAND (M, L, Fr)
 10-32 SANDY CLAY (SH, F)
 32-40 MIX OF SCLAY & PM
 * (NOTE: THIS IS MOST LIMITING PROFILE, OTHERS ARE BETTER)
 SOIL WETNESS 32 INCHES OR GREATER
- ② REC: TRENCH DEPTH 18 INCH
 LTR 0.3 gpd / ft²
- ③ SYSTEM SHOULD BE INSTALLED ON CONTOUR (MAY ALTER FROM DRAWING)
- ④ ASSUMES NO MORE THAN 3 BEDROOM HOME

REPAIR AREA CONV



ASHLEY DRIVE

↑ DRAINAGE EASEMENT

1" = 40'