

# OPERATIONS PERMIT

Name: (owner) Raynor BW13  New Installation  Septic Tank  
 Property Location: SR# 1414  Repairs  Nitrification Line  
 Subdivision Regalwood Lot # 29  
 TAX ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: Mike Ray Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:   
 Water Supply:  Well  Public  Community  
 Distance From Well: 60 ft.

**Following are the specifications for the sewage disposal system on above captioned property.**

Type of system:  Conventional  Other \_\_\_\_\_  
 Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons  
 Subsurface Drainage Field: No. of ditches 2 exact length of each ditch 200 ft. width of ditches 3 ft. depth of ditches 18-24 in.  
 French Drain: \_\_\_\_\_ Linear feet

PERMIT NO. 147516 Date: 5-20-98  
 Inspected by: Thomas J. Boyle R.S.  
 Environmental Health Specialist

