

OPERATIONS PERMIT

Name: (owner) Harris Co. Board of Education

☒ New Installation

☒ Septic Tank

Property Location: SR# _____

☐ Repairs

☒ Nitrification Line

Subdivision Dun Middle School

Lot # _____

TAX ID# _____

Quadrant # _____

Contractor: O.H. Strickland

Registration # _____

Basement with Plumbing: ☐

Garage: ☐

Water Supply: ☐ Well ☒ Public ☐ Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: ☒ Conventional ☐ Other _____

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 3 exact length of each ditch 100 ft. width of ditches 3 ft. depth of ditches 18-30 in.

French Drain: _____ Linear feet

Date: 4/18/2000

PERMIT NO. 14637

Inspected by: Bryan McGinnis R.S.
Environmental Health Specialist

