

HTE# \_\_\_\_\_

## Hart County Department of Public Health

29090

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: TERRY EVANSPROPERTY LOCATION: SR 100 Hobson RDNEW ☐REPAIR ☒EXPANSION ☐SUBDIVISION 1712

LOT # \_\_\_\_\_

Site Improvements required prior to Construction Authorization Issuance: \_\_\_\_\_

Type of Structure: EXProposed Wastewater System Type: 25% REDUCTIONProjected Daily Flow: 600 GPDNumber of bedrooms: 5 Number of Occupants: 10 maxBasement ☐ Yes ☒ NoPump Required: ☐ Yes ☐ No ☒ May be required based on final location and elevations of facilitiesType of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well \_\_\_\_\_ feet

Permit valid for:

☒ Five years☐ No expirationPermit conditions: Contractor to meet on site prior to installAuthorized State Agent: James E. MarkonDate: 11-2-16

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: TERRY EVANSPROPERTY LOCATION: on 1712 Hobson RD

SUBDIVISION \_\_\_\_\_

LOT # \_\_\_\_\_

Facility Type: EX☐ New☐ Expansion☒ RepairBasement? ☐ Yes ☒ NoBasement Fixtures? ☐ Yes ☒ No

Type of Wastewater System\*\*

(See note below, if applicable) ☐ Pump to25% REDUCTION (Repair)(Initial) Wastewater Flow: 600 GPDInstallation Requirements/ConditionsSeptic Tank Size EX gallonsPump Tank Size 1700 gallonsNumber of trenches 4Exact length of each trench 100 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 48" max inches(Trench bottoms shall be level to  $\pm 1/4"$ 

in all directions)

Trench Spacing: 9 Feet on CenterSoil Cover: 6 inches

(Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM

Aggregate Depth: 6 inches below pipe2 inches above pipe12 inches totalConditions: Contractor to meet on site prior to install 48" trench depths

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.  
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

TANK SIZE

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_

Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This

Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. MarkonDate: 11-2-16Construction Authorization Expiration Date: 11-2-17

HTE#

Permit # 29090

Harnett County Department of Public Health  
Site Sketch

ISSUED TO: Terry Evans PROPERTY LOCATOR: 54712 Hobson RD  
SUBDIVISION \_\_\_\_\_ LOT # \_\_\_\_\_  
Authorized State Agent: James E. Manhan Date: 11-2-16

\* Contractor to meet ON SITE  
Prior to install.

