

## IMPROVEMENT PERMIT

Be it ordained by the Harnett County Board of Health as follows: Section III, Item B. "No person shall begin construction of any building at which a septic tank system is to be used for disposal of sewage without first obtaining a written permit from the Harnett County Health Department".

Name: (owner) Bob West ☒ New Installation ☒ Septic Tank  
 Property Location: SR# Hwy 87 (Behind Sawyer's Store) ☐ Repairs ☒ Nitrification Line

Subdivision Starwood @ Overhills Lot # 5

Tax ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_

Number of Bedrooms Proposed: 3 Lot Size: 1.28 acres

Basement with Plumbing: ☐ Garage: ☒

Water Supply: ☐ Well ☒ Public ☐ Community

Distance From Well: \_\_\_\_\_ ft.

Following is the minimum specifications for sewage disposal system on above captioned property. Subject to final approval.

Type of system: ☒ Conventional ☐ Other \_\_\_\_\_

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface No. of exact length width of depth of  
 Drainage Field ditches 3 of each ditch 100 ft. ditches 3 ft. ditches 16-20 in.

French Drain required: \_\_\_\_\_ Linear feet

This permit is subject to revocation if site plans or intended use change.

Date: 21 September, 1993

Signed: [Signature]

Environmental Health Specialist

## VOID AFTER 5 YEARS

- \* Maintain at least 5' from dwelling
- \* Maintain at least 10' from property lines
- \*\* Maintain proper ditch depths \*\*
- \* Sufficient fill should be brought in to provide 6" of cover over gravel
- \*\* Install on contours
- \* Do not build or drive on system or repair areas

