

IMPROVEMENT PERMIT

Be it ordained by the Harnett County Board of Health as follows: Section III, Item B. "No person shall begin construction of any building at which a septic tank system is to be used for disposal of sewage without first obtaining a written permit from the Harnett County Health Department".

Name: (owner) James Farrar ☒ New Installation ☒ Septic Tank
 Property Location: SR# 1128 & 1126 ☐ Repairs ☒ Nitrification Line

Subdivision _____ Lot # _____

Tax ID# _____ Quadrant # _____

Number of Bedrooms Proposed: 2 Lot Size: 33.38

Basement with Plumbing: ☐ Garage: ☐

Water Supply: ☐ Well ☒ Public ☐ Community

Distance From Well: _____ ft.

Following is the minimum specifications for sewage disposal system on above captioned property. Subject to final approval.

Type of system: ☒ Conventional ☐ Other _____

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface No. of exact length width of depth of
 Drainage Field ditches 2 of each ditch 150 ft. ditches 3 ft. ditches 18-24 in.

French Drain required: — Linear feet

This permit is subject to revocation if site plans or intended use change.

Date: 4/7/95
 Signed: Chris Aiken, R.E.

Environmental Health Specialist

VOID AFTER 5 YEARS

- County water
- Lines shall be installed a maximum trench depth of 18-24" no more
- Schedule 40 solid line shall be used where needed
- Lines shall be installed on contour with 150 ground
- Mobile Home shall not be more than 100' from septic tank
- Solid line from mobile home to septic tank shall meet plumbing code & shall have adequate slope to insure solids are transported to septic tank.

