

OPERATIONS PERMIT

Name: (owner) Thomas Mettler Kwon

☒ New Installation

☒ Septic Tank

Property Location: SR# 1403 Hanwell Central

☐ Repairs

☒ Nitrification Line

Subdivision _____

Lot # 7

TAX ID# _____

Quadrant # _____

Contractor: Ralph Brown

Registration # _____

Basement with Plumbing: ☐

Garage: ☐

Water Supply: ☒ Well ☒ Public ☐ Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: ☒ Conventional ☐ Other _____

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of exact length width of depth of
ditches 2 of each ditch 150 ft. ditches 3 ft. ditches 18-20 in.

French Drain: — Linear feet

Date: 2-31-97

PERMIT NO. 10292

Inspected by: James C. Markley
Environmental Health Specialist

