

OPERATIONS PERMIT

Name: (owner) Rodney & Candace Lewis ☒ New Installation ☒ Septic Tank
Property Location: SR# 1001 Claude White Rd ☐ Repairs ☒ Nitrification Line
Subdivision _____ Lot # _____
TAX ID# _____ Quadrant # _____
Contractor: Nal Brown Registration # _____
Basement with Plumbing: ☐ Garage: ☐
Water Supply: ☒ Well ☐ Public ☐ Community
Distance From Well: 100 ft. minimum

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: ☒ Conventional ☐ Other _____
Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons
Subsurface No. of 1 exact length 200 width of 3 depth of 24"
Drainage Field ditches _____ of each ditch _____ ft. ditches _____ ft. ditches _____ in.
French Drain: _____ Linear feet

PERMIT NO. 14527

Date: 04 Nov 98
Inspected by: Vernat Dof
Environmental Health Specialist



well must be
installed at
least 100 feet
from any part
of the septic
system
and repair
area.