

# OPERATIONS PERMIT

Name: (owner) Michael Little ☒ New Installation ☒ Septic Tank  
Property Location: SR# 1294 ☐ Repairs ☒ Nitrification Line  
Subdivision L.C. McDonald Est. Lot # 3  
TAX ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_  
Contractor: Larry Sharp Registration # \_\_\_\_\_  
Basement with Plumbing: ☐ Garage: ☐  
Water Supply: ☒ Well ☐ Public ☐ Community  
Distance From Well: 100 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: ☐ Conventional ☐ Other \_\_\_\_\_  
Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons  
Subsurface No. of exact length width of depth of  
Drainage Field ditches 3 of each ditch 100 ft. ditches 3 ft. ditches 18 in.  
French Drain: \_\_\_\_\_ Linear feet

Date: 6-28-99

PERMIT NO. 15794

Inspected by: J. W. J. S.  
Environmental Health Specialist

