



Alternative Power Sales and Rental
 512 OLD APEX ROAD
 CARY, NC 27511
 (919) 467-8001
 www.alternativepower.com

Sizing Report

Sizing Information for:
 Roger Turrell
 70 Talbert Dr.
 Holly Springs, NC 27540

Rated Nominal Voltage 240
 Generator Fuel Choice Propane
 Sizing Method (NEC 220) Part IV
 (Part III required for selected circuit implementation, Both valid for whole house)

General Lighting & Receptacles		Load (kW)
Square Footage Being Covered (ft ²)	2200	6.6
Small Appliance Circuits (20 amps)		
Kitchen Circuits	2	3
Laundry Circuits	1	1.5

Fixed-In-Place Appliances & Motors	Managed Loads	Estimated (kW)	Nameplate (amps)	240 V	Load (kW)
Dryer		5.5		X	5.5
Microwave		1.3			1.3
Oven		5.0		X	5.0
Water Heater		5.0		X	5.0
Dishwasher		1.5			1.5
Freezer		0.8			0.8
Refrigerator		0.8			0.8

Air Conditioning & Cooling	Managed Loads	Estimated (kW)	Nameplate (amps)	240 V	Load (kW)
2.5 Ton Unit	X	2.5		X	0.0
1.5 Ton Unit	X	1.5		X	0.0

Heating & Heat Pumps	Managed Loads	Estimated (kW)	Nameplate (amps)	240 V	Load (kW)

Transient Requirement	Estimated (LRA)	Actual (LRA)	Utilized (LRA)
Largest Motor's Starting Amps (LRA)	72	63	63

	Load (kW)	NEC Required
Summary NEC Load		
General Lighting & Receptacles	11.1	
Fixed-in-Place Appliances & Motors	19.8	
Sum of all General Loads	30.9	18.4
Cooling	0.0	0.0
Heating (w/demand factors)	0.0	0.0
Larger of Heating & Cooling	0.0	0.0
Sizing based on requirements of NEC Article 220, Part IV		18.4
Elevation		0 ft
Minimum size generator for motor starting requirements		10
BTU load required		325000

20 kW Generac Model Generator Recommended