

**SCOPE OF WORK**

TO INSTALL A RESIDENTIAL ROOFTOP SOLAR PHOTOVOLTAIC (PV) SYSTEM.  
 THE POWER GENERATED BY THE PV SYSTEM WILL BE INTERCONNECTED WITH THE  
 UTILITY GRID THROUGH THE EXISTING ELECTRICAL SERVICE EQUIPMENT.  
 THE PV SYSTEM DOES NOT INCLUDE BATTERIES.

**ELECTRICAL NOTES**

- 1) ALL EQUIPMENT TO BE LISTED BY THE UL OR OTHER NRTL AND LABELED FOR ITS APPLICATION.
- 2) ALL CONDUCTORS SHALL BE COPPER, RATED FOR 600V AND 90°C WET ENVIRONMENT.
- 3) WIRING, CONDUIT, AND RACEWAYS MOUNTED ON ROOFTOPS SHALL BE ROUTED DIRECTLY TO, AND LOCATED AS CLOSE AS POSSIBLE TO THE NEAREST RIDGE, HIP, OR VALLEY.
- 4) WORKING CLEARANCES AROUND ALL NEW AND EXISTING ELECTRICAL EQUIPMENT SHALL COMPLY WITH NEC 110.26.
- 5) DRAWINGS INDICATE THE GENERAL ARRANGEMENT OF SYSTEMS. CONTRACTOR SHALL FURNISH ALL NECESSARY OUTLETS, SUPPORTS, FITTINGS AND ACCESSORIES TO FULFILL APPLICABLE CODES AND STANDARDS.
- 6) WHERE SIZES OF JUNCTION BOXES, RACEWAYS, AND CONDUITS ARE NOT SPECIFIED, THE CONTRACTOR SHALL SIZE THEM ACCORDINGLY.
- 7) ALL WIRE TERMINATIONS SHALL BE APPROPRIATELY LABELED AND READILY VISIBLE.
- 8) MODULE GROUNDING CLIPS TO BE INSTALLED BETWEEN MODULE FRAME AND MODULE SUPPORT RAIL, PER THE GROUNDING CLIP MANUFACTURER'S INSTRUCTION.
- 9) MODULE SUPPORT RAIL TO BE BONDED TO CONTINUOUS COPPER G.E.C. VIA WEEB LUG OR THE ILSCO GBL-4DBT LAY-IN LUG.
- 10) THE POLARITY OF THE GROUNDED CONDUCTORS IS (positive/negative) OR THE DC SIDE OF THE PV SYSTEM IS UNGROUNDED AND SHALL COMPLY WITH NEC 690.35

**NCDOT REQUIREMENTS**

**\*OPTION 2\***

WEIGHT OF PV SYSTEM ON ROOF:


**2.6956 PSF**

EXISTING ROOF MATERIAL TYPE:

**ASPHALT SHINGLES (SINGLE LAYER)**

PROJECT LOCATION WIND ZONE:

**115 MPH**



**VICINITY MAP**

**CONTRACTOR**



**SUN DOLLAR ENERGY, LLC**  
 4904 ELAINE AVENUE  
 RALEIGH, NC 27616  
 (919) 508-6907  
 NC ELE LICENSE #: 30043U  
 NC GC LICENSE #: 73462

**PROJECT & CLIENT INFORMATION**

**STRICKLAND RESIDENCE  
 NEW SOLAR PV SYSTEM**  
 SYSTEM SIZE: 8.03 KW DC  
 SYSTEM SIZE: 7.6 KW AC

**TRACY STRICKLAND**  
 33 GWENDOLYN WAY  
 FUQUAY-VARINA, NC 27526  
 (919) 274-9735

**ENGINEER OF RECORD**

**DRAWING BY**

**GBR**

**REVISIONS**

DESCRIPTION	DATE	#	BY
RELEASED FOR PERMITTING	9/25/2020	1	GBR

**SHEET SIZE**

**ANSI B  
 11" X 17"**

**DATE**

**9/25/2020**

**SHEET NAME**

**GENERAL  
 INFORMATION**

**SHEET NUMBER**

**COVER**

SHEET INDEX	
COVER	GENERAL INFORMATION
PV-1	SITE PLAN
PV-2	ROOF LAYOUT AND MOUNTING DETAIL
PV-3	ELECTRICAL SCHEMATIC
PV-4	AMPACITY CALCULATIONS AND WIRE SIZING
PV-5	LABELING SCHEDULE
CUTSHEETS	MANUFACTURER SPECIFICATION SHEETS

GOVERNING CODES
NFPA 70 NATIONAL ELECTRICAL CODE 2017
2018 INTERNATIONAL BUILDING CODE
2018 NORTH CAROLINA BUILDING CODE
2018 NORTH CAROLINA RESIDENTIAL CODE
UNDERWRITERS LABORATORIES (UL) STANDARDS
OSHA 29 CFR 1910.269
NORTH CAROLINA DEPARTMENT OF INSURANCE

DESIGN SPECIFICATIONS	
CONSTRUCTION TYPE	SINGLE-FAMILY
ZONING	RESIDENTIAL
GROUND SNOW LOAD	20 PSF
WIND EXPOSURE CATEGORY	CATEGORY B
WIND SPEED	115 MPH
UTILITY PROVIDER	DUKE PROGRESS
AHJ	HARNETT COUNTY

SYSTEM SPECIFICATIONS	
SOLAR MODULES	(22) REC REC365AA BLACK 365 WATT MODULES
POWER OPTIMIZERS	(22) SOLAREEDGE P400
INVERTER(S)	(1) SOLAREEDGE SE7600H-US
SOLAR MOUNTS	QUICKMOUNT PV L-MOUNTS
SOLAR RACKING SYSTEM	EVEREST CROSSRAIL X48
MONITORING	YES
POINT OF INTERCONNECT	40A/2P LOAD SIDE BREAKER IN MSP

# PROPERTY PLAN

SCALE: 1/16"=1'-0"



CONTRACTOR



**SUN DOLLAR ENERGY, LLC**  
 4904 ELAINE AVENUE  
 RALEIGH, NC 27616  
 (919) 508-6907  
 NC ELE LICENSE #: 30043U  
 NC GC LICENSE #: 73462

PROJECT & CLIENT INFORMATION

**STRICKLAND RESIDENCE  
 NEW SOLAR PV SYSTEM**  
 SYSTEM SIZE: 8.03 KW DC  
 SYSTEM SIZE: 7.6 KW AC

**TRACY STRICKLAND**  
 33 GWENDOLYN WAY  
 FUQUAY-VARINA, NC 27526  
 (919) 274-9735

ENGINEER OF RECORD

DRAWING BY

GBR

REVISIONS

DESCRIPTION	DATE	#	BY
RELEASED FOR PERMITTING	9/25/2020	1	GBR

SHEET SIZE

ANSI B  
 11" X 17"

DATE


9/25/2020

SHEET NAME

SITE PLAN


SHEET NUMBER

PV-1



# ROOF PLAN

SCALE: 1/8"=1'-0"



(22) REC REC365AA  
BLACK 365 WATT  
MODULES

QUICKMOUNT PV L-MOUNTS


EVEREST CROSSRAIL X48

ASPHALT SHINGLE (SINGLE LAYER) ROOF  
2X8 RAFTERS @ 24" O.C.


Flashings/Mounts	
Manufacturer	Quickmount PV
Mount Type	L-Mount
Flashing Material	Aluminum
Flashing Size	9" x 12" x .04"
Fastener Type	Lag Screw
Fastener Material	18-8 Stainless Steel
Fastener Size	5/16" x 4"
L-Foot Material	Aluminum
Sealing Washer	EPDM Bonded SS
Sealing Washer Size	5/16" ID x 3/4" OD
Weight	0.7565 Lbs.
Structural	IBC Compliant
UL Listing	UL 2703

Racking	
Manufacturer	Everest Solar
Model Number	Crossrail 48-X
Length	166"
Width	1.54"
Height	1.89"
Weight	0.56 Lbs./Ft
Material	Aluminum
Structural	IBC Compliant
UL Listing	UL 2703

ROOF 1 PITCH: 45°



LOAD CALCULATIONS		
NUMBER OF MODULES	22	
MODULE WEIGHT	43	LBS
MODULE SQ FT	18.8	SQ FT
TOTAL MODULE WEIGHT	946	LBS
TOTAL MODULE SQ FT	413.6	SQ FT
NUMBER OF PORTRAIT	21	
NUMBER OF LANDSCAPE	1	
NUMBER OF OPTIMIZERS	22	
WEIGHT PER OPTIMIZER	1.5	LBS
TOTAL OPTIMIZER WEIGHT	33	LBS
TOTAL LENGTH OF RAIL	151	LF
RAIL WEIGHT PER FOOT	0.56	LBS
TOTAL RAIL WEIGHT	84.56	LBS
NUMBER OF FLANGES	49	
WEIGHT PER FLANGE	0.7565	LBS
WEIGHT PER SYSTEM	37.0685	LBS
NUMBER OF MID CLAMPS	36	
MID CLAMP WEIGHT	0.21	LBS
WEIGHT PER SYSTEM	7.56	LBS
NUMBER OF END CLAMPS	18	
END CLAMP WEIGHT	0.32	LBS
WEIGHT PER SYSTEM	6	LBS
NUMBER OF SPLICES	7	
WEIGHT PER SPLICE	0.1	LBS
WEIGHT PER SYSTEM	0.7	LBS
TOTAL ARRAY WEIGHT	1114.889	LBS
POINT LOAD	22.75283	LBS/FT
TOTAL ARRAY AREA	413.6	SQ FT
<b>ARRAY DEAD LOAD</b>	<b>2.6956</b>	<b>PSF</b>



SOLAR MOUNTING DETAIL

CONTRACTOR

**SUN DOLLAR ENERGY, LLC**  
4904 ELAINE AVENUE  
RALEIGH, NC 27616  
(919) 508-6907  
NC ELE LICENSE #: 30043U  
NC GC LICENSE #: 73462

PROJECT & CLIENT INFORMATION

**STRICKLAND RESIDENCE  
NEW SOLAR PV SYSTEM**  
SYSTEM SIZE: 8.03 KW DC  
SYSTEM SIZE: 7.6 KW AC

**TRACY STRICKLAND**  
33 GWENDOLYN WAY  
FUQUAY-VARINA, NC 27526  
(919) 274-9735

ENGINEER OF RECORD

GBR

REVISIONS			
DESCRIPTION	DATE	#	BY
RELEASED FOR PERMITTING	9/25/2020	1	GBR

SHEET SIZE

ANSI B  
11" X 17"

DATE

9/25/2020

SHEET NAME

ROOF LAYOUT &  
DETAIL DRAWINGS

SHEET NUMBER

PV-2



## Ampacity Calculations

Wiring Location: Module to Power Optimizer (Direct Current)  
 Wiring Location: Inverter to Service Entrance (Alternating Current)  
 All calculations show minimum sizing for ampacity  
 Actual wire sizing may be larger for voltage drop or other factors  
 All calculations are according to the 2017 National Electric Code

Modules: REC Alpha REC365AA  
 Inverter: SolarEdge SE7600H-US

### Initial Input Values

Isc (Short Circuit Current)	10.26					
Number of circuits	10.26	x	1	=	10.26	
Maximum Circuit Current (NEC 690.8 (A)(1+2))	10.26	x	156%	=	16.0056	
Minimum Overcurrent Device	25	A	Series Fuse Rating by Manufacturer			
	<b>Size AWG #</b>					
Chosen Conductor Type (THHN, RHW-2, or USE-2)	10					

### Conductor Derating

NEC 690.31 © ref (NEC 310.16)						
Conductor 90°C Ampacity		40				
Conduit Fill Derating	1-3	40	x	1	=	40
Temperature Derating (°F)	141-149	40	x	0.65	=	26

### Ampacity vs Overcurrent

<b>Device</b>						
Conductor Ampacity Check		26		16.0056		OK
Conductor to Overcurrent Check		26		25		OK

Input Data Into Yellow Fields  
 Green Field must say OK

Use this calculation for over current protection and wire sizing for stringers coming from Solar Panels.  
 Isc comes from manufacturer

## Ampacity Calculations

Wiring Location: Inverter to Service Entrance (Alternating Current)  
 All calculations show minimum sizing for ampacity  
 Actual wire sizing may be larger for voltage drop or other factors  
 All calculations are according to the 2017 National Electric Code

Modules: REC Alpha REC365AA  
 Inverter: SolarEdge SE7600H-US

### Initial Input Values

Inverter Continuous AC Output Combined (Watts)	7600				
Minimum Operating Voltage	240				

	Watts		Volts	=	Amps
	7600	/	240	=	32
Inverter Continuous AC Amps	32				
Number of Inverters	32	x	1	=	32

### Overcurrent Device Rating

<b>NEC 690.8 (B)(3)</b>						
Minimum Overcurrent Device	40	Amps				
Circuit Breaker Size per NEC 240.6(A)	40	Amps				
	<b>Size AWG #</b>					
Chosen Conductor Type	8					

Chosen Conductor Type  
 THHN, THWN, RHW-2 or USE-2

### Conductor Derating

NEC 690.31© ref (NEC 310.16)						
Conductor 90°C Ampacity		55				
Conduit Fill Derating	1-3	55	x	1	=	55
Temperature Derating (°F)	96-104	55	x	0.91	=	50.05

### Ampacity vs Overcurrent

<b>Device</b>						
Conductor Ampacity Check		50.05		40		OK
Conductor to Overcurrent Check		50.05		40		OK

Input Data into Yellow Fields  
 Green Fields must say OK

Use this calculation for over current protection and wire sizing for inverter

CONTRACTOR



SUN DOLLAR ENERGY, LLC  
 4904 ELAINE AVENUE  
 RALEIGH, NC 27616  
 (919) 508-6907  
 NC ELE LICENSE #: 30043U  
 NC GC LICENSE #: 73462

PROJECT & CLIENT INFORMATION

**STRICKLAND RESIDENCE**  
**NEW SOLAR PV SYSTEM**  
 SYSTEM SIZE: 8.03 KW DC  
 SYSTEM SIZE: 7.6 KW AC

**TRACY STRICKLAND**  
 33 GWENDOLYN WAY  
 FUQUAY-VARINA, NC 27526  
 (919) 274-9735

ENGINEER OF RECORD

DRAWING BY

GBR

REVISIONS

DESCRIPTION	DATE	#	BY
RELEASED FOR PERMITTING	9/25/2020	1	GBR

SHEET SIZE

ANSI B  
 11" X 17"

DATE

9/25/2020

SHEET NAME

AMPACITY  
 CALCULATIONS

SHEET NUMBER

PV-4

**SIGNAGE REQUIREMENTS**

- > WARNING SIGNS OR LABELS SHALL COMPLY WITH NEC 110.21(B)
- > MIN. 3/8" LETTER HEIGHT
- > ALL CAPITAL LETTERS
- > ARIAL OR SIMILAR FONT
- > REFLECTIVE, WEATHER RESISTANT MATERIAL, UL 969

# PV LABELS

**PHOTOVOLTAIC SYSTEM  
DC DISCONNECT**

OPERATING VOLTAGE:  VDC  
 OPERATING CURRENT:  AMPS  
 MAX SYSTEM VOLTAGE:  VDC  
 SHORT CIRCUIT CURRENT:  AMPS  
 CHARGE CONTROLLER MAX:  AMPS


NEC 690.53 1  
 APPLY TO:  
 INVERTER

**WARNING: PHOTOVOLTAIC POWER SOURCE**

NEC 690.31(G)(3)(4) 2  
 APPLY TO:  
 SOLAR DC CONDUIT

**SOLAR PV SYSTEM EQUIPPED  
WITH RAPID SHUTDOWN**

TURN RAPID SHUTDOWN SWITCH TO THE "OFF" POSITION TO SHUT DOWN PV SYSTEM AND REDUCE SHOCK HAZARD IN THE ARRAY



NEC 690.56(C)(1)(a) 3  
 APPLY TO:  
 SOLAREGE INVERTERS

**WARNING**

ELECTRIC SHOCK HAZARD  
 TERMINALS ON THE LINE AND LOAD SIDES MAY BE ENERGIZED IN THE OPEN POSITION

NEC 690.13(B) 4  
 APPLY TO:  
 DISCONNECTS  
 SOLAR LOAD CENTERS  
 COMBINER BOXES

**RAPID SHUTDOWN  
SWITCH FOR  
SOLAR PV SYSTEM**

NEC 690.5(C)(3) 5  
 APPLY TO:  
 SMA AND SOLAREGE INVERTERS

**PHOTOVOLTAIC SYSTEM  
AC DISCONNECT**

OPERATING VOLTAGE:  VDC  
 OPERATING CURRENT:  AMPS

NEC 690.54 6  
 APPLY TO:  
 AC DISCONNECT

**WARNING**

TURN OFF PHOTOVOLTAIC AC DISCONNECT PRIOR TO WORKING INSIDE PANEL

NEC 110.27(C) & OSHA 1910.145(f)(7) 7  
 APPLY TO:  
 COMBINER BOXES  
 ENCLOSURES  
 BREAKER PANEL  
 MAIN SERVICE DISCONNECT

**SOLAR PV BREAKER**

BREAKER IS BACKFED  
 DO NOT RELOCATE

NEC 690.64(B)(7) & NEC 705.12(B)(2) 8  
 APPLY TO:  
 PV SYSTEM BREAKER

**WARNING**

DUAL POWER SUPPLY  
 SOURCES: UTILITY GRID AND PV SOLAR ELECTRIC SYSTEM

NEC 705.12(D)(3) & NEC 690.64 9  
 APPLY TO:  
 MAIN SERVICE PANEL  
 METER

**DC JUNCTION BOX**

**WARNING**

ELECTRIC SHOCK HAZARD  
 THE DC CONDUCTORS OF THIS PHOTOVOLTAIC SYSTEM ARE UNGROUNDED AND MAY BE ENERGIZED

PHOTOVOLTAIC POWER SOURCE

NEC 690.31(G)(2) 10  
 APPLY TO:  
 DC JUNCTION BOXES

CONTRACTOR



**SUN DOLLAR ENERGY, LLC**  
 4904 ELAINE AVENUE  
 RALEIGH, NC 27616  
 (919) 508-6907  
 NC ELE LICENSE #: 30043U  
 NC GC LICENSE #: 73462

PROJECT & CLIENT INFORMATION

**STRICKLAND RESIDENCE  
NEW SOLAR PV SYSTEM**  
 SYSTEM SIZE: 8.03 KW DC  
 SYSTEM SIZE: 7.6 KW AC

**TRACY STRICKLAND**  
 33 GWENDOLYN WAY  
 FUQUAY-VARINA, NC 27526  
 (919) 274-9735

ENGINEER OF RECORD

DRAWING BY  
**GBR**

REVISIONS

DESCRIPTION	DATE	#	BY
RELEASED FOR PERMITTING	9/25/2020	1	GBR


SHEET SIZE  
**ANSI B  
11" X 17"**

DATE  
**9/25/2020**

SHEET NAME  
**LABELING  
SCHEDULE**

SHEET NUMBER  
**PV-5**

SOLAR'S MOST TRUSTED



# REC ALPHA SERIES

380 W<sub>P</sub> POWER

20 YEAR PRODUCT WARRANTY


25 YEAR POWER OUTPUT WARRANTY



[recgroup.com/alpha](http://recgroup.com/alpha)

# REC ALPHA SERIES

## PRODUCT DATASHEET



### GENERAL DATA

Cell type:	120 half-cut cells with REC heterojunction cell technology 6 strings of 20 cells in series	Junction box:	3-part, 3 bypass diodes, IP67 rated in accordance with IEC 62790
Glass:	0.13 in (3.2 mm) solar glass with anti-reflection surface treatment	Cable:	12 AWG (4 mm <sup>2</sup> ) PV wire, 39 + 47 in (1 + 1.2 m) in accordance with EN 50618
Backsheet:	Highly resistant polymeric construction	Connectors:	Stäubli MC4PV-KBT4/KST4, 12 AWG (4 mm <sup>2</sup> ) in accordance with IEC 62852 IP68 only when connected
Frame:	Anodized aluminum (black)	Origin:	Made in Singapore

### ELECTRICAL DATA @ STC

Product Code\*: RECxxxAA

	360	365	370	375	380
Nominal Power - P <sub>MPP</sub> (Wp)	360	365	370	375	380
Watt Class Sorting - (W)	-0/+5	-0/+5	-0/+5	-0/+5	-0/+5
Nominal Power Voltage - V <sub>MPP</sub> (V)	37.7	38.0	38.3	38.7	39.0
Nominal Power Current - I <sub>MPP</sub> (A)	9.55	9.60	9.66	9.72	9.76
Open Circuit Voltage - V <sub>OC</sub> (V)	44.1	44.3	44.5	44.6	44.7
Short Circuit Current - I <sub>SC</sub> (A)	10.23	10.26	10.30	10.40	10.46
Panel Efficiency (%)	20.6	20.9	21.2	21.4	21.7

Values at standard test conditions (STC: air mass AM1.5, irradiance 10.75 W/sq ft (1000 W/m<sup>2</sup>), temperature 77°F (25°C), based on a production spread with a tolerance of V<sub>OC</sub> & I<sub>SC</sub> ±3% within one watt class. \*Where xxx indicates the nominal power class (P<sub>MPP</sub>) at STC above.

### ELECTRICAL DATA @ NMOT

Product Code\*: RECxxxAA

	274	278	282	286	290
Nominal Power - P <sub>MPP</sub> (Wp)	274	278	282	286	290
Nominal Power Voltage - V <sub>MPP</sub> (V)	35.5	35.8	36.1	36.4	36.7
Nominal Power Current - I <sub>MPP</sub> (A)	7.71	7.76	7.80	7.85	7.88
Open Circuit Voltage - V <sub>OC</sub> (V)	41.6	41.7	41.9	42.0	42.1
Short Circuit Current - I <sub>SC</sub> (A)	8.26	8.29	8.32	8.40	8.45

Nominal module operating temperature (NMOT: air mass AM1.5, irradiance 800 W/m<sup>2</sup>, temperature 68°F (20°C), windspeed 3.3 ft/s (1 m/s). \*Where xxx indicates the nominal power class (P<sub>MPP</sub>) at STC above.

### CERTIFICATIONS

IEC 61215:2016, IEC 61730:2016, UL 1703, UL 61730	
IEC 62804	PID
IEC 61701	Salt Mist
IEC 62716	Ammonia Resistance
UL 1703	Fire Type Class 2
IEC 62782	Dynamic Mechanical Load
IEC 61215-2:2016	Hailstone (35mm)
AS4040.2 NCC 2016	Cyclic Wind Load
ISO 14001:2004, ISO 9001:2015, OHSAS 18001:2007	



### WARRANTY

20 year product warranty  
25 year linear power output warranty  
Maximum annual power degradation of 0.25% p.a.  
Guarantees 92% of power after 25 years  
See warranty conditions for further details.

### MECHANICAL DATA

Dimensions:	678 x 40 x 1.2 in (1721 x 1016 x 30 mm)
Area:	18.8 sq ft (1.75 m <sup>2</sup> )
Weight:	43 lbs (19.5 kg)

### MAXIMUM RATINGS

Operational temperature:	-40 ... +85°C
Maximum system voltage:	1000 V
Design load (+): snow	4666 Pa (97.5 lbs/sq ft)*
Maximum test load (+):	7000 Pa (146 lbs/sq ft)*
Design load (-): wind	2666 Pa (55.6 lbs/sq ft)*
Maximum test load (-):	4000 Pa (83.5 lbs/sq ft)*
Max series fuse rating:	25 A
Max reverse current:	25 A

\* Calculated using a safety factor of 1.5  
\* See installation manual for mounting instructions


### TEMPERATURE RATINGS\*

Nominal Module Operating Temperature:	44°C (±2°C)
Temperature coefficient of P <sub>MPP</sub> :	-0.26 %/°C
Temperature coefficient of V <sub>OC</sub> :	-0.24 %/°C
Temperature coefficient of I <sub>SC</sub> :	0.04 %/°C

\*The temperature coefficients stated are linear values

### LOW LIGHT BEHAVIOUR

Typical low irradiance performance of module at STC:



Founded in Norway in 1996, REC is a leading vertically integrated solar energy company. Through integrated manufacturing from silicon to wafers, cells, high-quality panels and extending to solar solutions, REC provides the world with a reliable source of clean energy. REC's renowned product quality is supported by the lowest warranty claims rate in the industry. REC is a Bluestar Elkem company with headquarters in Norway and operational headquarters in Singapore. REC employs around 2,000 people worldwide, producing 1.5 GW of solar panels annually.





# Single Phase Inverter with HD-Wave Technology

for North America

SE3000H-US / SE3800H-US / SE5000H-US / SE6000H-US /  
SE7600H-US / SE10000H-US / SE11400H-US



## Optimized installation with HD-Wave technology

- / Specifically designed to work with power optimizers
- / Record-breaking efficiency
- / Quick and easy inverter commissioning directly from a smartphone using the SolarEdge SetApp
- / Fixed voltage inverter for longer strings
- / Integrated arc fault protection and rapid shutdown for NEC 2014 and 2017, per article 690.11 and 690.12
- / UL1741 SA certified, for CPUC Rule 21 grid compliance
- / Extremely small
- / Built-in module-level monitoring
- / Outdoor and indoor installation
- / Optional: Revenue grade data, ANSI C12.20 Class 0.5 (0.5% accuracy)

# / Single Phase Inverter with HD-Wave Technology for North America

SE3000H-US / SE3800H-US / SE5000H-US / SE6000H-US/  
SE7600H-US / SE10000H-US / SE11400H-US

Model Number	SE3000H-US	SE3800H-US	SE5000H-US	SE6000H-US	SE7600H-US	SE10000H-US	SE11400H-US	
APPLICABLE TO INVERTERS WITH PART NUMBER	SEXXXXH-XXXXXBXX4							
<b>OUTPUT</b>								
Rated AC Power Output	3000	3800 @ 240V 3300 @ 208V	5000	6000 @ 240V 5000 @ 208V	7600	10000	11400 @ 240V 10000 @ 208V	VA
Maximum AC Power Output	3000	3800 @ 240V 3300 @ 208V	5000	6000 @ 240V 5000 @ 208V	7600	10000	11400 @ 240V 10000 @ 208V	VA
AC Output Voltage Min.-Nom.-Max. (211 - 240 - 264)	✓	✓	✓	✓	✓	✓	✓	Vac
AC Output Voltage Min.-Nom.-Max. (183 - 208 - 229)	-	✓	-	✓	-	-	✓	Vac
AC Frequency (Nominal)	59.3 - 60 - 60.5 <sup>(1)</sup>							Hz
Maximum Continuous Output Current @240V	12.5	16	21	25	32	42	47.5	A
Maximum Continuous Output Current @208V	-	16	-	24	-	-	48.5	A
Power Factor	1, adjustable -0.85 to 0.85							
GFDI Threshold	1							A
Utility Monitoring, Islanding Protection, Country Configurable Thresholds	Yes							
<b>INPUT</b>								
Maximum DC Power @240V	4650	5900	7750	9300	11800	15500	17650	W
Maximum DC Power @208V	-	5100	-	7750	-	-	15500	W
Transformer-less, Ungrounded	Yes							
Maximum Input Voltage	480							Vdc
Nominal DC Input Voltage	380				400			Vdc
Maximum Input Current @240V <sup>(2)</sup>	8.5	10.5	13.5	16.5	20	27	30.5	Adc
Maximum Input Current @208V <sup>(2)</sup>	-	9	-	13.5	-	-	27	Adc
Max. Input Short Circuit Current	45							Adc
Reverse-Polarity Protection	Yes							
Ground-Fault Isolation Detection	600k $\Omega$ Sensitivity							
Maximum Inverter Efficiency	99	99.2						%
CEC Weighted Efficiency	99						99 @ 240V 98.5 @ 208V	%
Nighttime Power Consumption	< 2.5							W

<sup>(1)</sup> For other regional settings please contact SolarEdge support

<sup>(2)</sup> A higher current source may be used; the inverter will limit its input current to the values stated

---

# Power Optimizer

For North America

P320 / P340 / P370 / P400 / P405 / P505

POWER OPTIMIZER



## PV power optimization at the module-level

- Specifically designed to work with SolarEdge inverters
- Up to 25% more energy
- Superior efficiency (99.5%)
- Mitigates all types of module mismatch losses, from manufacturing tolerance to partial shading
- Flexible system design for maximum space utilization
- Fast installation with a single bolt
- Next generation maintenance with module-level monitoring
- Meets NEC requirements for arc fault protection (AFCI) and Photovoltaic Rapid Shutdown System (PVRSS)
- Module-level voltage shutdown for installer and firefighter safety

# / Power Optimizer

## For North America

P320 / P340 / P370 / P400 / P405 / P505

Optimizer model (typical module compatibility)	P320 (for 60-cell modules)	P340 (for high-power 60-cell modules)	P370 (for higher-power 60 and 72-cell modules)	P400 (for 72 & 96-cell modules)	P405 (for thin film modules)	P505 (for higher current modules)	
<b>INPUT</b>							
Rated Input DC Power <sup>(1)</sup>	320	340	370	400	405	505	W
Absolute Maximum Input Voltage (Voc at lowest temperature)	48		60	80	125 <sup>(2)</sup>		Vdc
MPPT Operating Range	8 - 48		8 - 60	8 - 80	12.5 - 105		Vdc
Maximum Short Circuit Current (Isc)	11			10.1		14	Adc
Maximum DC Input Current	13.75			12.63		17.5	Adc
Maximum Efficiency	99.5						%
Weighted Efficiency	98.8					98.6	%
Overvoltage Category	II						
<b>OUTPUT DURING OPERATION (POWER OPTIMIZER CONNECTED TO OPERATING SOLAREEDGE INVERTER)</b>							
Maximum Output Current	15						Adc
Maximum Output Voltage	60			85			Vdc
<b>OUTPUT DURING STANDBY (POWER OPTIMIZER DISCONNECTED FROM SOLAREEDGE INVERTER OR SOLAREEDGE INVERTER OFF)</b>							
Safety Output Voltage per Power Optimizer	1 ± 0.1						Vdc
<b>STANDARD COMPLIANCE</b>							
EMC	FCC Part15 Class B, IEC61000-6-2, IEC61000-6-3						
Safety	IEC62109-1 (class II safety), UL1741						
RoHS	Yes						
<b>INSTALLATION SPECIFICATIONS</b>							
Maximum Allowed System Voltage	1000						Vdc
Compatible inverters	All SolarEdge Single Phase and Three Phase inverters						
Dimensions (W x L x H)	129 x 153 x 27.5 / 5.1 x 6 x 1.1			129 x 153 x 33.5 / 5.1 x 6 x 1.3	129 x 159 x 49.5 / 5.1 x 6.3 x 1.9	129 x 162 x 59 / 5.1 x 6.4 x 2.3	mm / in
Weight (including cables)	630 / 1.4			750 / 1.7	845 / 1.9	1064 / 2.3	gr / lb
Input Connector	MC4 <sup>(3)</sup>						
Output Wire Type / Connector	Double Insulated; MC4						
Output Wire Length	0.95 / 3.0		1.2 / 3.9				m / ft
Input Wire Length	0.16 / 0.52						m / ft
Operating Temperature Range	-40 - +85 / -40 - +185						°C / °F
Protection Rating	IP68 / NEMA6P						
Relative Humidity	0 - 100						%

<sup>(1)</sup> Rated STC power of the module. Module of up to +5% power tolerance allowed

<sup>(2)</sup> NEC 2017 requires max input voltage be not more than 80V

<sup>(3)</sup> For other connector types please contact SolarEdge

PV System Design Using a SolarEdge Inverter <sup>(4)(5)</sup>	Single Phase HD-Wave	Single phase	Three Phase 208V	Three Phase 480V	
Minimum String Length (Power Optimizers)	P320, P340, P370, P400 P405 / P505	8	10	18	
Maximum String Length (Power Optimizers)		6	8	14	
Maximum String Length (Power Optimizers)		25	25	50 <sup>(6)</sup>	
Maximum Power per String	5700 (6000 with SE7600-US - SE11400-US)	5250	6000 <sup>(7)</sup>	12750 <sup>(8)</sup>	W
Parallel Strings of Different Lengths or Orientations	Yes				

<sup>(4)</sup> For detailed string sizing information refer to: [http://www.solaredge.com/sites/default/files/string\\_sizing\\_na.pdf](http://www.solaredge.com/sites/default/files/string_sizing_na.pdf)

<sup>(5)</sup> It is not allowed to mix P405/P505 with P320/P340/P370/P400 in one string

<sup>(6)</sup> A string with more than 30 optimizers does not meet NEC rapid shutdown requirements; safety voltage will be above the 30V requirement

<sup>(7)</sup> For SE14.4KUS/SE43.2KUS: It is allowed to install up to 6,500W per string when 3 strings are connected to the inverter (3 strings per unit for SE43.2KUS) and when the maximum power difference between the strings is up to 1,000W

<sup>(8)</sup> For SE30KUS/SE33.3KUS/SE66.6KUS/SE100KUS: It is allowed to install up to 15,000W per string when 3 strings are connected to the inverter (3 strings per unit for SE66.6KUS/SE100KUS) and when the maximum power difference between the strings is up to 2,000W

# Energy Meter with Modbus Connection

for North America

SE-MTR240-NN-S-S1

METERING



## Energy Meter for Residential Installations:

- Simple installations and connectivity
- Type NEMA 3R enclosure for outdoor protection
- Provides high accuracy meter readings
- Communicates over RS485 to provide monitoring data
- Suitable for export limitation, consumption monitoring and StorEdge™ applications

# / Energy Meter with Modbus Connection for North America


## SE-MTR240-NN-S-S1

SUPPORTED INVERTERS	SINGLE PHASE INVERTERS		UNITS
<b>ELECTRICAL SERVICE</b>			
AC Input Voltage (Nominal)	240		Vac
AC Frequency (Nominal)	60		Hz
Max AC Input Current	100		mA
Connector Type	Terminal block - 22 to 12		AWG
Grids supported	L1 / L2 / N / PE L1 / L2 / PE		
Power Consumption (Nominal)	3		W
<b>METER ACCURACY (@ 77°F / 25°C, PF:0.7- 1)</b>			
1 - 100% of Rated Current CT	±1.0		%
<b>CURRENT TRANSFORMERS<sup>(1)</sup></b>			
Nominal Input (at CT Rated Current)	CT1, CT2: 0.333		Vac RMS
Rated RMS current <sup>(2)</sup>	200	400	A
Dimensions (Internal / External)	0.8 x 0.8; 2.4 x 2.4 / 20 x 20; 61 x 61	1.26 x 1.83; 3.3 x 4.5 / 32 x 46.5; 83.4 x 114	in/mm
<b>STANDARD COMPLIANCE</b>			
Safety	UL 1741:2010 Ed.2(Supplement SA)+R: 07 Sep 2016		
Emissions	FCC 47 CFR Part 15 Subpart B		
<b>ENVIRONMENTAL</b>			
Operating Temperatures	-40 to +140 / -40 to +60		°F / °C
Relative Humidity (noncondensing)	5-90		%
Enclosure type	High impact, ABS and/or ABS/PC plastic UL 94V-0, IEC FV-0		
Protection Rating	NEMA Type 3R		
<b>INSTALLATION SPECIFICATIONS</b>			
Dimensions (HxWxD)	8.1 x 12.4 x 4.6 / 206.6 x 316 x 117.5		in / mm
Weight	3.9 / 1.8		lb / kg
Conduit Entry Diameters	0.75 or 1 / 19 or 25		in
Mounting Type	Bracket mount		


<sup>(1)</sup> Current Transformers should be ordered separately: SEACT0750-200NA-20 (200A) or SEACT1250-400NA-20 (400A), 20 per box

<sup>(2)</sup> For other ratings contact SolarEdge

### Current Transformer Dimensions




### Connecting the Energy Meter



\* Current Transformers (CTs) should be ordered separately: SEACT0750-200NA-20 (200A); SEACT1250-400NA-20 (400A). Each comes in boxes of 20.



# L-Mount® Series



The L-Mount® Series is designed for cost-effective, one-bolt installation onto existing composition/asphalt shingle roofs. Quick Mount PV engineered its patented Elevated Water Seal Technology® into an integrated L-foot and flashing for super-fast, single-lag bolt installation with unparalleled waterproofing. The L-Mount comes with a lag bolt or structural screw for attachment versatility and works with all leading racks. The L-Mount features a 9" x 12" aluminum flashing with alignment guides and rounded corners to easily slide under shingles and speed installation on the roof.

## FEATURES

- L-foot can be rotated 360 degree for optimal adjustability
- Works with all leading racks
- Available with lag bolt or structural screw
- QBlock® Elevated Water Seal Technology®
- Single bolt installation, no shingle cutting
- 9" x 12" aluminum flashing
- Meets or exceeds roofing industry best practices; 100% IBC compliant
- 18-8 stainless steel hardware included
- Alignment guides
- 25-year warranty






## SINGLE-SLOT L-MOUNT

Available finishes:  
aluminum mill (A); black (B)



# Mounting systems for solar technology



EVEREST SOLAR SYSTEMS  
**RESIDENTIAL ROOF SOLUTIONS**  
**CROSSRAIL SYSTEM**

Everest Solar Systems, LLC  
3809 Ocean Ranch Blvd., Suite 111  
Oceanside, CA 92056  
Service-Hotline +1.760.301.5300  
info@everest-solarsystems.com  
www.everest-solarsystems.com


# CROSSRAIL SYSTEM




- ▶ High quality, German-engineered system optimized for residential installation
- ▶ MK3 mounting hardware simplifies module installation – fast, easy, and secure
- ▶ Easily integrates with third party roof attachment products
- ▶ L-foot provides adjustability and compatibility with common roof types
- ▶ 100% code-compliant, structural validation for all solar states
- ▶ Three rail sizes available to suit all structural conditions
- ▶ Most components also available in dark
- ▶ Fast installation with minimal component count result in low total installed cost
- ▶ Simple to design using code compliant Everest Online Design Tool
- ▶ Use two innovative components to turn this system into Shared Rail or Tilt Up

## TECHNICAL DATA

Applicable roof types	Composition shingle, tile, flat tile
Flexibility	Modular construction, suitable for any system size, height adjustable
PV modules	For all common module types
Module orientation	Portrait and landscape
Material	High corrosion resistance, stainless steel and high grade aluminum
Roof attachment	Screw connection into rafter
Structural validity	IBC compliant, stamped engineering letters available for all solar states
Warranty	20 years
System components	CrossRail 48-X/48-XL/80, L-Foot, Mid and End Clamp Sets



CrossRail Structural Splice



CrossRail with EverFlash, Rail Sleeve and End Cap



Bonding Mid Clamp | End Clamp | Micro, Optimizer & Accs Mounting Kit