

SHEET CATALOG

| INDEX NO. | DESCRIPTION |
|-----------|-----------------------|
| T-1 | COVER PAGE |
| M-1 | MOUNTING DETAIL |
| M-2 | STRUCTURAL DETAIL |
| E-1 | SINGLE LINE DIAGRAM |
| E-2 | THREE LINE DIAGRAM |
| E-3 | STRING WIRING DIAGRAM |
| PL-1 | WARNING PLACARDS |
| PL-2 | SAFETY PLANS |
| SS | SPEC SHEET(S) |

SCOPE OF WORK

GENERAL SYSTEM INFORMATION:
 SYSTEM SIZE:
 7920W DC, 6000W AC
 MODULES:
 (24)TITAN SOLAR SIL-330NL
 INVERTER:
 (1)SOLAREDEGE TECHNOLOGIES SE6000H-US
 (240V)
 OPTIMIZER:
 (24)SOLAREDEGE P340 POWER OPTIMIZER

APPLICABLE CODES



- ELECTRIC CODE:NEC 2017
- FIRE CODE:IFC 2018
- BUILDING CODE:IBC 2018
- RESIDENTIAL CODE:IRC 2018

GENERAL NOTES

- 1.MODULES ARE LISTED UNDER UL 1703 AND CONFORM TO THE STANDARDS.
- 2.INVERTERS ARE LISTED UNDER UL 1741 AND CONFORM TO THE STANDARDS.
- 3.DRAWINGS ARE DIAGRAMMATIC, INDICATING GENERAL ARRANGEMENT OF THE PV SYSTEM AND THE ACTUAL SITE CONDITION MIGHT VARY.
- 4.WORKING CLEARANCES AROUND THE NEW PV ELECTRICAL EQUIPMENT WILL BE MAINTAINED IN ACCORDANCE WITH NEC 110.26.
- 5.ALL GROUND WIRING CONNECTED TO THE MAIN SERVICE GROUNDING IN MAIN SERVICE PANEL/ SERVICE EQUIPMENT.
- 6.ALL CONDUCTORS SHALL BE 600V, 75°C STANDARD COPPER UNLESS OTHERWISE NOTED.
- 7.WHEN REQUIRED, A LADDER SHALL BE IN PLACE FOR INSPECTION IN COMPLIANCE WITH OSHA REGULATIONS.
- 8.THE SYSTEM WILL NOT BE INTERCONNECTED BY THE CONTRACTOR UNTIL APPROVAL FROM THE LOCAL JURISDICTION AND/OR THE UTILITY.
- 9.ROOF ACCESS POINT SHALL BE LOCATED IN AREAS THAT DO NOT REQUIRE THE PLACEMENT OF GROUND LADDERS OVER OPENINGS SUCH AS WINDOWS OR DOORS, AND LOCATED AT STRONG POINTS OF BUILDING CONSTRUCTION WHERE THE ACCESS POINT DOES NOT CONFLICT WITH OVERHEAD OBSTRUCTIONS SUCH AS TREES, WIRES OR SIGNS.
- 10.PV ARRAY COMBINER/JUNCTION BOX PROVIDES TRANSITION FROM ARRAY WIRING TO CONDUIT WIRING

BRYCE KRYTUSA - 7.920kW DC, 6.000kW AC


SITE PLAN LAYOUT



SCALE:1/32" = 1'-0"

NOTE: NO GATE OR FENCE

VICINITY MAP



ADDRESS: 525W, BASELINE RD
 MESA AZ,85210

CUSTOMER INFORMATION

NAME:BRYCE KRYTUSA

ADDRESS:524 MINERAL SPRINGS LANE,
 FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ:NC-COUNTY HARNETT

UTILITY:DUKE ENERGY

PRN NUMBER:TPS-013801



COVER PAGE

DESIGNER /CHECKED
 BY: RB/AJ

PAPER SIZE:17"X11"

SCALE:AS NOTED

REV:A

DATE:9/22/2020

T-1


INSTALLATION NOTES

- 1.STRUCTURAL ROOF MEMBER LOCATIONS ARE ESTIMATED AND SHOULD BE LOCATED AND VERIFIED BY THE CONTRACTOR WHEN LAG BOLT PENETRATION OR MECHANICAL ATTACHMENT TO THE STRUCTURE IS REQUIRED.
- 2.ROOFTOP PENETRATIONS FOR SOLAR RACKING WILL BE COMPLETED AND SEALED WITH APPROVED SEALANT PER CODE BY A LICENSED CONTRACTOR.
- 3.LAGS MUST HAVE A MINIMUM 2.5" THREAD EMBEDMENT INTO THE STRUCTURAL MEMBER.
- 4.ALL PV RACKING ATTACHMENTS SHALL BE STAGGERED BY ROW BETWEEN THE ROOF FRAMING MEMBERS AS NECESSARY.
- 5.ROOF MOUNTED STANDARD RAIL REQUIRES ONE THERMAL EXPANSION GAP FOR EVERY RUN OF RAIL GREATER THAN 40'.
- 6.ALL CONDUCTORS AND CONDUITS ON THE ROOF SHALL BE MINIMUM 2.5" ABOVE THE ROOF SURFACE (INCLUDING CABLES UNDERNEATH MODULES AND RACKING).
- 7.THE PV INSTALLATION SHALL NOT OBSTRUCT ANY PLUMBING, MECHANICAL OR BUILDING ROOF VENTS.

SITE INFORMATION - WIND SPEED: 117 MPH AND SNOW LOAD: 15 PSF

| SR. NO | AZIMUTH | PITCH | NO. OF MODULES | ARRAY AREA (SQ. FT.) | ROOF TYPE | ATTACHMENT | ROOF EXPOSURE | FRAME TYPE | FRAME SIZE | FRAME SPACING | MAX RAIL SPAN | OVER HANG |
|--------|---------|-------|----------------|----------------------|---------------------|-------------|---------------|------------------------|------------|---------------|---------------|-----------|
| MP-01 | 176° | 18° | 17 | 311.2 | COMPOSITION SHINGLE | QUICK MOUNT | ATTIC | PRE-FABRICATED TRUSSES | 2 X 4 | 2'-0" | 4'-0" | 2'-0" |
| MP-02 | 356° | 18° | 7 | 128.1 | COMPOSITION SHINGLE | QUICK MOUNT | ATTIC | PRE-FABRICATED TRUSSES | 2 X 4 | 2'-0" | 4'-0" | 2'-0" |

NOTE: PENETRATIONS ARE STAGGERED



SCALE: 1/8" = 1'-0"



ADDRESS: 525W, BASELINE RD
MESA AZ,85210

CUSTOMER INFORMATION

NAME: BRYCE KRYTUSA

ADDRESS: 524 MINERAL SPRINGS LANE,
FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ: NC-COUNTY HARNETT

UTILITY: DUKE ENERGY

PRN NUMBER: TPS-013801



MOUNTING DETAIL

DESIGNER /CHECKED
BY: RB/AJ

PAPER SIZE: 17"X11"


SCALE: AS NOTED

REV: A



DATE: 9/22/2020

M-1

| DEAD LOAD CALCULATIONS | | | |
|---|----------|----------|--------------------|
| BOM | QUANTITY | LBS/UNIT | TOTAL WEIGHT (LBS) |
| MODULES | 24 | 40.1 | 962.40 |
| MID-CLAMP | 28 | 0.050 | 1.40 |
| END-CLAMP | 40 | 0.050 | 2.00 |
| RAIL LENGTH | 250 | 0.680 | 170.00 |
| SPLICE BAR | 6 | 0.360 | 2.16 |
| QUICK MOUNT | 79 | 1.04 | 82.16 |
| TOTAL WEIGHT OF THE SYSTEM (LBS) | | | 1220.12 |
| TOTAL ARRAY AREA ON THE ROOF (SQ. FT.) | | | 439.31 |
| WEIGHT PER SQ. FT.(LBS) | | | 2.78 |
| WEIGHT PER PENETRATION (LBS) | | | 15.44 |






| MODULES DATA | |
|-----------------------|------------------------------|
| TITAN SOLAR SIL-330NL | |
| MODULE DIMS | 66.9"x39.4"x1.5" |
| LAG SCREWS | 5/16"x3.5":2.5"MIN EMBEDMENT |
| UPLIFT CALCULATIONS | |
| UPLIFT | 13179.3 LBS |
| PULL OUT STRENGTH | 48585 LBS |
| POINT LOADING | 12 LBS |



ADDRESS: 525W, BASELINE RD
MESA AZ,85210

GROUNDING DETAILS



CUSTOMER INFORMATION

NAME: BRYCE KRYTUSA

ADDRESS: 524 MINERAL SPRINGS LANE,
FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ: NC-COUNTY HARNETT

UTILITY: DUKE ENERGY

PRN NUMBER: TPS-013801

| STRUCTURAL DETAIL | |
|-----------------------------|---------------------|
| DESIGNER /CHECKED BY: RB/AJ | PAPER SIZE: 17"X11" |
| SCALE: AS NOTED | REV: A |
| DATE: 9/22/2020 | M-2 |

SINGLE LINE DIAGRAM: DC SYSTEM SIZE - 7920W, AC SYSTEM SIZE - 6000W

ELECTRICAL NOTES

| INVERTER-1 SPECIFICATIONS | | MODULE SPECIFICATION | | OPTIMIZER CHARACTERISTICS | | SYSTEM CHARACTERISTICS | |
|---------------------------|---|-----------------------------------|-----------------------|---------------------------|--------|---|--------|
| MODEL | SOLAREEDGE TECHNOLOGIES SE6000H-US (240V) | MODEL | TITAN SOLAR SIL-330NL | MODEL | P340 | DC SYSTEM SIZE | 7920 W |
| POWER RATING | 6000W | MODULE POWER @ STC | 330W | MIN INPUT VOLTAGE | 8 VDC | INVERTER STRING VOLTAGE: Vmp | 380V |
| MAX OUTPUT CURRENT | 25A | OPEN CIRCUIT VOLTAGE: Voc | 40.5V | MAX INPUT VOLTAGE | 48 VDC | MAX INVERTER SYSTEM VOLTAGE: Voc | 480V |
| CEC WEIGHTED EFFICIENCY | 99% | MAX POWER VOLTAGE: Vmp | 33.3V | MAX INPUT CURRENT | 11 ADC | MAX SHORT CIRCUIT CURRENT | 15A |
| MAX INPUT CURRENT | 16.5A | SHORT CIRCUIT VOLTAGE: Isc | 10.42A | MAX OUTPUT CURRENT | 15 ADC | OPERATING CURRENT | 10.42A |
| MAX DC VOLTAGE | 480V | MAX POWER CURRENT: Imp | 9.92A | | | | |

- 1.CONDUCTORS EXPOSED TO SUNLIGHT SHALL BE LISTED AS SUNLIGHT RESISTANT PER NEC 310.10(D).
- 2.CONDUCTORS EXPOSED TO WET LOCATIONS SHALL BE SUITABLE FOR USE IN WET LOCATIONS PER NEC 310.10(C).
- 3.MAXIMUM DC/AC VOLTAGE DROP SHALL BE NO MORE THAN 2%.
- 4.ALL CONDUCTORS SHALL BE IN CONDUIT UNLESS OTHERWISE NOTED.
- 5.BREAKER/FUSE SIZES CONFORMS TO NEC 240.6 CODE SECTION.
- 6.AC GROUNDING ELECTRODE CONDUCTOR SIZED PER NEC 250.66.
- 7.AMBIENT TEMPERATURE CORRECTION FACTOR IS BASED ON NEC 690.31(C).
- 8.AMBIENT TEMPERATURE ADJUSTMENT FACTOR IS BASED ON NEC 310.15(B)(2).
- 9.MAX. SYSTEM VOLTAGE CORRECTION IS PER NEC 690.7.
- 10.CONDUCTORS ARE SIZED PER WIRE AMPACITY TABLE NEC 310.15(B)(16).



ADDRESS: 525W, BASELINE RD
MESA AZ,85210

CUSTOMER INFORMATION

NAME: BRYCE KRYTUSA


ADDRESS: 524 MINERAL SPRINGS LANE,
FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ: NC-COUNTY HARNETT

UTILITY: DUKE ENERGY

PRN NUMBER: TPS-013801



CONDUIT SCHEDULE

| TAG ID | CONDUIT SIZE | CONDUCTOR | NEUTRAL | GROUND |
|--------|------------------|-----------------------|----------------------|-----------------------|
| 1 | NONE | (4) 10AWG PV WIRE | NONE | (1) 10AWG BARE COPPER |
| 2 | 3/4"EMT OR EQUIV | (4) 10AWG THHN/THWN-2 | NONE | (1) 10AWG THHN/THWN-2 |
| 3 | 3/4"EMT OR EQUIV | (2) 8AWG THHN/THWN-2 | (1) 8AWG THHN/THWN-2 | (1) 10AWG THHN/THWN-2 |

NOTE:
MAIN PANEL RATING: 225A, MAIN BREAKER RATING: 200A
120% RULE: (225A x 1.2) - 200A = 70A => ALLOWABLE BACKFEED IS 70A

OCPD CALCULATIONS:
INVERTER OVERCURRENT PROTECTION = INVERTER O/P I X CONTINUOUS LOAD (1.25)
= 25 x 1.25 = 31.25A => PV BREAKER = 35A
ALLOWABLE BACKFEED 70A => 35A PV BREAKER
THE DESIGNED INTERCONNECTION MEETS THE 705.12(B)(2) REQUIREMENTS.

ELECTRICAL CALCULATIONS

DC WIRE SIZING CALCULATIONS BASED OF FOLLOWING EQUATIONS >>

- REQUIRED CONDUCTOR AMPACITY: 125% PER 690.8(A)(1) X I_{sc}(A) X # OF PARALLEL STRINGS = MAX CURRENT PER 690.8(A)(1) X 125% PER 690.8(B)(2)(a) = MAX CURRENT PER 690.8(B)(2)(a)
- CORRECTED AMPACITY CALCULATIONS: AMPACITY X TEMPERATURE DERATE FACTOR X CONDUIT FILL DERATE = DERATED CONDUCTOR AMPACITY
- DERATED CONDUCTOR AMPACITY CHECK: MAX CURRENT PER 690.8(B)(2)(2) < DERATED CONDUCTOR AMPACITY

AC WIRE SIZING CALCULATIONS BASED OF FOLLOWING EQUATIONS >>

- REQUIRED CONDUCTOR AMPACITY: INVERTER OUTPUT CURRENT X # OF INVERTERS X MAX CURRENT PER 690.8(A)(3) X 125% PER 690.8(B)(2)(A)
- CORRECTED AMPACITY CALCULATIONS: AMPACITY X TEMPERATURE DERATE FACTOR X CONDUIT FILL DERATE = DERATED CONDUCTOR AMPACITY
- DERATED CONDUCTOR AMPACITY CHECK: MAX CURRENT PER 690.8(B)(2)(2) < DERATED CONDUCTOR AMPACITY

DC WIRE CALCULATIONS:- MATERIAL: COPPER & TEMPERATURE RATING: 90°C

| TAG ID | REQUIRED CONDUCTOR AMPACITY | | | | | | | CORRECTED AMPACITY CALCULATION | | | | | | | DERATED CONDUCTOR AMPACITY CHECK | | | | | | |
|--------|-----------------------------|---|----|---|---|---|----|--------------------------------|------|---|--------|----|---|------|----------------------------------|-----|---|--------|--------|---|--------|
| 1 | 1 | X | 15 | X | 1 | = | 15 | X | 1.25 | = | 18.75A | 40 | X | 0.71 | X | 0.8 | = | 22.72A | 18.75A | < | 22.72A |
| 2 | 1 | X | 15 | X | 1 | = | 15 | X | 1.25 | = | 18.75A | 40 | X | 0.71 | X | 0.8 | = | 22.72A | 18.75A | < | 22.72A |

AC WIRE CALCULATIONS:- MATERIAL: COPPER & TEMPERATURE RATING: 90°C

| TAG ID | REQUIRED CONDUCTOR AMPACITY | | | | | | | CORRECTED AMPACITY CALCULATION | | | | | | | DERATED CONDUCTOR AMPACITY CHECK | | | | |
|--------|-----------------------------|---|---|---|----|---|------|--------------------------------|--------|----|---|------|---|---|----------------------------------|--------|--------|---|--------|
| 3 | 25 | X | 1 | = | 25 | X | 1.25 | = | 31.25A | 55 | X | 0.87 | X | 1 | = | 47.85A | 31.25A | < | 47.85A |



SINGLE LINE DIAGRAM

DESIGNER /CHECKED BY: RB/AJ PAPER SIZE: 17"X11"

SCALE: AS NOTED REV: A


DATE: 9/22/2020 E-1

THREE LINE DIAGRAM: DC SYSTEM SIZE - 7920W, AC SYSTEM SIZE - 6000W

ELECTRICAL NOTES

| INVERTER-1 SPECIFICATIONS | | MODULE SPECIFICATION | | OPTIMIZER CHARACTERISTICS | | SYSTEM CHARACTERISTICS | |
|---------------------------|---|-----------------------------------|-----------------------|---------------------------|-------------|---|--------|
| MODEL | SOLAREDEGE TECHNOLOGIES SE6000H-US (240V) | MODEL | TITAN SOLAR SIL-330NL | MODEL | P340 | DC SYSTEM SIZE | 7920 W |
| POWER RATING | 6000W | MODULE POWER @ STC | 330W | MIN INPUT VOLTAGE | 8 VDC | INVERTER STRING VOLTAGE: Vmp | 380V |
| MAX OUTPUT CURRENT | 25A | OPEN CIRCUIT VOLTAGE: Voc | 40.5V | MAX INPUT VOLTAGE | 48 VDC | MAX INVERTER SYSTEM VOLTAGE: Voc | 480V |
| CEC WEIGHTED EFFICIENCY | 99% | MAX POWER VOLTAGE: Vmp | 33.3V | MAX INPUT CURRENT | 11 ADC | MAX SHORT CIRCUIT CURRENT | 15A |
| MAX INPUT CURRENT | 16.5A | SHORT CIRCUIT VOLTAGE: Isc | 10.42A | MAX OUTPUT CURRENT | 15 ADC | OPERATING CURRENT | 10.42A |
| MAX DC VOLTAGE | 480V | MAX POWER CURRENT: Imp | 9.92A | | | | |

- 1.CONDUCTORS EXPOSED TO SUNLIGHT SHALL BE LISTED AS SUNLIGHT RESISTANT PER NEC 310.10(D).
- 2.CONDUCTORS EXPOSED TO WET LOCATIONS SHALL BE SUITABLE FOR USE IN WET LOCATIONS PER NEC 310.10(C).
- 3.MAXIMUM DC/AC VOLTAGE DROP SHALL BE NO MORE THAN 2%.
- 4.ALL CONDUCTORS SHALL BE IN CONDUIT UNLESS OTHERWISE NOTED.
- 5.BREAKER/FUSE SIZES CONFORMS TO NEC 240.6 CODE SECTION.
- 6.AC GROUNDING ELECTRODE CONDUCTOR SIZED PER NEC 250.66.
- 7.AMBIENT TEMPERATURE CORRECTION FACTOR IS BASED ON NEC 690.31(C).
- 8.AMBIENT TEMPERATURE ADJUSTMENT FACTOR IS BASED ON NEC 310.15(B)(2).
- 9.MAX. SYSTEM VOLTAGE CORRECTION IS PER NEC 690.7.
- 10.CONDUCTORS ARE SIZED PER WIRE AMPACITY TABLE NEC 310.15(B)(16).



ADDRESS: 525W, BASELINE RD
MESA AZ,85210

CUSTOMER INFORMATION

NAME: BRYCE KRYTUSA

ADDRESS: 524 MINERAL SPRINGS LANE, FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ: NC-COUNTY HARNETT

UTILITY: DUKE ENERGY

PRN NUMBER: TPS-013801

CONDUIT SCHEDULE

| TAG ID | CONDUIT SIZE | CONDUCTOR | NEUTRAL | GROUND |
|--------|-------------------|-----------------------|----------------------|-----------------------|
| 1 | NONE | (4) 10AWG PV WIRE | NONE | (1) 10AWG BARE COPPER |
| 2 | 3/4" EMT OR EQUIV | (4) 10AWG THHN/THWN-2 | NONE | (1) 10AWG THHN/THWN-2 |
| 3 | 3/4" EMT OR EQUIV | (2) 8AWG THHN/THWN-2 | (1) 8AWG THHN/THWN-2 | (1) 10AWG THHN/THWN-2 |

NOTE:
MAIN PANEL RATING: 225A, MAIN BREAKER RATING: 200A
120% RULE: (225A x 1.2) - 200A = 70A => ALLOWABLE BACKFEED IS 70A

OCPD CALCULATIONS:
INVERTER OVERCURRENT PROTECTION = INVERTER O/P I X CONTINUOUS LOAD (1.25)
= 25 x 1.25 = 31.25A => PV BREAKER = 35A
ALLOWABLE BACKFEED 70A => 35A PV BREAKER

THE DESIGNED INTERCONNECTION MEETS THE 705.12(B)(2) REQUIREMENTS.

ELECTRICAL CALCULATIONS

DC WIRE SIZING CALCULATIONS BASED OF FOLLOWING EQUATIONS >>

- REQUIRED CONDUCTOR AMPACITY: 125% PER 690.8(A)(1) X I_{sc}(A) X #OF PARALLEL STRINGS = MAX CURRENT PER 690.8(A)(1) X 125% PER 690.8(B)(2)(a) = MAX CURRENT PER 690.8(B)(2)(a)
- CORRECTED AMPACITY CALCULATIONS: AMPACITY X TEMPERATURE DERATE FACTOR X CONDUIT FILL DERATE = DERATED CONDUCTOR AMPACITY
- DERATED CONDUCTOR AMPACITY CHECK: MAX CURRENT PER 690.8(B)(2)(2) < DERATED CONDUCTOR AMPACITY

AC WIRE SIZING CALCULATIONS BASED OF FOLLOWING EQUATIONS >>

- REQUIRED CONDUCTOR AMPACITY: INVERTER OUTPUT CURRENT X #OF INVERTERS X MAX CURRENT PER 690.8(A)(3) X 125% PER 690.8(B)(2)(A)
- CORRECTED AMPACITY CALCULATIONS: AMPACITY X TEMPERATURE DERATE FACTOR X CONDUIT FILL DERATE = DERATED CONDUCTOR AMPACITY
- DERATED CONDUCTOR AMPACITY CHECK: MAX CURRENT PER 690.8(B)(2)(2) < DERATED CONDUCTOR AMPACITY

DC WIRE CALCULATIONS:- MATERIAL: COPPER & TEMPERATURE RATING: 90°C

| TAG ID | REQUIRED CONDUCTOR AMPACITY | | | | CORRECTED AMPACITY CALCULATION | | | | DERATED CONDUCTOR AMPACITY CHECK | | | | | | | | | | | | |
|--------|-----------------------------|---|----|---|--------------------------------|---|----|---|----------------------------------|---|--------|----|---|------|---|-----|---|--------|--------|---|--------|
| 1 | 1 | X | 15 | X | 1 | = | 15 | X | 1.25 | = | 18.75A | 40 | X | 0.58 | X | 1 | = | 23.20A | 18.75A | < | 23.20A |
| 2 | 1 | X | 15 | X | 1 | = | 15 | X | 1.25 | = | 18.75A | 40 | X | 0.71 | X | 0.8 | = | 22.72A | 18.75A | < | 22.72A |

AC WIRE CALCULATIONS:- MATERIAL: COPPER & TEMPERATURE RATING: 90°C

| TAG ID | REQUIRED CONDUCTOR AMPACITY | | | | CORRECTED AMPACITY CALCULATION | | | | DERATED CONDUCTOR AMPACITY CHECK | | | | | | | | | | |
|--------|-----------------------------|---|---|---|--------------------------------|---|------|---|----------------------------------|----|---|------|---|---|---|--------|--------|---|--------|
| 3 | 25 | X | 1 | = | 25 | X | 1.25 | = | 31.25A | 55 | X | 0.87 | X | 1 | = | 47.85A | 31.25A | < | 47.85A |



THREE LINE DIAGRAM


DESIGNER /CHECKED BY: RB/AJ PAPER SIZE: 17"X11"

SCALE: AS NOTED REV: A

DATE: 9/22/2020 E-2

STRING WIRING DIAGRAM

2 STRINGS OF 12 MODULES



ADDRESS: 525W, BASELINE RD
 MESA AZ,85210

CUSTOMER INFORMATION

NAME: BRYCE KRYTUSA

ADDRESS: 524 MINERAL SPRINGS LANE,
 FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ: NC-COUNTY HARNETT

UTILITY: DUKE ENERGY

PRN NUMBER: TPS-013801



STRING WIRING DIAGRAM

DESIGNER /CHECKED
 BY: RB/AJ

PAPER SIZE: 17"X11"

SCALE: AS NOTED

REV: A

DATE: 9/22/2020

E-3

WARNING PLACARD

1

CAUTION
PHOTOVOLTAIC SYSTEM CIRCUIT IS BACKFED

LABEL LOCATION
BACKFED BREAKER [PER CODE: NEC 705.12(4)]

2

WARNING
INVERTER OUTPUT CONNECTION:
DO NOT RELOCATE THIS
OVERCURRENT DEVICE

LABEL LOCATION: BACKFED BREAKER
[PER CODE: 2017 NEC 705.12(2)(3)(b)]

3

WARNING
A GENERATION SOURCE IS CONNECTED TO THE SUPPLY
(UTILITY) SIDE OF THE MAIN SERVICE DISCONNECT. FOLLOW
THE PROPER LOCK-OUT/TAG-OUT PROCEDURES TO ENSURE
THE PHOTOVOLTAIC SYSTEM UTILITY DISCONNECT SWITCH IS
OPENED PRIOR TO PERFORMING WORK ON THIS DEVICE

LABEL LOCATION: (IF APPLICABLE) SUPPLY SIDE TAP LOAD PANEL
[PER CODE: UTILITY]

4

PHOTOVOLTAIC AC DISCONNECT
RATED AC OPERATING CURRENT 25.00 A
AC NOMINAL OPERATING VOLTAGE 240 VAC

LABEL LOCATION: MAIN PANEL AC DISCONNECT(S)
[PER CODE: NEC 690.54]

5

**RAPID SHUTDOWN SWITCH
FOR SOLAR PV SYSTEM**

LABEL LOCATION: MAIN PANEL
[PER CODE: NEC 690.12,690.56(C)(3)]

6

WARNING
ELECTRIC SHOCK HAZARD
TERMINALS ON BOTH LINE AND LOAD SIDES MAY
BE ENERGIZED IN THE OPEN POSITION

LABEL LOCATION: COMBINER PANEL
AC DISCONNECT JUNCTION BOX INVERTER(S)
[PER CODE: NEC 690.13(B)]

8

WARNING
PHOTOVOLTAIC SYSTEM
COMBINER PANEL
DO NOT ADD LOADS

LABEL LOCATION: AC COMBINER PANEL
[PER CODE: NEC 690.13(B)]

9

MAXIMUM VOLTAGE: 480 VDC
MAXIMUM CIRCUIT CURRENT: 15 ADC
MAX. RATED OUTPUT CURRENT OF THE
CHARGE CONTROLLER OR
DC-TO-DC-CONVERTER (IF 15 ADC
INSTALLED)

LABEL LOCATION: DC DISCONNECT INVERTER
[PER CODE: NEC 690.53 UTILITY]

10

WARNING
ELECTRIC SHOCK HAZARD
DO NOT TOUCH TERMINALS
TERMINALS ON BOTH LINE AND LOAD SIDES MAY
BE ENERGIZED IN THE OPEN POSITION


DC VOLTAGE IS ALWAYS PRESENT WHEN SOLAR
MODULES ARE EXPOSED TO SUNLIGHT

LABEL LOCATION
DC DISCONNECT INVERTER, COMBINE BOX
[PER CODE: NEC 690.13(B)]

11

**SOLAR PV SYSTEM EQUIPPED
WITH RAPID SHUTDOWN**

TURN RAPID SHUTDOWN
SWITCH TO THE
"OFF" POSITION TO
SHUT DOWN PV SYSTEM
AND REDUCE
SHOCK HAZARD
IN THE ARRAY



LABEL LOCATION: MAIN SERVICE
[PER CODE: NEC 690.12, NEC 690.56(C)(1)(a)]

13

CAUTION
DUAL POWER SOURCE
SECOND SOURCE IS
PHOTOVOLTAIC

LABEL LOCATION :SERVICE METER MAIN PANEL
[PER CODE: UTILITY]

14

WARNING
INVERTER OUTPUT CONNECTION
**DO NOT RELOCATE THIS
OVER-CURRENT DEVICE**

LABEL LOCATION : (IF APPLICABLE) SERVICE PANEL
[PER CODE: NEC 705.12(D)(7)]

15

**PHOTOVOLTAIC SYSTEM
UTILITY DISCONNECT SWITCH**

LABEL LOCATION :AC DISCONNECT
[PER CODE: NEC 690.13(B)UTILITY]

16

WARNING
ELECTRIC SHOCK HAZARD
IF GROUND FAULT IS INDICATED ALL NORMALLY
GROUNDED CONDUCTORS MAY BE UNGROUNDED
AND ENERGIZED

LABEL LOCATION
AC DISCONNECT COMBINER BOX SERVICE METER
[PER CODE: NEC 690.5(C)]

17

PV SOLAR BREAKER
**DO NOT RELOCATE THIS
OVERCURRENT DEVICE**

LABEL LOCATION
MAIN PANEL DEAD FRONT
[PER CODE: NEC 705.12(B)(2)(3)(b)]

18

WARNING PHOTOVOLTAIC POWER SOURCE

LABEL LOCATION
DC CONDUIT JUNCTION BOX NO MORE THAN 10FT
[PER CODE: NEC 690.31(G)(3), NEC 690.31(G)(4)]



ADDRESS: 525W, BASELINE RD
MESA AZ,85210

CUSTOMER INFORMATION

NAME: BRYCE KRYTUSA

ADDRESS: 524 MINERAL SPRINGS LANE,
FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ: NC-COUNTY HARNETT

UTILITY: DUKE ENERGY

PRN NUMBER: TPS-013801



WARNING PLACARDS

DESIGNER /CHECKED
BY: RB/AJ

PAPER SIZE: 17"X11"

SCALE: AS NOTED

REV: A

DATE: 9/22/2020

PL-1

LABELS ARE REFLECTIVE AND WEATHER RESISTANT. LABEL REQUIRES CAPITALIZED LETTER WITH A MINIMUM HEIGHT OF 3/8 INCH, WHITE LETTERS ON RED BACKGROUND LABELS SHALL BE PLACED ON INTERIOR AND EXTERIOR DC CONDUIT, RACEWAYS, ENCLOSURES, AND CABLE ASSEMBLIES EVERY 10 FEET, WITHIN 1 FOOT OF TURNS OR BENDS AND WITHIN 1 FOOT ABOVE AND BELOW PENETRATIONS OF ROOF/CEILING ASSEMBLIES, WALLS OR BARRIER

SAFETY PLANS


SAFETY PLANS

NOTES:

1. INSTALLERS SHALL DRAW IN DESIGNATED SAFETY AREA AROUND HOME.
2. INSTALLERS SHALL UPDATE NAME ADDRESS AND PHONE NUMBER OF NEAREST.
3. URGENT CARE FACILITY RELATIVE TO THE SITE BEFORE STARTING WORK.

LOCATION OF NEAREST URGENT CARE FACILITY

NAME:
ADDRESS:
PHONE NUMBER:



ADDRESS: 525W, BASELINE RD
MESA AZ,85210

CUSTOMER INFORMATION

NAME: BRYCE KRYTUSA

ADDRESS: 524 MINERAL SPRINGS LANE,
FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ: NC-COUNTY HARNETT

UTILITY: DUKE ENERGY

PRN NUMBER: TPS-013801



SAFETY PLANS

DESIGNER /CHECKED
BY: RB/AJ

PAPER SIZE: 17"X11"

SCALE: AS NOTED

REV: A

DATE: 9/22/2020

PL-2

SPEC SHEET



TITAN

SOLAR PANEL

60 Cell
Monocrystalline
PV Module



CHUBB
* Chubb provides error and omission insurance to Silfab Solar Inc.

SIL-330 NL
POWERED BY
SILFAB SOLAR




INDUSTRY LEADING WARRANTY
The Titan Solar Panel is manufactured by Silfab Solar and includes an industry leading 25-year product workmanship and 30-year performance warranty.

MAXIMUM ENERGY OUTPUT
Leveraging over 35+ years of worldwide experience in the solar industry, Silfab is dedicated to superior manufacturing processes and innovations such as Bifacial and Back Contact technologies, to ensure our partners, such as Titan Solar have the latest in solar innovation.

NORTH AMERICAN QUALITY
Silfab is the leading automated solar module manufacturer in North America. Utilizing premium quality materials and strict quality control management to deliver the highest efficiency, premium quality PV modules 100% made in North America.



BAA / ARRA COMPLIANT

Panels are designed and manufactured to meet Buy American Act Compliance. The US State Department, US Military and FAA have all utilized Silfab panels in their solar installations.

LIGHT AND DURABLE

Engineered to accommodate high wind load conditions for test loads validated up to 4000Pa uplift. The light-weight frame is exclusively designed for wide-ranging racking compatibility and durability.

QUALITY MATTERS

Total automation ensures strict quality controls during the entire manufacturing process at ISO certified facilities.

DOMESTIC PRODUCTION

Silfab Solar manufactures PV modules in two automated locations within North America. Our 500+ North American team is ready to help Titan Solar win the hearts and minds of customers, providing customer service and product delivery that is direct, efficient and local.

AESTHETICALLY PLEASING

All black sleek design, ideal for high-profile residential or commercial applications.

PID RESISTANT

PID Resistant due to advanced cell technology and material selection. In accordance to IEC 62804-1.

| Electrical Specifications | | SIL-330 NL mono PERC | |
|-------------------------------|----|----------------------|----------|
| Test Conditions | | STC | NOCT |
| Module Power (Pmax) | Wp | 330 | 235 |
| Maximum power voltage (Vpmax) | V | 33.3 | 30.2 |
| Maximum power current (Ipmax) | A | 9.92 | 7.8 |
| Open circuit voltage (Voc) | V | 40.5 | 36.7 |
| Short circuit current (Isc) | A | 10.42 | 8.2 |
| Module efficiency | % | 19.4 | 17.3 |
| Maximum system voltage (VDC) | V | | 1000 |
| Series fuse rating | A | | 20 |
| Power Tolerance | Wp | | 0 to +10 |

Measurement conditions: STC 1000 W/m² • AM 1.5 • Temperature 25 °C • NOCT 800 W/m² • AM 1.5 • Measurement uncertainty ± 3%
• Sun simulator calibration reference modules from Fraunhofer Institute. Electrical characteristics may vary by ±5% and power by 0 to +10W.

| Temperature Ratings | | SIL-330 NL mono PERC | |
|------------------------------|--|----------------------|--|
| Temperature Coefficient Isc | | 0.064 %/°C | |
| Temperature Coefficient Voc | | -0.28 %/°C | |
| Temperature Coefficient Pmax | | -0.36 %/°C | |
| NOCT (± 2°C) | | 45 °C | |
| Operating temperature | | -40/+85 °C | |

| Mechanical Properties and Components | | |
|--|---|---|
| | Metric | Imperial |
| Module weight | 18.6 kg ±0.2 kg | 41 ±0.4 lbs |
| Dimensions (H x L x D) | 1700 mm x 1000 mm x 38 mm | 66.9 in x 39.4 in x 1.5 in |
| Maximum surface load (wind/snow)* | 4000 Pa rear load / 5400 Pa front load N/m ² | 83.5/112.8 lb/ft ² |
| Hail impact resistance | ø 25 mm at 83 km/h | ø 1 in at 51.6 mph |
| Cells | 60 - Si mono PERC - 5 busbar 158.75 x 158.75 mm | 60 - Si mono PERC - 5 busbar 6.25 x 6.25 Inch |
| Glass | 3.2 mm high transmittance, tempered, DSM anti-reflective coating | 0.126 in high transmittance, tempered, DSM anti-reflective coating |
| Cables and connectors (refer to installation manual) | 1200 mm, ø 5.7 mm, MC4 from Staubli | 47.2 in, ø 0.22 in, MC4 from Staubli |



Backsheet High durability, superior hydrolysis and UV resistance, multi-layer dielectric film, fluorine-free PV backsheet
Frame Anodized Aluminum (Black)
Bypass diodes 3 diodes-30SQ045T (45V max DC blocking voltage, 30A max forward rectified current)
Junction Box UL 3730 Certified, IEC 62790 Certified, IP67 rated

| Warranties | |
|-------------------------------------|---|
| Module product workmanship warranty | 25 years** |
| Linear power performance guarantee | 30 years |
| | ≥ 97.1% end 1 st year ≥ 91.6% end 12 th year ≥ 85.1% end 25 th year ≥ 82.6% end 30 th year |

Certifications ULC ORD C1703, UL1703, CEC listed***, UL 61215-1/-1-1/-2, UL 61730-1/-2, IEC 61215-1/-1-1/-2***, IEC 61730-1/-2***, CSA C22.2#61730-1/-2***, IEC 62716 Ammonia Corrosion; IEC61701:2011 Salt Mist Corrosion Certified, UL Fire Rating: Type 2

Factory ISO9001:2015
 ■ Modules Per Pallet: 26
 ■ Pallets Per Truck: 36
 ■ Modules Per Truck: 936

*Warning: Read the Safety and Installation Manual for mounting specifications and before handling, installing and operating modules.
 **12 year extendable to 25 years subject to registration and conditions outlined under "Warranty" at www.silfabsolar.com.
 ***Certification and CEC listing in progress.
 Third-party generated pan files from Fraunhofer-Institute for Solar Energy Systems ISE are available for download at: www.silfabsolar.com/downloads



TITAN SOLAR POWER
 Titan Solar Power
 525 W Baseline Rd
 Mesa, AZ 85210
 Tel 855 SAY-SOLAR
 Titansolarpower.com
 info@titansolarpower.com

Silfab SOLAR
 Silfab Solar Inc.
 240 Courtneypark Drive East
 Mississauga ON L5T 2Y3 Canada
 Tel +1 905-255-2501 | Fax +1 905-696-0267
 info@silfabsolar.com | www.silfabsolar.com

Silfab Solar Inc.
 800 Cornwall Ave
 Bellingham WA 98225 USA
 Tel +1 360-569-4733



ADDRESS: 525W, BASELINE RD
MESA AZ,85210

CUSTOMER INFORMATION

NAME: BRYCE KRYTUSA
 ADDRESS: 524 MINERAL SPRINGS LANE,
 FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ: NC-COUNTY HARNETT

UTILITY: DUKE ENERGY

PRN NUMBER: TPS-013801



MODULE SPEC SHEET

DESIGNER /CHECKED BY: RB/AJ PAPER SIZE: 17"X11"

SCALE: AS NOTED REV: A

DATE: 9/22/2020 SS-1

SIL-330-NL-20200715 - No reproduction of any kind is allowed. Data and information is subject to modifications without notice. ©Silfab, 2020.

Single Phase Inverter with HD-Wave Technology

for North America

SE3000H-US / SE3800H-US / SE5000H-US / SE6000H-US / SE7600H-US / SE10000H-US / SE11400H-US



INVERTERS

Optimized installation with HD-Wave technology

- Specifically designed to work with power optimizers
- Record-breaking 99% weighted efficiency
- Quick and easy inverter commissioning directly from a smartphone using the SolarEdge SetApp
- Fixed voltage inverter for longer strings
- Integrated arc fault protection and rapid shutdown for NEC 2014 and 2017, per article 690.11 and 690.12
- UL1741 SA certified, for CPUC Rule 21 grid compliance
- Small, lightweight, and easy to install both outdoors or indoors
- Built-in module-level monitoring
- Optional: Faster installations with built-in consumption metering (1% accuracy) and production revenue grade metering (0.5% accuracy, ANSI C12.20)

solaredge.com



Single Phase Inverter with HD-Wave Technology for North America

SE3000H-US / SE3800H-US / SE5000H-US / SE6000H-US / SE7600H-US / SE10000H-US / SE11400H-US

| MODEL NUMBER | SE3000H-US | SE3800H-US | SE5000H-US | SE6000H-US | SE7600H-US | SE10000H-US | SE11400H-US | |
|---|-------------------------------|----------------------------|------------|----------------------------|------------|-------------|------------------------------|-----|
| APPLICABLE TO INVERTERS WITH PART NUMBER | SEXXXH-XXXXBXX4 | | | | | | | |
| OUTPUT | | | | | | | | |
| Rated AC Power Output | 3000 | 3800 @ 240V 3300 @ 208V | 5000 | 6000 @ 240V 5000 @ 208V | 7600 | 10000 | 11400 @ 240V 10000 @ 208V | VA |
| Maximum AC Power Output | 3000 | 3800 @ 240V 3300 @ 208V | 5000 | 6000 @ 240V 5000 @ 208V | 7600 | 10000 | 11400 @ 240V 10000 @ 208V | VA |
| AC Output Voltage Min.-Nom.-Max. (211 - 240 - 264) | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | Vac |
| AC Output Voltage Min.-Nom.-Max. (183 - 208 - 229) | - | ✓ | - | ✓ | - | - | ✓ | Vac |
| AC Frequency (Nominal) | 59.3 - 60 - 60.5 ^① | | | | | | | Hz |
| Maximum Continuous Output Current @240V | 12.5 | 16 | 21 | 25 | 32 | 42 | 47.5 | A |
| Maximum Continuous Output Current @208V | - | 16 | - | 24 | - | - | 48.5 | A |
| Power Factor | 1, Adjustable - 0.85 to 0.85 | | | | | | | |
| GFDI Threshold | 1 | | | | | | | A |
| Utility Monitoring, Islanding Protection, Country Configurable Thresholds | Yes | | | | | | | |
| INPUT | | | | | | | | |
| Maximum DC Power @240V | 4650 | 5900 | 7750 | 9300 | 11800 | 15500 | 17650 | W |
| Maximum DC Power @208V | - | 5100 | - | 7750 | - | - | 15500 | W |
| Transformer-less, Ungrounded | Yes | | | | | | | |
| Maximum Input Voltage | 480 | | | | | | | Vdc |
| Nominal DC Input Voltage | 380 | | | 400 | | | | Vdc |
| Maximum Input Current @240V ^② | 8.5 | 10.5 | 13.5 | 16.5 | 20 | 27 | 30.5 | Adc |
| Maximum Input Current @208V ^② | - | 9 | - | 13.5 | - | - | 27 | Adc |
| Max. Input Short Circuit Current | 45 | | | | | | | Adc |
| Reverse-Polarity Protection | Yes | | | | | | | |
| Ground-Fault Isolation Detection | 600ka Sensitivity | | | | | | | |
| Maximum Inverter Efficiency | 99 | 99.2 | | | | | | % |
| CEC Weighted Efficiency | 99 | | | | | | 99 @ 240V 98.5 @ 208V | % |
| Nighttime Power Consumption | < 2.5 | | | | | | | W |

^① For other regional settings please contact SolarEdge support
^② A higher current source may be used; the inverter will limit its input current to the values stated



ADDRESS: 525W, BASELINE RD
MESA AZ,85210

CUSTOMER INFORMATION

NAME: BRYCE KRYTUSA

ADDRESS: 524 MINERAL SPRINGS LANE,
FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ: NC-COUNTY HARNETT

UTILITY: DUKE ENERGY

PRN NUMBER: TPS-013801



INVERTER SPEC SHEET

DESIGNER /CHECKED BY: RB/AJ PAPER SIZE: 17"X11"

SCALE: AS NOTED REV: A

DATE: 9/22/2020 SS-2

SPEC SHEET

/ Single Phase Inverter with HD-Wave Technology for North America


SE3000H-US / SE3800H-US / SE5000H-US / SE6000H-US/
SE7600H-US / SE10000H-US / SE11400H-US

| MODEL NUMBER | SE3000H-US | SE3800H-US | SE5000H-US | SE6000H-US | SE7600H-US | SE10000H-US | SE11400H-US | |
|--|---|-------------|-------------|-------------------------------------|------------|-------------|-------------|---------|
| ADDITIONAL FEATURES | | | | | | | | |
| Supported Communication Interfaces | RS485, Ethernet, ZigBee (optional), Cellular (optional) | | | | | | | |
| Revenue Grade Metering, ANSI C12.20 | Optional ⁽³⁾ | | | | | | | |
| Consumption metering | | | | | | | | |
| Inverter Commissioning | With the SetApp mobile application using Built-in Wi-Fi Access Point for Local Connection | | | | | | | |
| Rapid Shutdown - NEC 2014 and 2017 690.12 | Automatic Rapid Shutdown upon AC Grid Disconnect | | | | | | | |
| STANDARD COMPLIANCE | | | | | | | | |
| Safety | UL1741, UL1741 SA, UL1699B, CSA C22.2, Canadian AFCI according to T.I.L. M-07 | | | | | | | |
| Grid Connection Standards | IEEE1547, Rule 21, Rule 14 (HI) | | | | | | | |
| Emissions | FCC Part 15 Class B | | | | | | | |
| INSTALLATION SPECIFICATIONS | | | | | | | | |
| AC Output Conduit Size / AWG Range | 1" Maximum / 14-6 AWG | | | 1" Maximum /14-4 AWG | | | | |
| DC Input Conduit Size / # of Strings / AWG Range | 1" Maximum / 1-2 strings / 14-6 AWG | | | 1" Maximum / 1-3 strings / 14-6 AWG | | | | |
| Dimensions with Safety Switch (HxWxD) | 17.7 x 14.6 x 6.8 / 450 x 370 x 174 | | | 21.3 x 14.6 x 7.3 / 540 x 370 x 185 | | | | in / mm |
| Weight with Safety Switch | 22 / 10 | 25.1 / 11.4 | 26.2 / 11.9 | 38.8 / 17.6 | | | | lb / kg |
| Noise | < 25 | | | <50 | | | | dBA |
| Cooling | Natural Convection | | | | | | | |
| Operating Temperature Range | -40 to +140 / -40 to +60 ⁽⁴⁾ | | | | | | | °F / °C |
| Protection Rating | NEMA 4X (Inverter with Safety Switch) | | | | | | | |

⁽³⁾ Inverter with Revenue Grade Meter P/N: SExxxxH-US000BNC4; Inverter with Revenue Grade Production and Consumption Meter P/N: SExxxxH-US000BN4 . For consumption metering, current transformers should be ordered separately: SEACT0750-200NA-20 or SEACT0750-400NA-20. 20 units per box
⁽⁴⁾ Full power up to at least 50°C / 122°F; for power de-rating information refer to: <https://www.solaredge.com/sites/default/files/se-temperature-derating-note-na.pdf>

How to Enable Consumption Monitoring

By simply wiring current transformers through the inverter's existing AC conduits and connecting them to the service panel, homeowners will gain full insight into their household energy usage helping them to avoid high electricity bills



© SolarEdge Technologies, Inc. All rights reserved. SOLAREEDGE, the SolarEdge logo, OPTIMIZED BY SOLAREEDGE are trademarks or registered trademarks of SolarEdge Technologies, Inc. All other trademarks mentioned herein are trademarks of their respective owners. Date: 01/2020/V01/ENG NAM. Subject to change without notice.



ADDRESS: 525W, BASELINE RD
MESA AZ,85210

CUSTOMER INFORMATION

NAME: BRYCE KRYTUSA

ADDRESS: 524 MINERAL SPRINGS LANE,
FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ: NC-COUNTY HARNETT

UTILITY: DUKE ENERGY

PRN NUMBER: TPS-013801



INVERTER SPEC SHEET

DESIGNER /CHECKED
BY: RB/AJ

PAPER SIZE: 17"X11"

SCALE: AS NOTED

REV: A

DATE: 9/22/2020

SS-3

Power Optimizer

For North America

P320 / P340 / P370 / P400 / P405 / P485 / P505



POWEROPTIMIZER

PV power optimization at the module-level

- Specifically designed to work with SolarEdge inverters
- Up to 25% more energy
- Superior efficiency (99.5%)
- Mitigates all types of module mismatch losses, from manufacturing tolerance to partial shading
- Flexible system design for maximum space utilization
- Fast installation with a single bolt
- Next generation maintenance with module-level monitoring
- Meets NEC requirements for arc fault protection (AFCI) and Photovoltaic Rapid Shutdown System (PVRSS)
- Module-level voltage shutdown for installer and firefighter safety

solaredge.com



Power Optimizer

For North America

P320 / P340 / P370 / P400 / P405 / P485 / P505

| Optimizer model (typical module compatibility) | P320 (for 60-cell modules) | P340 (for high-power 60-cell modules) | P370 (for higher-power 60 and 72-cell modules) | P400 (for 72 & 96-cell modules) | P405 (for high-voltage modules) | P485 (for high-voltage modules) | P505 (for higher current modules) | | |
|---|--|---------------------------------------|--|---------------------------------|------------------------------------|---------------------------------|--------------------------------------|--------------------|---------|
| INPUT | | | | | | | | | |
| Rated Input DC Power ⁽¹⁾ | 320 | 340 | 370 | 400 | 405 | 485 | 505 | W | |
| Absolute Maximum Input Voltage (Voc at lowest temperature) | 48 | | 60 | 80 | 125 ⁽²⁾ | | 83 ⁽²⁾ | Vdc | |
| MPPT Operating Range | 8 - 48 | | 8 - 60 | 8 - 80 | 12.5 - 105 | | 12.5 - 83 | Vdc | |
| Maximum Short Circuit Current (Isc) | | 11 | | | 10.1 | | 14 | Adc | |
| Maximum DC Input Current | | 13.75 | | | 12.5 | | 17.5 | Adc | |
| Maximum Efficiency | | | | 99.5 | | | | % | |
| Weighted Efficiency | | | 98.8 | | | | 98.6 | % | |
| Overvoltage Category | II | | | | | | | | |
| OUTPUT DURING OPERATION (POWER OPTIMIZER CONNECTED TO OPERATING SOLAREEDGE INVERTER) | | | | | | | | | |
| Maximum Output Current | | | | 15 | | | | Adc | |
| Maximum Output Voltage | | 60 | | | | 85 | | Vdc | |
| OUTPUT DURING STANDBY (POWER OPTIMIZER DISCONNECTED FROM SOLAREEDGE INVERTER OR SOLAREEDGE INVERTER OFF) | | | | | | | | | |
| Safety Output Voltage per Power Optimizer | 1 ± 0.1 | | | | | | | | Vdc |
| STANDARD COMPLIANCE | | | | | | | | | |
| EMC | FCC Part15 Class B, IEC61000-6-2, IEC61000-6-3 | | | | | | | | |
| Safety | IEC62109-1 (class II safety), UL1741 | | | | | | | | |
| Material | UL94 V-0, UV Resistant | | | | | | | | |
| RoHS | Yes | | | | | | | | |
| INSTALLATION SPECIFICATIONS | | | | | | | | | |
| Maximum Allowed System Voltage | 1000 | | | | | | | | Vdc |
| Compatible inverters | All SolarEdge Single Phase and Three Phase inverters | | | | | | | | |
| Dimensions (W x L x H) | 129 x 153 x 27.5 / 5.1 x 6 x 1.1 | | 129 x 153 x 33.5 / 5.1 x 6 x 1.3 | | 129 x 159 x 49.5 / 5.1 x 6.3 x 1.9 | | 129 x 162 x 59 / 5.1 x 6.4 x 2.3 | mm / in | |
| Weight (including cables) | 630 / 1.4 | | 750 / 1.7 | | 845 / 1.9 | | 1064 / 2.3 | gr / lb | |
| Input Connector | MC4 ⁽³⁾ | | | | | | Single or dual MC4 ⁽³⁾⁽⁴⁾ | MC4 ⁽³⁾ | |
| Input Wire Length | 0.16 / 0.52 | | | | | | | | m / ft |
| Output Wire Type / Connector | Double Insulated / MC4 | | | | | | | | |
| Output Wire Length | 0.9 / 2.95 | | 1.2 / 3.9 | | 1.2 / 3.9 | | 1.2 / 3.9 | m / ft | |
| Operating Temperature Range ⁽⁵⁾ | -40 - +85 / -40 - +185 | | | | | | | | °C / °F |
| Protection Rating | IP68 / NEMA6P | | | | | | | | |
| Relative Humidity | 0 - 100 | | | | | | | | % |

⁽¹⁾ Rated power of the module at STC will not exceed the optimizer "Rated Input DC Power". Modules with up to +5% power tolerance are allowed.
⁽²⁾ NEC 2017 requires max input voltage be not more than 80V
⁽³⁾ For other connector types please contact SolarEdge
⁽⁴⁾ For dual version for parallel connection of two modules use the P485. In the case of an odd number of PV modules in one string, installing one P485 dual version power optimizer
⁽⁵⁾ For ambient temperature above +85°C / +185°F power de-rating is applied. Refer to Power Optimizers Temperature De-Rating Technical Note for more details.

| PV System Design Using a SolarEdge Inverter ⁽⁶⁾⁽⁷⁾ | Single Phase HD-Wave | Single phase | Three Phase for 208V grid | Three Phase for 277/480V grid | |
|---|---|--------------|---------------------------|-------------------------------|---|
| Minimum String Length (Power Optimizers) | P320, P340, P370, P400 | 8 | 10 | 18 | |
| | P405, P485, P505 | 6 | 8 | 14 | |
| Maximum String Length (Power Optimizers) | | 25 | 25 | 50 ⁽⁸⁾ | |
| Maximum Power per String | 5700 (6000 with SE7600-US - SE11400-US) | 5250 | 6000 ⁽⁹⁾ | 12750 ⁽¹⁰⁾ | W |
| Parallel Strings of Different Lengths or Orientations | Yes | | | | |

⁽⁶⁾ For detailed string sizing information refer to: http://www.solaredge.com/sites/default/files/string_sizing_na.pdf
⁽⁷⁾ It is not allowed to mix P405/P485/P505 with P320/P340/P370/P400 in one string
⁽⁸⁾ A string with more than 30 optimizers does not meet NEC rapid shutdown requirements; safety voltage will be above the 30V requirement
⁽⁹⁾ For 208V grid: it is allowed to install up to 6,500W per string when the maximum power difference between each string is 1,000W
⁽¹⁰⁾ For 277/480V grid: it is allowed to install up to 17,550W per string when the maximum power difference between each string is 2,000W



ADDRESS: 525W, BASELINE RD
MESA AZ,85210

CUSTOMER INFORMATION

NAME: BRYCE KRYTUSA

ADDRESS: 524 MINERAL SPRINGS LANE,
FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ: NC-COUNTY HARNETT

UTILITY: DUKE ENERGY

PRN NUMBER: TPS-013801



OPTIMIZER SPEC SHEET

DESIGNER /CHECKED BY: RB/AJ

PAPER SIZE: 17"X11"

SCALE: AS NOTED


REV: A

DATE: 9/22/2020

SS-4

L-Mount | QMLM / QMLM-ST

Elevated Water Seal Technology®



L-Mount Installation Instructions

Installation Tools Required: tape measure, roofing bar, chalk line, stud finder, caulking gun, sealant compatible with roofing materials, drill with 7/32" or 1/8" bit, drill or impact gun with 1/2" socket.


WARNING: Quick Mount PV products are NOT designed for and should NOT be used to anchor fall protection equipment.



Locate, choose, and mark centers of rafters to be mounted. Select the courses of shingles where mounts will be placed.




Carefully lift composition roof shingle with roofing bar, just above placement of mount. Remove nails as required and backfill holes with approved sealant. See "Proper Flashing Placement" on next page.



Insert flashing between 1st and 2nd course. Slide up so top edge of flashing is at least 3/4" higher than the butt-edge of the 3rd course and lower flashing edge is above the butt-edge of 1st course. Mark center for drilling.




If attaching with lag bolt use a 7/32" bit (Lag). Use a 1/8" bit (ST) for attaching with the structural screw. Drill pilot hole into roof and rafter, taking care to drill square to the roof. Do not use mount as a drill guide. Drill a 2" deep hole into rafter.



Clean off any sawdust, and fill hole with sealant compatible with roofing materials.



Place L-foot onto elevated flute and rotate L-foot to desired orientation.



Prepare lag bolt or structural screw with sealing washer. Using a 1/2-inch socket on an impact gun, drive prepared lag bolt through L-foot until L-foot can no longer easily rotate. **DO NOT over-torque.** NOTE: Structural screw can be driven with T-30 hex head bit.



You are now ready for the rack of your choice. Follow all the directions of the rack manufacturer as well as the module manufacturer. NOTE: Make sure top of L-Foot makes solid contact with racking.

All roofing manufacturers' written instructions must also be followed by anyone modifying a roof system. Consult the roof manufacturer's specs and instructions prior to working on the roof.

Quick Mount PV®
RESPECT THE ROOF



ADDRESS: 525W, BASELINE RD
MESA AZ,85210

CUSTOMER INFORMATION

NAME: BRYCE KRYTUSA

ADDRESS: 524 MINERAL SPRINGS LANE,
FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ: NC-COUNTY HARNETT

UTILITY: DUKE ENERGY

PRN NUMBER: TPS-013801



MOUNT SPEC SHEET

DESIGNER /CHECKED
BY: RB/AJ

PAPER SIZE: 17"X11"

SCALE: AS NOTED

REV: A

DATE: 9/22/2020

SS-5

SPEC SHEET





XR Rail Family

Tech Brief

Solar Is Not Always Sunny

Over their lifetime, solar panels experience countless extreme weather events. Not just the worst storms in years, but the worst storms in 40 years. High winds capable of ripping panels from a roof, and snowfalls weighing enough to buckle a panel frame.

XR Rails are the structural backbone preventing these results. They resist uplift, protect against buckling and safely and efficiently transfer loads into the building structure. Their superior spanning capability requires fewer roof attachments, reducing the number of roof penetrations and the amount of installation time.



Force-Stabilizing Curve

Sloped roofs generate both vertical and lateral forces on mounting rails which can cause them to bend and twist. The curved shape of XR Rails is specially designed to increase strength in both directions while resisting the twisting. This unique feature ensures greater security during extreme weather and a longer system lifetime.


Compatible with Flat & Pitched Roofs

XR Rails are compatible with FlashFoot and other pitched roof attachments.

IronRidge offers a range of tilt leg options for flat roof mounting applications.

Corrosion-Resistant Materials

All XR Rails are made of 6000-series aluminum alloy, then protected with an anodized finish. Anodizing prevents surface and structural corrosion, while also providing a more attractive appearance.



XR Rail Family

The XR Rail Family offers the strength of a curved rail in three targeted sizes. Each size supports specific design loads, while minimizing material costs. Depending on your location, there is an XR Rail to match.

Tech Brief



XR10

XR10 is a sleek, low-profile mounting rail, designed for regions with light or no snow. It achieves spans up to 6 feet, while remaining light and economical.

- 6' spanning capability
- Moderate load capability
- Clear & black anodized finish
- Internal splices available



XR100

XR100 is the ultimate residential mounting rail. It supports a range of wind and snow conditions, while also maximizing spans up to 10 feet.

- 10' spanning capability
- Heavy load capability
- Clear & black anodized finish
- Internal splices available



XR1000

XR1000 is a heavyweight among solar mounting rails. It's built to handle extreme climates and spans up to 12 feet for commercial applications.

- 12' spanning capability
- Extreme load capability
- Clear anodized finish
- Internal splices available

Rail Selection

The table below was prepared in compliance with applicable engineering codes and standards.* Values are based on the following criteria: ASCE 7-16, Gable Roof Flush Mount, Roof Zones 1 & 2e, Exposure B, Roof Slope of 8 to 20 degrees and Mean Building Height of 30 ft. Visit IronRidge.com for detailed certification letters.

| Load | | Rail Span | | | | | |
|------------|------------|-----------|-------|-------|----|--------|-----|
| Snow (PSF) | Wind (MPH) | 4' | 5' 4" | 6' | 8' | 10' | 12' |
| None | 90 | | | | | | |
| | 120 | | | | | | |
| | 140 | XR10 | | XR100 | | XR1000 | |
| | 160 | | | | | | |
| 20 | 90 | | | | | | |
| | 120 | | | | | | |
| | 140 | | | | | | |
| | 160 | | | | | | |
| 30 | 90 | | | | | | |
| | 160 | | | | | | |
| 40 | 90 | | | | | | |
| | 160 | | | | | | |
| 80 | 160 | | | | | | |
| | 160 | | | | | | |
| 120 | 160 | | | | | | |
| | 160 | | | | | | |

*Table is meant to be a simplified span chart for conveying general rail capabilities. Use approved certification letters for actual design guidance.



ADDRESS: 525W, BASELINE RD
MESA AZ,85210

CUSTOMER INFORMATION

NAME: BRYCE KRYTUSA

ADDRESS: 524 MINERAL SPRINGS LANE,
FUQUAY-VARINA, NC 27526

35.496310, -78.821436

AHJ: NC-COUNTY HARNETT

UTILITY: DUKE ENERGY

PRN NUMBER: TPS-013801



RAIL SPEC SHEET

DESIGNER /CHECKED
BY: RB/AJ

PAPER SIZE: 17"X11"

SCALE: AS NOTED

REV: A

DATE: 9/22/2020

SS-6