#### **GENERAL NOTES**

#### CODES AND STANDARDS

- 1. ALL WORK SHALL COMPLY WITH 2017 NATIONAL ELECTRIC CODE (NEC), 2018 NORTH CAROLINA BUILDING CODE (NCBC), 2018 NORTH CAROLINA RESIDENTIAL CODE (NCRC), PLUMBING CODE (NCPC), AND ALL STATE AND LOCAL BUILDING, ELECTRICAL, AND PLUMBING CODES.
- 2. DRAWINGS HAVE BEEN DETAILED ACCORDING TO UL LISTING REQUIREMENTS.

#### SITE NOTES / OSHA REGULATION

- ${\bf 1.}\ \ {\bf A}\ {\bf L}{\bf A}{\bf D}{\bf D}{\bf E}{\bf R}\ {\bf S}{\bf H}{\bf A}{\bf L}{\bf L}\ {\bf B}{\bf E}\ {\bf I}{\bf N}\ {\bf P}{\bf L}{\bf A}{\bf C}{\bf E}\ {\bf F}{\bf O}{\bf R}\ {\bf I}{\bf N}{\bf S}{\bf P}{\bf E}{\bf C}{\bf I}{\bf I}{\bf O}{\bf N}{\bf I}{\bf N}{\bf C}{\bf O}{\bf M}{\bf P}{\bf L}{\bf A}{\bf C}{\bf E}\ {\bf WITH}\ {\bf O}{\bf S}{\bf H}{\bf A}\ {\bf R}{\bf E}{\bf G}{\bf U}{\bf L}{\bf A}{\bf T}{\bf I}{\bf O}{\bf N}{\bf S}.$
- 2. THE PV MODULES ARE CONSIDERED NON-COMBUSTIBLE AND THIS SYSTEM IS A UTILITY INTERACTIVE SYSTEM WITH NO STORAGE BATTERIES.
- 3. THE SOLAR PV INSTALLATION SHALL NOT OBSTRUCT ANY PLUMBING, MECHANICAL, OR BUILDING ROOF VENTS.
- 4. ROOF COVERINGS SHALL BE DESIGNED, INSTALLED, AND MAINTAINED IN ACCORDANCE WITH THIS CODE AND THE APPROVED MANUFACTURER'S INSTRUCTIONS SUCH THAT THE ROOF COVERING SHALL SERVE TO PROTECT THE BUILDING OR STRUCTURE.

#### SOLAR CONTRACTOR

- 1. MODULE CERTIFICATIONS WILL INCLUDE UL1703, IEC61646, IEC61730.
- 2. IF APPLICABLE, MODULE GROUNDING LUGS MUST BE INSTALLED AT THE MARKED GROUNDING LUG HOLES PER THE MANUFACTURERS' INSTALLATION REQUIREMENTS.
- 3. AS INDICATED BY DESIGN, OTHER NRTL LISTED MODULE GROUNDING DEVICES MAY BE USED IN PLACE OF STANDARD GROUNDING LUGS AS SHOWN IN MANUFACTURER DOCUMENTATION AND APPROVED BY THE AHJ.
- 4. CONDUIT AND WIRE SPECIFICATIONS ARE BASED ON MINIMUM CODE REQUIREMENTS AND ARE NOT MEANT TO LIMIT UP-SIZING AS REQUIRED BY FIELD CONDITIONS.
- 5. CONDUIT POINT OF PENETRATION FROM EXTERIOR TO INTERIOR TO BE INSTALLED AND SEALED WITH A SUITABLE SEALING COMPOUND.
- 6. DC WIRING LIMITED TO MODULE FOOTPRINT W/ ENPHASE AC SYSTEM.
- 7. ENPHASE WIRING SYSTEMS SHALL BE LOCATED AND SECURED UNDER THE ARRAY W/SUITABLE WIRING CLIPS.
- 8. MAX DC VOLTAGE CALCULATED USING MANUFACTURER PROVIDED TEMP COEFFICIENT FOR VOC UNLESS NOT AVAILABLE.
- 9. ALL INVERTERS, MOTOR GENERATORS, PHOTOVOLTAIC MODULES, PHOTOVOLTAIC PANELS, AC PHOTOVOLTAIC MODULES, DC COMBINERS, DC-TO-DC CONVERTERS, SOURCE CIRCUIT COMBINERS, AND CHARGE CONTROLLERS INTENDED FOR USE IN A PHOTOVOLTAIC POWER SYSTEM WILL BE IDENTIFIED AND LISTED FOR THE APPLICATION PER 690.4 (B).
- 10. ALL SIGNAGE TO BE PLACED IN ACCORDANCE WITH LOCAL BUILDING CODE
- 11. TERMINALS AND LUGS WILL BE TIGHTENED TO MANUFACTURER TORQUE SPECIFICATIONS (WHEN PROVIDED) IN ACCORDANCE WITH NEC CODE 110.14(D) ON ALL ELECTRICAL CONNECTIONS.

#### **EQUIPMENT LOCATIONS**


- 1. PROPER ACCESS AND WORKING CLEARANCE AROUND EXISTING AND PROPOSED ELECTRICAL EQUIPMENT WILL BE PROVIDED AS PER SECTION INEC 110.261.
- 2. EQUIPMENT INSTALLED IN DIRECT SUNLIGHT MUST BE RATED FOR EXPECTED OPERATING TEMPERATURE AS SPECIFIED BY [NEC 690.31 (A)] AND [NEC TABLE 310.15 (B)].
- 3. ADDITIONAL AC DISCONNECTS SHALL BE PROVIDED WHERE THE INVERTER IS NOT ADJACENT TO THE UTILITY AC DISCONNECT, OR NOT WITHIN SIGHT OF THE UTILITY AC DISCONNECT.
- 4. ALL EQUIPMENT SHALL BE INSTALLED ACCESSIBLE TO QUALIFIED PERSONNEL ACCORDING TO NEC APPLICABLE CODES.
- 5. ALL COMPONENTS ARE LISTED FOR THEIR PURPOSE AND RATED FOR OUTDOOR USAGE WHEN APPROPRIATE.



Sealed For Existing Roof & Attachment Only

RACKING: Unirac SFM Infinity

#### AERIAL VIEW



DESIGN CRITERIA
WIND SPEED: 115 MPH
GROUND SNOW LOAD: 15 PSF

GROUND SNOW LOAD: 15 PSF WIND EXPOSURE FACTOR: C SEISMIC DESIGN CATEGORY: B SITE SPECIFICATIONS
CONSTRUCTION - V-B
ZONING: RESIDENTIAL

#### SCOPE OF WORK

INSTALLATION OF UTILITY INTERACTIVE PHOTOVOLTAIC SOLAR SYSTEM

8.775 kW DC PHOTOVOLTAIC SOLAR ARRAY

ROOF TYPE: Comp Shingle

MODULES: (27) REC Solar REC325TP3M INVERTER(S): Enphase IQ7-60-2-US,----

VACINITO. Office of Williamy

#### SHEET INDEX

PV1 - COVER SHEET

PV2 - PROPERTY PLAN

PV3 - SITE PLAN

PV4 - EQUIPMENT & ATTACHMENT DETAIL

PV5 - ELECTRICAL SINGLE LINE DIAGRAM

PV6 - ELECTRICAL CALCULATIONS & ELECTRICAL NOTES

PV7 - MAIN BREAKER DERATE CALCS. (IF NEEDED)

**PV8 - LABELS & LOCATIONS** 

PV9 - CUSTOM DIRECTORY PLACARD (IF NEEDED - NEC 690.56(B))

UTILITY COMPANY: ----

PERMIT ISSUER: Harnett County



1403 N RESEARCH WAY, BUILDING J OREM, UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUERAVENSOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNEC TION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUERAVENSOLAR LLC.



CONTRACTOR: BRS FIELD OPS 385.498.6700

27526

Lloyd Derby 326 Moonlight Dr Fuquay-Varina, North Carolina

DRAWING BY

SITE INFORMATION:

Eric Thomas

DATE

February 16, 2021

PROJECT NUMBER

324685

COVER SHEET


PAGE NUMBER

REVISION


----

2/19/2021

#### 326 Moonlight Dr







Sealed For Existing Roof & Attachment Only

Fuquay-Varina, North Carolina 27526 SITE INFORMATION: 326 Moonlight Dr Lloyd Derby

1403 N RESEARCH WAY, BUILDING J OREM, UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION

HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF

ANYONE EXCEPT

BLUERAVENSOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN

PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNEC TION WITH THE

SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUERAVENSOLAR LLC.

**NABCEP** 

CERTIFIED

PV INSTALLATION

PROFESSIONAL Scott Gurney # PV-011719-015866

CONTRACTOR:

**BRS FIELD OPS** 

385.498.6700

DRAWING BY

Eric Thomas

DATE

February 16, 2021

PROJECT NUMBER

324685


SHEET NAME

PROPERTY PLAN

PAGE NUMBER


PV2

REVISION



2/19/2021

#### FRONT OF HOME



MP1 # OF MODULES: 27 AZIMUTH:232° PITCH:29° TSRF:94% AREA: 1002 SQ. FT LEGEND

INVERTER & DC DISCONNECT

(E) SUBPANEL

(N) LOAD CENTER

AC DISCONNECT

M UTILITY METER

MAIN SERVICE PANEL

TRANSFER SWITCH

**=** 

JUNCTION BOX

TS

COMBINER BOX/AGGREGATOR

V) PV REVENUE METER

FIRE SETBACK

EMT CONDUIT RUN (TO BE DETERMINED IN FIELD)

PV WIRE STRING

PROPERTY LINE

SCALE: 1/8" = 1'-0"

385.498.6700 9722 385.498.6700

Sealed For Existing Roof & Attachment Only



2/19/2021

BLUE RAVEN SOLAR

1403 N RESEARCH WAY, BUILDING J OREM, UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUERAVENSOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNEC TION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUERAVENSOLAR LLC.



CONTRACTOR: BRS FIELD OPS

SITE INFORMATION:
Lloyd Derby
326 Moonlight Dr
Fuquay-Varina, North Carolina

DRAWING BY
Eric Thomas

DATE

February 16, 2021

PROJECT NUMBER

324685

SHEET NAME

SITE PLAN

PAGE NUMBER

#### PV ARRAY INFORMATION

PV MODULE COUNT: 27 MODULES

# OF ATTACHMENT POINTS: 44


ARRAY AREA: Module Count x 17.51ft<sup>2</sup> = 472.8ft<sup>2</sup>


ROOF AREA: 2818.0ft<sup>2</sup> % OF ARRAY/ROOF: 16.8%


ARRAY WEIGHT: Module Count x 50lbs = 1350.0lbs

DISTRIBUTED LOAD: Array Weight ÷ Array Area = 2.86 lbs/ft²

POINT LOAD: Array Weight ÷ Attachments = 30.7lbs/attachment







ROOF TYPE: Comp Shingle

ROOF FRAMING TYPE: Manufactured Truss

RAFTER OR TOP CHORD(TRUSS) 2x4 @ 24"O.C. CEILING JOIST OR BOTTOM CHORD(TRUSS) 2x4 @ 24"O.C.



2/19/2021

Sealed For Existing Roof & Attachment Only



1403 N RESEARCH WAY, BUILDING J OREM, UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUERAVENSOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNEC TION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUERAVENSOLAR LLC.



CONTRACTOR: BRS FIELD OPS 385.498.6700

SITE INFORMATION:
Lloyd Derby
326 Moonlight Dr
Fuquay-Varina, North Carolina 27526

Eric Thomas

DATE

February 16, 2021

PROJECT NUMBER

324685

SHEET NAME

EQUIP. DETAIL

PAGE NUMBER

REVISION

PAGI

(27) REC Solar REC325TP3M

UL 1703 COMPLIANT

(27) Enphase IQ7-60-2-US MICRO INVERTERS

**UL 1741 COMPLIANT** 

7 MODULES MAX FOR ALL SUB-BRANCH

1403 N RESEARCH WAY, BUILDING J OREM, UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUERAVENSOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUERAVENSOLAR LLC.



CONTRACTOR:

**BRS FIELD OPS** 385.498.6700

DC

 $\stackrel{\mathsf{A}}{\geq}$ 

SIZE

SYSTEM

DC

27526 Carolina North ( 326 Moonlight Dr Fuquay-Varina, Lloyd Derby

DRAWING BY

INFORMATION

SIT

Eric Thomas

DATE

February 16, 2021

PROJECT NUMBER

324685


SHEET NAME

ELEC. 3 LINE DIAG

PAGE NUMBER

PV<sub>5</sub>

27 INVERTERS x 240 W AC = 6.48 kW AC PANEL WATTAGE = 325 W DC





1. ONE OF THE METHODS THAT FOLLOWS SHALL BE USED TO DETERMINE THE RATINGS OF BUSBARS AND PANELBOARDS. (a) THE SUM OF 125 PERCENT OF THE INVERTER(S) OUTPUT CIRCUIT CURRENT AND THE RATING OF THE OVERCURRENT DEVICE PROTECTING THE BUSBAR SHALL NOT EXCEED THE AMPACITY OF THE BUS BAR. (b) WHERE TWO SOURCES, ONE THE UTILITY AND THE OTHER AN INVERTER ARE LOCATED AT OPPOSITE ENDS OF A BUSBAR THAT CONTAINS LOADS, THE SUM OF 125 PERCENT OF THE INVERTER(S) OUTPUT CIRCUIT CURRENT AND THE RATING OF THE OVERCURRENT DEVICE PROTECTING THE BUSBAR SHALL NOT EXCEED 120 PERCENT OF THE AMPACITY OF THE BUSBAR [NEC 705.12].

(E) GROUNDING

WITH CURRENT REQUIREMENTS [NEC 250

INSTALLED.

ELECTRODE (S)

VERIFICATION WILL BE

DONE TO ENSURE THE

GROUNDING ELECTRODE

SYSTEM IS CONGRUENT

PART III.] IF NOT, A NEW

GROUND ROD WILL BE

PV BREAKER TO BE LOCATED OPPOSITE

END OF BUSSING FROM MAIN BREAKER

(N) 5/8" COPPER GROUND

ROD, 8 FT LONG, AT

(E) GROUND ROD.

NEC 250.64:

LEAST 6' APART FROM

GEC INSTALLED PER

4 AWG SOLID COPPER

6 AWG SOLID COPPER

GEC PROTECTED BY RMC/PVC/EMT

INTERCONNECTION NOTES

1. DISCONNECTING SWITCHES SHALL BE WIRED SUCH THAT WHEN THE SWITCH IS OPENED THE CONDUCTORS REMAINING LIVE ARE CONNECTED TO THE TERMINALS MARKED "LINE SIDE" (TYPICALLY THE UPPER TERMINALS) 2. AC DISCONNECT MUST BE ACCESSIBLE TO QUALIFIED UTILITY PERSONNEL, BE LOCKABLE, AND BE A VISIBLE-BREAK SWITCH

MODULE SPECIFICATIONS	REC Solar REC325TP3M
RATED POWER (STC)	325 W
MODULE VOC	39.5 V DC
MODULE VMP	34.1 V DC
MODULE IMP	9.54 A DC
MODULE ISC	10.36 A DC
VOC CORRECTION	-0.28 %/°C
VMP CORRECTION	-0.37 %/°C
SERIES FUSE RATING	20 A DC
ADJ. MODULE VOC @ ASHRAE LOW TEMP	43.4 V DC
ADJ. MODULE VMP @ ASHRAE 2% AVG. HIGH T	EMP 28.8 V DC

MICROINVERTER SPECIFICATIONS	Enphase IQ7 Microinverters
POWER POINT TRACKING (MPPT) MIN/N	VIAX 22 - 48 V DC
MAXIMUM INPUT VOLTAGE	48 V DC
MAXIMUM DC SHORT CIRCUIT CURRENT	15 A DC
MAXIMUM USABLE DC INPUT POWER	350 W
MAXIMUM OUTPUT CURRENT	1 A AC
AC OVERCURRENT PROTECTION	20 A
MAXIMUM OUTPUT POWER	240 W
CEC WEIGHTED EFFICIENCY	97 %

AC PHOTOVOLATIC MODULE MARKING (NEC 690.52)
---

NOMINAL OPERATING AC VOLTAGE	240 V AC
NOMINAL OPERATING AC FREQUENCY	47 - 68 HZ AC
MAXIMUM AC POWER	240 VA AC
MAXIMUM AC CURRENT	1.0 A AC
MAXIMUM OCPD RATING FOR AC MODULE	20 A AC

DESIGN LOCATION AND TEMPERATURES	
TEMPERATURE DATA SOURCE	ASHRAE 2% AVG. HIGH TEMP
STATE	North Carolina
CITY	Fuquay-Varina
WEATHER STATION	SEYMOUR-JOHNSON AFB
ASHRAE EXTREME LOW TEMP (°C)	-10
ASHRAE 2% AVG. HIGH TEMP (°C)	35

SYSTEM ELECTRICAL SPECIFICATIONS	CIR 1	CIR 2	CIR 3	CIR 4	CIR 5	CIR 6
NUMBER OF MODULES PER MPPT	14	13				
DC POWER RATING PER CIRCUIT (STC)	4550	4225				
TOTAL MODULE NUMBER	27 MODULES					
STC RATING OF ARRAY	8775W DC					
AC CURRENT @ MAX POWER POINT (IMP)	14.0	13.0				
MAX. CURRENT (IMP X 1.25)	17.5	16.25				
OCPD CURRENT RATING PER CIRCUIT	20	20				
MAX. COMB. ARRAY AC CURRENT (IMP)	27.0					
MAX. ARRAY AC POWER	6480W AC					

AC VOLTAGE RISE CALCULATIONS	DIST (FT)	COND.	√RISE(V)	VEND(V)	%VRISE	<b>IQ7-7</b>
VRISE SEC. 1 (MICRO TO JBOX)	25.2	12 Cu.	0.71	240.71	0.30%	
VRISE SEC. 2 (JBOX TO COMBINER BOX)	30	10 Cu.	1.07	241.07	0.44%	
VRISE SEC. 3 (COMBINER BOX TO POI)	10	6Cu.	0.28	240.28	0.11%	
TOTAL VRISE			2.05	242.05	0.86%	

PHOTOVOLTAIC	AC DISCONNECT	OLITPLIT LA REL	NEC 600 54)
PHOTOVOLIAIC	AC DISCONNECT	OUTPUT LABEL	(NEC 090.54)

,	
AC OUTPUT CURRENT	27.0 A AC
NOMINAL AC VOLTAGE	240 V AC

#### CONDUCTOR CIZE CALCULATIONS

CONDUCTOR SIZE CALCULATIONS				
MICROINVERTER TO	14.0 A	A AC		
JUNCTION BOX (1)	CTION BOX (1) MAX. CURRENT (ISC X1.25) =		A AC	
	CONDUCTOR (TC-ER, COPPER (90°C)) =		AWG	i
	CONDUCTOR RATING =	30 A	A	
	AMB. TEMP. AMP. CORRECTION =	0.96		
	ADJUSTED AMP. =	28.8	>	17.5
JUNCTION BOX TO	MAX. SHORT CIRCUIT CURRRENT (ISC) =	14.0	AC	
JUNCTION BOX (2)	MAX. CURRENT (ISC $X1.25$ ) =	17.5 A	AC	
	CONDUCTOR (UF-B, COPPER (60°C)) =	10 /	AWG	i
	CONDUCTOR RATING =	30 A	4	
	CONDUIT FILL DERATE =	1		
	AMB. TEMP. AMP. CORRECTION =	0.96		
ADJUSTED AMP. =		28.8	>	17.5
JUNCTION BOX TO	MAX. SHORT CIRCUIT CURRRENT (ISC) =	14.0	AC	
COMBINER BOX (3)	MAX. CURRENT (ISC $X1.25$ ) =	17.5 A		
	CONDUCTOR (UF-B, COPPER (60°C)) =		٩WG	i
	CONDUCTOR RATING =	30 A	4	
	CONDUIT FILL DERATE =	0.8		
	AMB. TEMP. AMP. CORRECTION =	0.96		
	ADJUSTED AMP. =	23.04	>	17.5
COMBINER BOX TO	INVERTER RATED AMPS =	27.0 A	AC	
MAIN PV OCPD (15)	MAX. CURRENT (RATED AMPS X1.25) =	33.75	AC	
CONDU	JCTOR (THWN-2, COPPER (75°C TERM.)) =	6 /	٩WG	i
	CONDUCTOR RATING =	65 A	4	
	CONDUIT FILL DERATE =	1		
	AMB. TEMP. AMP. CORRECTION =	0.96		
	ADJUSTED AMP. =	62.4	>	33.8



1403 N RESEARCH WAY, BUILDING J OREM. UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUERAVENSOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION. EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT. WITHOUT THE WRITTEN PERMISSION OF BLUERAVENSOLAR LLC.



CONTRACTOR: **BRS FIELD OPS** 

385.498.6700

27

Carolina

North

uay-Varina,

Fugi

 $\tilde{\Box}$ 

 $\overline{S}$ 

ΕM

S

S

#### **GROUNDING NOTES**

- 1. A GROUNDING ELECTRODE SYSTEM IN ACCORDANCE WITH [NEC 690-47] AND [NEC 250-50] THROUGH [NEC 250-60] SHALL BE PROVIDED. PER NEC, GROUNDING ELECTRODE SYSTEM OF EXISTING BUILDING MAY BE USED AND BONDED TO AT THE SERVICE ENTRANCE. IF EXISTING SYSTEM IS INACCESSIBLE, OR INADEQUATE, OR IS ONLY METALLIC WATER PIPING, A SUPPLEMENTAL GROUNDING ELECTRODE WILL BE USED AT THE INVERTER LOCATION CONSISTING OF A UL LISTED 8 FT GROUND ROD WITH ACORN CLAMP.
- 2. THE GROUNDING ELECTRODE CONDUCTOR SHALL BE PROTECTED FROM PHYSICAL DAMAGE BETWEEN THE GROUNDING ELECTRODE AND THE PANEL (OR INVERTER) IF SMALLER THAN #6 AWG COPPER WIRE PER NEC 250-64B. THE GROUNDING ELECTRODE CONDUCTOR WILL BE CONTINUOUS, EXCEPT FOR SPLICES OR JOINTS AT BUSBARS WITHIN LISTED EQUIPMENT PER [NEC 250.64C.].
- 3. GROUNDING ELECTRODE CONDUCTORS SHALL BE NO LESS THAN #8 AWG AND NO GREATER THAN #6 AWG COPPER AND BONDED TO THE EXISTING GROUNDING ELECTRODE TO PROVIDE FOR A COMPLETE SYSTEM.
- 4. PV SYSTEM SHALL BE GROUNDED IN ACCORDANCE TO [NEC 250.21], [NEC TABLE 250.122], AND ALL METAL PARTS OR MODULE FRAMES ACCORDING TO [NEC 690.46].
- 5. MODULE SOURCE CIRCUITS SHALL BE GROUNDED IN ACCORDANCE TO [NEC 690.421
- 6. THE GROUNDING CONNECTION TO A MODULE SHALL BE ARRANGED SUCH THAT THE REMOVAL OF A MODULE DOES NOT INTERRUPT A GROUNDED CONDUCTOR TO ANOTHER MODULE.
- 7. EACH MODULE WILL BE GROUNDED USING THE SUPPLIED CONNECTIONS POINTS IDENTIFIED IN THE MANUFACTURER'S INSTALLATION INSTRUCTIONS.
- 8. ENCLOSURES SHALL BE PROPERLY PREPARED WITH REMOVAL OF PAINT/FINISH AS APPROPRIATE WHEN GROUNDING EQUIPMENT WITH TERMINATION **GROUNDING LUGS**
- 9. GROUNDING SYSTEM COMPONENTS SHALL BE LISTED FOR THEIR PURPOSE, AND GROUNDING DEVISES EXPOSED TO THE ELEMENTS SHALL BE RATED FOR DIRECT BURIAL. 7. ALL CONDUCTORS AND OCPD SIZES AND TYPES SPECIFIED ACCORDING TO [NEC 10. GROUNDING AND BONDING CONDUCTORS SHALL BE COPPER, SOLID OR

- STRANDED, AND BARE WHEN EXPOSED.
- 11. EQUIPMENT GROUNDING CONDUCTORS SHALL BE SIZE ACCORDING TO [NEC 690.45] AND BE A MINIMUM OF #10AWG WHEN NOT EXPOSED TO DAMAGE (#6AWG SHALL BE USED WHEN EXPOSED TO DAMAGE).
- 12. GROUNDING AND BONDING CONDUCTORS, IF INSULATED, SHALL BE COLOR CODED GREEN (OR MARKED GREEN IF #4 AWG OR LARGER)
- 13. ALL CONDUIT BETWEEN THE UTILITY AC DISCONNECT AND THE POINT OF CONNECTION SHALL HAVE GROUNDED BUSHINGS AT BOTH ENDS.
- 14. SYSTEM GEC SIZED ACCORDING TO [NEC 690.47], [NEC TABLE 250.66], DC SYSTEM GEC SIZED ACCORDING TO [NEC 250.166], MINIMUM #8AWG WHEN INSULATED, #6AWG WHEN EXPOSED TO DAMAGE.
- 15. EXPOSED NON-CURRENT CARRYING METAL PARTS OF MODULE FRAMES, EQUIPMENTS, AND CONDUCTOR ENCLOSURES SHALL BE GROUNDED IN ACCORDANCE WITH 250.134 OR 250.136(A) REGARDLESS OF VOLTAGE.

#### WIRING & CONDUIT NOTES

- 1. ALL CONDUIT SIZES AND TYPES, SHALL BE LISTED FOR ITS PURPOSE AND APPROVED FOR THE SITE APPLICATIONS
- 2. BOLTED CONNECTION REQUIRED IN DC DISCONNECTS ON THE WHITE GROUNDED CONDUCTOR (USE POLARIS BLOCK OR NEUTRAL BAR)
- 3. ANY CONNECTION ABOVE LIVE PARTS MUST BE WATERTIGHT. REDUCING WASHERS DISALLOWED ABOVE LIVE PARTS, MEYERS HUBS RECOMMENDED
- 4. UV RESISTANT CABLE TIES(NOT ZIP TIES) USED FOR PERMANENT WIRE MANAGEMENT OFF THE ROOF SURFACE IN ACCORDANCE WITH NEC 110.2,110.3(A-B). 300.4
- 5. SOLADECK JUNCTION BOXES MOUNTED FLUSH W/ROOF SURFACE TO BE USED FOR WIRE MANAGEMENT AND AS FLASHED ROOF PENETRATIONS FOR INTERIOR CONDUIT
- 6. ALL PV CABLES AND HOMERUN WIRES BE TYPE USE-2, AND SINGLE-CONDUCTOR CABLE LISTED AND IDENTIFIED AS PV WIRE. TYPE TC-ER. OR EQUIVALENT: ROUTED TO SOURCE CIRCUIT COMBINER BOXES AS REQUIRED

#### 690.8] FOR MULTIPLE CONDUCTORS

- 8. ALL PV DC CONDUCTORS IN CONDUIT EXPOSED TO SUNLIGHT SHALL BE INSTALLED AT LEAST 7/8" ABOVE THE ROOF SURFACE AND DERATED ACCORDING TO [NEC TABLE 310.15 (B)(2)(a), NEC TABLE 310.15(B)(3)(a),& NEC 310.15(B)(3)(c)].
- 9. EXPOSED ROOF PV DC CONDUCTORS SHALL BE USE-2, 90°C RATED, WET AND UV RESISTANT, AND UL LISTED RATED FOR 600V, UV RATED SPIRAL WRAP SHALL BE USED TO PROTECT WIRE FROM SHARP EDGES
- 10. PHASE AND NEUTRAL CONDUCTORS SHALL BE DUAL RATED THHN/THWN-2 INSULATED, 90°C RATED, WET AND UV RESISTANT, RATED FOR 600V
- 11. 4-WIRE DELTA CONNECTED SYSTEMS HAVE THE PHASE WITH THE HIGHER VOLTAGE TO GROUND MARKED ORANGE OR IDENTIFIED BY OTHER EFFECTIVE MEANS.
- 12. ALL SOURCE CIRCUITS SHALL HAVE INDIVIDUAL SOURCE CIRCUIT PROTECTION 13. VOLTAGE DROP LIMITED TO 2% FOR DC CIRCUITS AND 3% FOR AC CIRCUITS
- 14. NEGATIVE GROUNDED SYSTEMS DC CONDUCTORS SHALL BE COLOR CODED AS
- FOLLOWS: DC POSITIVE- RED (OR MARKED RED), DC NEGATIVE- GREY (OR MARKED GREY)
- 15. POSITIVE GROUNDED SYSTEMS DC CONDUCTORS COLOR CODED:
- DC POSITIVE- GREY (OR MARKED GREY), DC NEGATIVE- BLACK (OR MARKED BLACK) 16. AC CONDUCTORS >4AWG COLOR CODED OR MARKED:
- PHASE A OR L1- BLACK, PHASE B OR L2- RED, PHASE C OR L3- BLUE, NEUTRAL-WHITE/GRAY
- \* USE-2 IS NOT INDOOR RATED BUT PV CABLE IS RATED THWN/THWN-2 AND MAY BE USED INSIDE
- \*\* USE-2 IS AVAILABLE AS UV WHITE
- 17. RIGID CONDUIT, IF INSTALLED, (AND/OR NIPPLES) MUST HAVE A PULL BUSHING TO PROTECT WIRES
- 18. IF CONDUIT DETERMINED TO BE RAN THROUGH ATTIC IN FIELD THEN CONDUIT WILL BE EITHER EMT, FMC, OR MC CABLE IF DC CURRENT COMPLYING WITH NEC 690.31, NEC 250.118(10). DISCONNECTING MEANS SHALL COMPLY WITH 690.13 AND 690.15 19. CONDUIT RAN THROUGH ATTIC WILL BE AT LEAST 18" BELOW ROOF SURFACE COMPLYING WITH NEC 230.6(4) AND SECURED NO GREATER THAN 6' APART PER NEC 330.30(B).

ā Moonligh Derby Lloyd 326 S

DRAWING BY Eric Thomas

DATE

February 16, 2021

PROJECT NUMBER

324685

ELEC. CALCS.

PAGE NUMBER PV6

### **MWARNING**

ELECTRIC SHOCK HAZARD

TERMINALS ON THE LINE AND LOAD SIDES MAY BE ENERGIZED PUBLICUM IN THE OPEN POSITION STATES

**DIRECT CURRENT** 

MAXIMUM VOLTAGE

MAX CIRCUIT CURRENT

PHOTOVOLTAIC POWER SOURCE

FOR PV DISCONNECTING MEANS WHERE ALL TERMINALS OF THE DISCONNECTING MEANS MAY BE ENERGIZED IN THE OPEN POSITION. [NEC 690.13(B), NEC 705.22]

#### **SOLAR PV SYSTEM EQUIPPED** WITH RAPID SHUTDOWN

TURN RAPID SHUTDOWN SWITCH TO THE "OFF" POSITION TO SHUT DOWN PV SYSTEM AND REDUCE SHOCK HAZARD IN THE ARRAY

TRAYS, COVERS AND ENCLOSURES OF JUNCTION BOXES, AND OTHER WIRING METHODS: SPACED AT MAXIMUM 10FT SECTION OR WHERE SEPARATED BY ENCLOSURES, WALLS, PARTITIONS, CEILINGS, OR FLOORS. [NEC 690.31(G)(3&4)]

AT DIRECT-CURRENT EXPOSED RACEWAYS, CABLE

FOR PV SYSTEMS THAT SHUT DOWN THE ARRAY AND CONDUCTORS LEAVING THE ARRAY SIGN TO BE LOCATED ON OR NO MORE THAN 3 FT AWAY FROM SERVICE DISCONNECTING MEANS TO WHICH THE PV SYSTEMS ARE CONNECTED AND SHALL INDICATE THE LOCATION OF ALL IDENTIFIED RAPID SHUTDOWN SWITCHES IF NOT AT THE SAME LOCATION. INEC 690.56(C)(1)(A)1

## **↑** WARNING

**⚠ WARNING** 

MAIN DISTRIBUTION UTILITY DISCONNECT(S)

POWER TO THIS BUILDING IS ALSO SUPPLIED

FROM A ROOF MOUNTED SOLAR ARRAY WITH A RAPID SHUTDOWN DISCONNECTING MEANS

GROUPED AND LABELED WITHIN LINE OF SITE

AND 10 FT OF THIS LOCATION.

POWER TO THIS BUILDING IS ALSO SUPPLIED FROM MAIN DISTRIBUTION UTILITY DISCONNECT LOCATED

**▲ WARNING** 

POWER TO THIS BUILDING IS ALSO SUPPLIED.

FROM ROOF MOUNTED SOLAR ARRAY, SOLAR

ARRAY RAPID SHUTDOWN DISCONNECT IS

LOCATED OUTSIDE NEXT TO UTILITY METER.

PERMANENT DIRECTORY TO BE LOCATED AT SOLAR ARRAY RAPID SHUTDOWN SWITCH DENOTING THE LOCATION OF THE SERVICE **EQUIPMENT LOCATION IF SOLAR ARRAY RAPID** SHUT DOWN DISCONNECT SWITCH IS NOT GROUPED AND WITHIN LINE OF SITE OF MAIN SERVICE DISCONNECTING MEANS. [NEC 705.10]

PERMANENT DIRECTORY TO BE LOCATED AT

MAIN SERVICE EQUIPMENT LOCATION IF ALL

MEANS (SOLAR ARRAY RAPID SHUTDOWN

MAIN SERVICE DISCONNECTING MEANS.

[NEC 690.56(C) & NEC 705.10].

ELECTRICAL POWER SOURCE DISCONNECTING

SWITCH) ARE GROUPED AND IN LINE OF SITE OF

PERMANENT DIRECTORY TO BE LOCATED AT MAIN SERVICE EQUIPMENT DENOTING THE LOCATION OF THE PV RAPID SHUTDOWN SYSTEM DISCONNECTING MEANS IF SOLAR ARRAY RAPID SHUT DOWN DISCONNECT SWITCH IS NOT GROUPED AND WITHIN LINE OF SITE OF MAIN SERVICE DISCONNECTING MEANS. [NEC 705.10, NEC 690.56(C)(1)]

AC JUNCTION BOX

OR AC COMBINER BOX

INTEGRATED DC DISCONNECT

PERMANENT DIRECTORY TO BE LOCATED AT AC COMBINER PANEL [NEC 110.21(B)]

AT EACH DC DISCONNECTING MEANS, INCLUDING THE DC DISCONNECT AT THE INVERTER. [NEC 690.53, NEC 690.13(B)]

# PHOTOVOLTAIC SYSTEM

VDC

**AMPS** 

RATED AC OUTPUT CURRENT NOMINAL OPERATING AC VOLTAGE

AC DISCONNECT

AT POINT OF INTERCONNECTION, MARKED AT AC DISCONNECTING MEANS [NEC 690.54, NEC 690.13 (B)]

#### SOLAR PV SYSTEM EQUIPPED WITH RAPID SHUTDOWN

RAPID SHUTDOWN

SWITCH FOR

SOLAR PV SYSTEM

WARNING: PHOTOVOLTAIC

**POWER SOURCE** 

TURN RAPID SHUTDOWN SWITCH TO THE "OFF" POSITION TO SHUT DOWN CONDUCTORS OUTSIDE THE ARRAY CONDUCTORS WITHIN THE ARRAY REMAIN ENERGIZED IN SUNLIGHT



LABELING DIAGRAM FOR MICRO INV.:

(8)

(3)&(4)

(11) OR (13)

OR PLACARD

(5)

(ONLY IF PV

NTERCONNECTIO

CONSISTS OF LOAD

SIDE BREAKER)

BREAKER USED

MAIN SERVICE PANEL

\_ \_ \_ \_

FOR PV SYSTEMS THAT ONLY SHUT DOWN CONDUCTORS LEAVING THE ARRAY SIGN TO BE LOCATED ON OR NO MORE THAN 3 FT AWAY FROM SERVICE DISCONNECTING MEANS TO WHICH THE PV SYSTEMS ARE CONNECTED AND SHALL INDICATE THE LOCATION OF ALL IDENTIFIED RAPID SHUTDOWN SWITCHES IF NOT AT THE SAME LOCATION. [NEC 690.56(C)(1)(B)]

SIGN LOCATED AT RAPID SHUT DOWN

IS MADE)

DISCONNECT SWITCH [NEC 690.56(C)(3)].

**EXISTING SUB PANEL** 

(IF WHERE POINT OF

INTERCONNECTION

(3)&(4)

BREAKER USED

(ONLY IF PV

ITERCONNECTIO

ONSISTS OF LOAD

SIDE BREAKER)

PV COMBINER

IF USED TO COMBINE

PV OUTPUT CIRCUITS

(3)

(6)

(11)

(14)

SURPANEL -

AC DISCONNECT

(12) OR

PLACARD

(3)

(10)

PHOTOVOLTAIC SYSTEM **COMBINER PANEL** 

#### ♠ WARNING

DO NOT ADD LOADS

1403 N RESEARCH WAY, BUILDING J OREM, UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUERAVENSOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION. EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT. WITHOUT THE WRITTEN PERMISSION OF BLUERAVENSOLAR LLC.



CONTRACTOR:

**BRS FIELD OPS** 385.498.6700

> 27526 Carolina North (

DC

 $\stackrel{>}{\geq}$ 

775

 $\infty$ 

SIZE:

SYSTEM

DC

۵ Fuquay-Varina, 326 Moonlight Derby Lloyd I

DRAWING BY

SIT

INFORMATION:

**Eric Thomas** 

DATE

February 16, 2021

PROJECT NUMBER

324685

SHEET NAME

LABELS

REVISION

\_\_\_\_

PAGE NUMBER

PV8

**↑ WARNING** 

**DUAL POWER SUPPLY** SOURCES: UTILITY GRID AND

PV SOLAR ELECTRIC SYSTEM

**∴WARNING** 

INVERTER OUTPUT CONNECTION

DO NOT RELOCATE

THIS OVERCURRENT

DEVICE

IF INTERCONNECTING ON THE LOAD SIDE, INSTALL THIS LABEL ANYWHERE THAT IS POWERED BY BOTH THE UTILITY AND THE SOLAR PV SYSTEM: THE MAIN SERVICE PANEL AND SUB-PANELS. [NEC 705.12(B)(3)]

PLACED ADJACENT TO THE BACK-FED BREAKER FROM THE INVERTER IF TIE IN CONSISTS OF LOAD SIDE CONNECTION TO BUSBAR. [NEC 705.12(B)(2)(3)(b)]

## **AWARNING**

THIS EQUIPMENT FED BY MULTIPLE SOURCES. TOTAL RATING OF ALL OVERCURRENT DEVICES, EXCLUDING MAIN SUPPLY OVERCURRENT DEVICE, SHALL NOT EXCEED AMPACITY OF BUSBAR.


(ONLY IF 3 OR MORE SUPPLY SOURCES TO A BUSBAR)

SIGN LOCATED AT LOAD CENTER IF IT CONTAINS 3 OR MORE POWER SOURCES. [NEC 705.12(B)(2)(3)(C)]

- LABELS CALLED OUT ACCORDING TO ALL COMMON CONFIGURATIONS. ELECTRICIAN TO DETERMINE EXACT REQUIREMENTS IN THE FIELD PER CURRENT NEC AND LOCAL CODES AND MAKE APPROPRIATE ADJUSTMENTS
- LABELING REQUIREMENTS BASED ON THE 2017 NATIONAL ELECTRIC CODE, OSHA STANDARD 19010 145 ANSI 7535
- MATERIAL BASED ON THE REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION.
- LABELS TO BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT INVOLVED AND SHALL NOT BE HANDWRITTEN [NEC 110.21]
- LABELS TO BE A MINIMUM LETTER HEIGHT OF 3/8", WHITE ON RED BACKGROUND; REFLECTIVE, AND PERMANENTLY AFFIXED [IFC 605.11.1.1]

# LABELING DIAGRAM FOR STRING INV. / DC OPTIMIZER INV.:

#### MAIN SERVICE PANEL



\*ELECTRICAL DIAGRAM SHOWN ABOVE IS FOR LABELING PURPOSES ONLY. NOT AN ACTUAL REPRESENATION OF EQUIPMENT AND CONNECTIONS TO BE INSTALLED. LABEL LOCATIONS PRESENTED MAY VERY DEPENDING ON TYPE OF INTERCONNECTION METHOD AND LOCATION PRESENTED ON PV5 OF 3 LINE DIAGRAM. PV5 LINE DIAGRAM TO REFLECT ACTUAL REPRESENTATION OF PROPOSED SCOPE OF WORK.

# **Enphase** IQ 7 and IQ 7+ **Microinverters**

IQ7

The high-powered smart grid-ready

Enphase IQ 7 Micro™ and Enphase IQ 7+ Micro™ dramatically simplify the installation process while achieving the highest system efficiency.

Part of the Enphase IQ System, the IQ 7 and IQ 7+ Microinverters integrate with the Enphase IQ Envoy™, Enphase IQ Battery™, and the Enphase Enlighten™ monitoring and analysis software.

IQ Series Microinverters extend the reliability standards set forth by previous generations and undergo over a million hours of power-on testing, enabling Enphase to provide an industry-leading warranty of up to 25 years.

## Easy to Install

- · Lightweight and simple
- · Faster installation with improved, lighter two-wire cabling
- Built-in rapid shutdown compliant (NEC 2014 & 2017)

#### Productive and Reliable

- Optimized for high powered 60-cell/120 half-cell and 72cell/144 half-cell\* modules
- More than a million hours of testing
- · Class II double-insulated enclosure
- UL listed

#### **Smart Grid Ready**

- · Complies with advanced grid support, voltage and frequency ride-through requirements
- · Remotely updates to respond to changing grid requirements
- Configurable for varying grid profiles
- Meets CA Rule 21 (UL 1741-SA)

<sup>\*</sup> The IQ 7+ Micro is required to support 72-cell/144 half-cell modules.



INPUT DATA (DC)

Enphase IQ 7 and IQ 7+ Microinverters

0 : 2::::: (2 0)			•		
Commonly used module pairings <sup>1</sup>	235 W - 350 W +	F		235 W - 440 W -	+
Module compatibility	60-cell/120 half	f-cell PV modules		60-cell/120 half	f-cell and 72-
	only			cell/144 half-ce	II PV modules
Maximum input DC voltage	48 V			60 V	
Peak power tracking voltage	27 V - 37 V			27 V - 45 V	
Operating range	16 V - 48 V			16 V - 60 V	
Min/Max start voltage	22 V / 48 V			22 V / 60 V	
Max DC short circuit current (module lsc)	15 A			15 A	
Overvoltage class DC port	II			II	
DC port backfeed current	0 A			0 A	
PV array configuration		ed array; No addi <sup>.</sup>			
	AC side protect	ion requires max	20 <i>A</i>	per branch circu	uit
OUTPUT DATA (AC)	IQ 7 Microinve	erter		IQ 7+ Microin	verter
Peak output power	250 VA			295 VA	
Maximum continuous output power	240 VA			290 VA	
Nominal (L-L) voltage/range <sup>2</sup>	240 V / 211-264 V	208 V / 183-229 V		240 V / 211-264 V	208 V / 183-229 V
Maximum continuous output current	1.0 A (240 V)	1.15 A (208 V)		1.21 A (240 V)	1.39 A (208 V)
Nominal frequency	60 Hz			60 Hz	
Extended frequency range	47 - 68 Hz			47 - 68 Hz	
AC short circuit fault current over 3 cycles	5.8 Arms			5.8 Arms	
Maximum units per 20 A (L-L) branch circuit <sup>3</sup>	16 (240 VAC)	13 (208 VAC)		13 (240 VAC)	11 (208 VAC)
Overvoltage class AC port	III			III	
AC port backfeed current	18 mA			18 mA	
Power factor setting	1.0			1.0	
Power factor (adjustable)	0.85 leading (	0.85 lagging		0.85 leading (	0.85 lagging
EFFICIENCY	@240 V	@208 V		@240 V	@208 V
Peak efficiency	97.6 %	97.6 %		97.5 %	97.3 %
CEC weighted efficiency	97.0 %	97.0 %		97.0 %	97.0 %

I07PLUS-72-2-US

	Ambient temperature range	-40°C to +65°C
	Relative humidity range	4% to 100% (condensing)
	0	NAO 4 / A

MC4 (or Amphenol H4 UTX with additional Q-DCC-5 adapter) Connector type Dimensions (HxWxD) 212 mm x 175 mm x 30.2 mm (without bracket) 1.08 kg (2.38 lbs) Weight

Cooling Natural convection - No fans Approved for wet locations Yes

Environmental category / UV exposure rating

Pollution degree Class II double-insulated, corrosion resistant polymeric enclosure Enclosure

NEMA Type 6 / outdoor

**FEATURES** 

**MECHANICAL DATA** 

Communication Power Line Communication (PLC) Monitoring Enlighten Manager and MyEnlighten monitoring options. Both options require installation of an Enphase IQ Envoy.

Disconnecting means The AC and DC connectors have been evaluated and approved by UL for use as the load-break disconnect required by NEC 690.

Compliance CA Rule 21 (UL 1741-SA)

UL 62109-1, UL1741/IEEÉ1547, FCC Part 15 Class B, ICES-0003 Class B, CAN/CSA-C22.2 NO. 107.1-01

This product is UL Listed as PV Rapid Shut Down Equipment and conforms with NEC 2014, NEC 2017, and NEC 2020 section 690.12 and C22.1-2015 Rule 64-218 Rapid Shutdown of PV Systems, for AC and DC conductors, when installed according manufacturer's instructions.

- 1. No enforced DC/AC ratio. See the compatibility calculator at <a href="https://enphase.com/en-us/support/module-compatibility">https://enphase.com/en-us/support/module-compatibility</a>.

**ENPHASE**. To learn more about Enphase offerings, visit **enphase.com** ENPHASE



1403 N RESEARCH WAY, BUILDING J OREM, UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.



CONTRACTOR: **BRS FIELD OPS** 385.498.6700

Nominal voltage range can be extended beyond nominal if required by the utility.
 Limits may vary. Refer to local requirements to define the number of microinverters per branch in your area.

© 2020 Enphase Energy. All rights reserved. Enphase, the Enphase logo, Enphase IQ 7, Enphase IQ 7+, Enphase IQ Battery,

SPEC SHEET

REVISION

0


AGE NUMBER SS



Enphase Enlighten, Enphase IQ Envoy, and other trademarks or service names are the trademarks of Enphase Energy, Inc. Data subject to change. 2020-08-12

# **Enphase IQ Combiner 3**

(X-IQ-AM1-240-3)



#### Smart

busbar assembly.

 Includes IQ Envoy for communication and control

The **Enphase IQ Combiner 3**™ with Enphase

streamlines PV and storage installations by

providing a consistent, pre-wired solution for

residential applications. It offers up to four

2-pole input circuits and Eaton BR series

IQ Envoy™ consolidates interconnection

equipment into a single enclosure and

- · Flexible networking supports Wi-Fi, Ethernet, or cellular
- Optional AC receptacle available for PLC
- Provides production metering and optional consumption monitoring

#### Simple

- · Reduced size from previous combiner
- · Centered mounting brackets support single stud mounting
- · Supports back and side conduit entry
- Up to four 2-pole branch circuits for 240 VAC plug-in breakers (not included)
- 80 A total PV or storage branch circuits

#### Reliable

- Durable NRTL-certified NEMA type 3R enclosure
- Five-year limited warranty
- UL listed

#### **Enphase IQ Combiner 3**

#### MODEL NUMBER

Circuit Breakers

IQ Combiner 3 IQ Combiner 3 with Enphase IQ Envoy™ printed circuit board for integrated revenue grade PV X-IQ-AM1-240-3 production metering (ANSI C12.20 +/- 0.5%) and optional\* consumption monitoring (+/- 2.5%).

#### ACCESSORIES and REPLACEMENT PARTS (not included, order separately)

Enphase Mobile Connect™ CELLMODEM-03 (4G/12-year data plan) CELLMODEM-01 (3G/5-year data plan) Consumption Monitorina\* CT CT-200-SPLIT \* Consumption monitoring is required for Enphase Storage Systems

Plug and play industrial grade cellular modem with data plan for systems up to 60 microinverters. (Available in the US, Canada, Mexico, Puerto Rico, and the US Virgin Islands, CELLMODEM-M1 (4G based LTE-M/5-year data plan) where there is adequate cellular service in the installation area.)

Split core current transformers enable whole home consumption metering (+/- 2.5%).

Supports Eaton BR210, BR215, BR220, BR230, BR240, BR250, and BR260 circuit breakers.

Wireless USB adapter Installed at the IQ Envoy. For communications with Enphase Encharge™ storage and Enphase COMMS-KIT-01 Enpower™ smart switch. Includes USB cable for connection to IQ Envoy or Enphase IQ Combiner™ and allows redundant wireless communication with Encharge and Enpower

BRK-10A-2-240 Circuit breaker, 2 pole, 10A, Eaton BR210 BRK-15A-2-240 Circuit breaker, 2 pole, 15A, Eaton BR215 BRK-20A-2P-240 Circuit breaker, 2 pole, 20A, Eaton BR220

EPLC-01 Power line carrier (communication bridge pair), quantity - one pair XA-PLUG-120-3 Accessory receptacle for Power Line Carrier in IQ Combiner 3 (required for EPLC-01)

XA-ENV-PCBA-3 Replacement IQ Envoy printed circuit board (PCB) for Combiner 3

#### **ELECTRICAL SPECIFICATIONS**

Rating	Continuous duty
System voltage	120/240 VAC, 60 Hz
Eaton BR series busbar rating	125 A
Max. continuous current rating (output to grid)	65 A
Max. fuse/circuit rating (output)	90 A
Branch circuits (solar and/or storage)	Up to four 2-pole Eaton BR series Distributed Generation (DG) breakers only (not included)
Max. continuous current rating (input from PV)	64 A
Max. total branch circuit breaker rating (input)	80A of distributed generation / 90A with IQ Envoy breaker included
Production Metering CT	200 A solid core pre-installed and wired to IQ Envoy

#### MECHANICAL DATA

MEGHANICAE DATA	
Dimensions (WxHxD)	49.5 x 37.5 x 16.8 cm (19.5" x 14.75" x 6.63"). Height is 21.06" (53.5 cm with mounting brackets
Weight	7.5 kg (16.5 lbs)
Ambient temperature range	-40° C to +46° C (-40° to 115° F)
Cooling	Natural convection, plus heat shield
Enclosure environmental rating	Outdoor, NRTL-certified, NEMA type 3R, polycarbonate construction
Wire sizes	<ul> <li>20 A to 50 A breaker inputs: 14 to 4 AWG copper conductors</li> <li>60 A breaker branch input: 4 to 1/0 AWG copper conductors</li> <li>Main lug combined output: 10 to 2/0 AWG copper conductors</li> <li>Neutral and ground: 14 to 1/0 copper conductors</li> <li>Always follow local code requirements for conductor sizing.</li> </ul>
Altitude	To 2000 meters (6,560 feet)

#### INTERNET CONNECTION OPTIONS

Integrated Wi-Fi	802.11b/g/n
Ethernet	Optional, 802.3, Cat5E (or Cat 6) UTP Ethernet cable (not included)
Cellular	Optional, CELLMODEM-01 (3G) or CELLMODEM-03 (4G) or CELLMODEM-M1 (4G based LTE-M) (not included)
COMPLIANCE	·

#### COMPLIANCE

Compliance, Combiner	UL 1741, CAN/CSA C22.2 No. 107.1, 47 CFR, Part 15, Class B, ICES 003 Production metering: ANSI C12.20 accuracy class 0.5 (PV production)
Compliance, IQ Envoy	UL 60601-1/CANCSA 22.2 No. 61010-1

To learn more about Enphase offerings, visit enphase.com

© 2018 Enphase Energy. All rights reserved. Enphase, the Enphase logo, IQ Combiner 3, and other trademarks or service names are the



OREM, UT 84097 800-377-4480 WWW.BLUERAVENSOLAR.COM

1403 N RESEARCH WAY, BUILDING J

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND

USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.



CONTRACTOR: **BRS FIELD OPS** 385.498.6700


SPEC SHEET

SS





# REC TWINPEAK 3 MONO BLACK SERIES



					(1.5
Measurements in mm [in]					
ELECTRICAL DATA @ STC		Product co	de*: RECxxxTP3M	B <mark>la</mark> ck	
Power Output - P <sub>MAX</sub> (Wp)	315	320	325	330	335
Watt Class Sorting-(W)	-0/+5	-0/+5	-0/+5	<del>-</del> 0/+5	-0/+5
Nominal Power Voltage - V <sub>MPP</sub> (V)	33.6	33.8	34.1	34.3	34.6
Nominal Power Current - $I_{MPP}(A)$	9.40	9.50	9.54	9.62	9.69
Open Circuit Voltage - V <sub>oc</sub> (V)	38.7	39.1	39.5	39.9	40.2
Short Circuit Current - $I_{SC}(A)$	10.30	10.30	10.36	10.39	10.42
Panel Efficiency (%)	18.8	19.1	19.4	19.7	20.0
Values at standard test conditions (STC: air mass A of P <sub>MAX</sub> , V <sub>oc</sub> & I <sub>sc</sub> ±3% within one watt class. At a lov					

ELECTRICAL DATA @ NMOT		Product code	*: RECxxxTP3M	l Bl <mark>ac</mark> k	
Power Output - P <sub>MAX</sub> (Wp)	235	238	242	246	250
Nominal Power Voltage - V <sub>MPP</sub> (V)	31.3	31.5	31.7	31.9	32.2
Nominal Power Current - I <sub>MPP</sub> (A)	7.51	7.57	7.63	7.70	7.75
Open Circuit Voltage - V <sub>oc</sub> (V)	36.1	36.4	36.8	37.1	37.5
Short Circuit Current - I <sub>SC</sub> (A)	8.23	8.26	8.29	8.31	8.34
Nominal module operating temperature (NMOT: air	r mass AM 1.5, irradiar	nce 800 W/m² <mark>, te</mark> n	nperature 20°C, wind	dsp <mark>ee</mark> d 1 m/s).	

dicates the nominal power class (P<sub>MAX</sub>) at STC indicated above.

# CERTIFICATIONS LINE LI

Standard REC ProTrust Installed by an REC Certified Solar Yes Professional System Size Any ≤25kW 25-500kW Product Warranty (yrs) 20 25 25 Power Warranty (yrs) 25 25 25 Labor Warranty (yrs) 25 10 97.5% 97.5% 97.5% Annual Degradation 0.7% 0.7% 0.7% 80.7% 80.7% 80.7% Power in Year 25

20.0% EFFICIENCY

YEAR PRODUCT WARRANTY

25 YEAR LINEAR POWER OUTPUT WARRANTY

TEMPERATURE RATINGS	
Nominal Module Operating Temperature:	44.6°C (±2°C)
Temperature coefficient of P <sub>MAX</sub> :	-0.37 %/°C
Temperature coefficient of V <sub>oc</sub> :	-0.28 %/°C
Temperature coefficient of I <sub>sc</sub> :	0.04 %/°C

Cells:	120 half-cut mono-Si p-type PERC cells 6 strings of 20 cells in series
Glass:	0.13" (3.2 mm) solar glass with anti-reflective surface treatment
Back sheet:	Highly resistant polyester polyolefin construction (black)
Frame:	Anodized aluminum (black)
Junction box:	3-part with 3 bypass diodes, IP67 rated 12 AWG (4 mm²) PV wire, 39" + 47" (1.0 m + 1.2 m)
c .	C. T. LUMCADV VDTA/DV VCTA

MAXIMUM RATINGS

Operational temperature: -40 ... +185°F (-40 ... +85°C)

Maximum system voltage: 1000 V

Design load (+): snow 3600 Pa (75.2 lbs/ft²)\* 5400 Pa (112.8 lbs/ft²)\* 1600 Pa (33.4 lbs/ft²)\* 2400 Pa (50 lbs/ft²)\* 2400 Pa (50 lbs/ft²)\* 2400 Pa (50 lbs/ft²)\* 20 A

Maxreverse current: 20 A

ANICAL DATA

nsions: 66.3 x 39.25 x 1.5 (1683 x 997 x 38 mm)

17.98 ft² (1.68 m²)

nt: 41.7 lbs (18.9 kg)

**Note!** Specifications subject to change without notice.

REC Group is an international pioneering solar energy company dedicated to empowering consumers with clean, affordable solar power in order to facilitate global energy transitions. Committed to quality and innovation, REC offers photovoltaic modules with leading high quality, backed by an exceptional low warranty claims rate of less than 100ppm. Founded in Norway in 1996, REC employs 2,000 people and has an annual solar panel capacity of 1.8 GW. Withover 10 GW installed worldwide, REC is empowering more than 16 million people with clean solar energy, REC Group is a Bluestar Elkem company withheadquarters in Norway, operational headquarters in Singapore, and regional bases in North America, Europe, and Asia-Pacific.



12 AWG (4 mm²)



1403 N RESEARCH WAY, BUILDING J OREM, UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.



CONTRACTOR: BRS FIELD OPS 385.498.6700

.com

SPEC SHEET

PAGE NUMBER REVISION 0



# **UNIRAC INC.**

# **LETTER REPORT**

#### **SCOPE OF WORK**

ADDITION OF MODULES TO THE UNIRAC SFM CDR 102393982LAX-002

#### **REPORT NUMBER**

104430210LAX-001a


#### **ISSUE DATE**

24-Sept-2020

#### **PAGES**

#### **DOCUMENT CONTROL NUMBER**

GFT-OP-10a (21-June-2019) © 2019 INTERTEK





LETTER REPORT

September 24, 2020

1411 Broadway Blvd NE

Albuquerque, NM 87102-1545

klaus.nicolaedis@unirac.com

**Subject:** Addition of modules to the Unirac SFM CDR 102393982LAX-002

to the requirements contained in the following standards:

This letter report represents the results of our evaluation of the above referenced product(s)

This investigation was authorized by quote # Qu-01101732 dated 08-17-2020. The scope of the project was to evaluate and add module frames to the SFM CDR 102393982LAX-002.

Mounting Systems, Mounting Devices, Clamping/Retention Devices, and Ground Lugs for Use with Flat-Plate Photovoltaic Modules and Panels [UL 2703:2015 Ed.1]

Model

TP3M, TP3M Black

SIL-xxx-BL, SIL-xxx-HL

Q.PEAK DUO L-G7, Q.PEAK DUO L-G7.1, Q.PEAK DUO L-G7.2, Q.PEAK DUO L-G7.3,

Q.PEAK DUO L-G8. Q.PEAK DUO L-G8.1. Q.PEAK DUO L-G8.2, Q.PEAK DUO L-G8.3

SIL-xxx-NT, SIL-xxx-ML, SIL-xxx-NL,

Klaus Nicolaedis

Unirac Inc.

Dear Klaus.

**SECTION 1** 

SUMMARY

**SECTION 2 EVALUATION** 

Hanwha Q Cell

Silfab

25791 Commercentre Drive Lake Forest, CA 92630

Telephone: 949-448-4100 Facsimile: 949-448-4111 www.intertek.com

Unirac Inc. Intertek Report No: . 104430210LAX-001a

LETTER REPORT

Intertek Report No. 104430210LAX-001a SECTION 3

Intertek Project No. G104430210 PROJECT STATUS & ACTION

Ph: 505-462-2190 Issuance of this letter report provides results of the evaluation covered by Intertek Project No. G104430210.

> If there are any questions regarding the results contained in this report, or any of the other services offered by Intertek, please do not hesitate to contact your dedicated Intertek Project Manager.

Reviewed by: Adam Muliawan Completed by: Abhinav Prakash Title: Project Engineer Title: Reviewer Idam Muliana Signature: Signature Date 09-24-2020 Date: 09-25-2020

Please note: this Letter Report does not represent authorization for the use of any Intertek certification marks.

1403 N RESEARCH WAY, BUILDING J OREM, UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.



CONTRACTOR: **BRS FIELD OPS** 385.498.6700

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client, Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification

Version: 6-March-2017 Page 2 of 3 GFT-OP-10a

Version: 6-March-2017 Page 3 of 3 GFT-OP-10a SHEET NAME

SPEC SHEET

PAGE NUMBER REVISION SS



#### pe.eaton.com

# **General Duty Non-Fusible Safety Switch**

DG222UGB

UPC:782114731130

#### **Dimensions:**

Height: 7 INLength: 6.41 INWidth: 8.4 IN

#### Weight:6 LB

**Notes:**WARNING! Switch is not approved for service entrance unless a neutral kit is installed.

#### Warranties:

 Eaton Selling Policy 25-000, one (1) year from the date of installation of the Product or eighteen (18) months from the date of shipment of the Product, whichever occurs first.

#### Specifications:

• Type: General Duty/Non-Fusible

Amperage Rating: 60A
 Enclosure: NEMA 1

• Enclosure Material: Painted steel

Fuse Configuration: Non-fusible
Number Of Poles: Two-pole

• Number Of Wires: Two-wire

• Product Category: General Duty Safety Switch

• Voltage Rating: 240V

#### Supporting documents:

• Eatons Volume 2-Commercial Distribution

Eaton Specification Sheet - DG222UGB

#### **Certifications:**

UL Listed

Product compliance: No Data





1403 N RESEARCH WAY, BUILDING J OREM, UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.




CONTRACTOR: BRS FIELD OPS 385.498.6700

HEET NAME

SPEC SHEET

PAGE NUMBER

0





1403 N RESEARCH WAY, BUILDING J

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.




CONTRACTOR: **BRS FIELD OPS** 385.498.6700

SPEC SHEET

0

PAGE NUMBER REVISION SS





1403 N RESEARCH WAY, BUILDING J OREM, UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.




CONTRACTOR: BRS FIELD OPS 385.498.6700

SHEET NAM

SPEC SHEET

PAGE NUMBER





1403 N RESEARCH WAY, BUILDING J OREM, UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.



CONTRACTOR: BRS FIELD OPS 385.498.6700

SHEET NAME


SPEC SHEET

PAGE NUMBER



# SYSTEM BONDING & GROUNDING | Q INSTALLATION GUIDE | PAGE





Single Use Only


**TERMINAL TORQUE, Install Conductor and** torque to the following:

4-6 AWG: 35in-lbs 8 AWG: 25 in-lbs 10-14 AWG: 20 in-lbs

## **LUG DETAIL & TORQUE INFO**

## Ilsco Lay-In Lug (GBL-4DBT)

- 10-32 mounting hardware
- Torque = 5 ft-lb
- AWG 4-14 Solid or Stranded



**TERMINAL TOROUE, Install Conductor and** torque to the following: 4-14 AWG: 35in-lbs

#### **LUG DETAIL & TORQUE INFO**

#### Ilsco Flange Lug(SGB-4)

- 1/4" mounting hardware
- Torque = 75 in-lb
- AWG 4-14 Solid or Stranded

### **WEEBLUG** Single Use Only



**TERMINAL TOROUE, Install Conductor and** torque to the following: 6-14 AWG: 7ft-lbs


#### **LUG DETAIL & TORQUE INFO**

#### Wiley WEEBLug (6.7)

- 1/4" mounting hardware
- Torque = 10 ft-lb
- AWG 6-14 Solid or Stranded


#### NOTE: ISOLATE COPPER FROM ALUMINUM CONTACT TO PREVENT CORROSION


System bonding is accomplished through modules. System grounding accomplished by attaching a ground lug to any module at a location on the module specified by the module manufacturer.



#### E-W BONDING PATH:


E-W module to module bonding is accomplished with 2 pre-installed bonding pins which engage on the secure side of the MicrorailTM and splice.





#### N-S BONDING PATH:

N-S module to module bonding is accomplished with bonding clamp with 2 integral bonding pins. (refer also to alternate method)





#### TRIMRAIL BONDING PATH:

Trimrail to module bonding is accomplished with bonding clamp with integral bonding pin and bonding T-bolt. (refer also to alternate method)



1403 N RESEARCH WAY, BUILDING J

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BI USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PAR TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.



CONTRACTOR: **BRS FIELD OPS** 385.498.6700

SPEC SHEET

AGE NUMBER SS



# UL CODE COMPLIANCE NOTES | R INSTALLATION GUIDE | PAGE

#### SYSTEM LEVEL FIRE CLASSIFICATION

The system fire class rating requires installation in the manner specified in the SUNFRAME MICRORAIL (SFM) Installation Guide. SFM has been classified to the system level fire portion of UL 1703. This UL 1703 classification has been incorporated into the UL 2703 product certification. SFM has achieved Class A, B & C system level performance for low slope & steep sloped roofs when used in conjunction with type 1 and type 2 modules. Class A, B & C system level fire

performance is inherent in the SFM design, and no additional mitigation measures are required. The fire classification rating is valid for any roof pitch. There is no required minimum or maximum height limitation above the roof deck to maintain the Class A, B & C fire rating for SFM. SUNFRAME MICRORAIL™ components shall be mounted over a fire resistant roof covering rated for the application.

Module Type	Roof Slope	System Level Fire Rating	Microrail Direction	Module Orientation	Mitigation Required
Type 1 and Type 2	Steep Slope & Low Slope	Class A, B & C	East-West	Landscape OR Portrait	None Required


#### **UL2703 TEST MODULES**


See page "S" for a list of modules that were electrically and mechanically tested or qualified with the SUNFRAME MICRORAIL (SFM) components outlined within this Installation Guide.

- Maximum Area of Module = 22.3 sqft
- UL2703 Design Load Ratings:
  - a) Downward Pressure 113 PSF / 5400 Pa
  - b) Upward Pressure 50 PSF / 2400 Pa
  - c) Down-Slope Load 30 PSF / 1400 Pa
- Tested Loads:
  - a) Downward Pressure 170 PSF / 8000 Pa
  - b) Upward Pressure 75 PSF / 3500 Pa
  - c) Down-Slope Load 45 PSF / 2100 Pa
- Maximum Span = 6ft
- Use with a maximum over current protection device OCPD of 30A
- System conforms to UL Std 2703, certified to LTR AE-001-2012
- Rated for a design load of 2400 Pa / 5400 Pa with 24 inch span

#### LABEL MARKINGS

- System fire class rating: See installation instructions for installation requirements to achieve a specified system fire class rating with Unirac.
- Unirac SUNFRAME MICRORAIL™ is listed to UL 2703.
- All splices within a system are shipped with marking indicating date and location of manufacture.







1403 N RESEARCH WAY, BUILDING J

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.



CONTRACTOR: BRS FIELD OPS 385.498.6700

SHEET NAME

SPEC SHEET

PAGE NUMBER



# TESTED / CERTIFIED MODULE LIST | S | NSTALLATION GUIDE | PAGE

Manufacture	Module Model / Series	
Aleo	P-Series	
Astronergy	CHSM6612P, CHSM6612P/HV, CHSM6612M, CHSM6612M/HV, CHSM6610M (BL)(BF)/(HF), CHSM72M-HC	
Auxin	AXN6M610T, AXN6P610T, AXN6M612T & AXN6P612T	
Axitec	AXI Power, AXI Premium, AXI Black Premium	
Boviet	BVM6610, BVM6612	
BYD	P6K & MHK-36 Series	
Canadian Solar	CS6V-M, CS6P-P, CS6K-M, CS5A-M, CS6K-MS, CS6U-P, CS6U-M, CS6X-P, CS6K-MS, CS6K-M, CS3U-P, CS6P-P, CS6P-M, CS3U-P, CS3U-MS, CS3K-P, CS3K-MS, CS1K-MS, CS3K, CS3U, CS3U-MB-AG, CS3K-MB-AG, CS6K, CS6U, CS3L, CS3W, CS1H-MS, CS1U-MS	
Centrosolar America	C-Series & E-Series	
CertainTeed	CT2xxMxx-01, CT2xxPxx-01, CTxxxMxx-02, CTxxxM-03, CTxxxMxx-04, CTxxxHC11-04	
Dehui	DH-60M	
Eco Solargy	Orion 1000 & Apollo 1000	
FreeVolt	Mono PERC	
GCL	GCL-P6 & GCL-M6 Series	
Hansol	TD-AN3, TD-AN4, UB-AN1, UD-AN1	
Heliene	36M, 60M, 60P, 72M & 72P Series	
HT Solar	HT60-156(M) (NDV) (-F), HT 72-156(M/P)	
Hyundai	KG, MG, TG, RI, RG, TI, MI, HI & KI Series	
ITEK	iT, iT-HE & iT-SE Series	
Japan Solar	JPS-60 & JPS-72 Series	

Manufacture	Module Model / Series
JA Solar	JAP6 60-xxx, JAM6-60-xxx/SI, JAM6(K)-60/xxx, JAP6(k)-72-xxx/4BB, JAP72SYY-xxx/ZZ, JAP6(k)-60-xxx/4BB, JAP60SYY-xxx/ZZ, JAM6(k)-72-xxx/ZZ, JAM72SYY-xxx/ZZ, JAM6(k)-60-xxx/ZZ, JAM60SYY-xxx/ZZ. i. YY: 01, 02, 03, 09, 10 ii. ZZ: SC, PR, BP, HiT, IB, MW
Jinko	JKM & JKMS Series
Kyocera	KU Series
LG Electronics	LG xxx S1C-A5, LG xxx N1C-A5, LGxxxQ1C(Q1K)-A5, LGxxxN1C(N1K)-A5, LGxxxS1CA5, LGxxxA1C-A5, LGxxxN2T-A4, LGxxxN2T-A5, LGxxxN2W-A5 LGxxxS2W-A5, LGxxxE1C-A5, LGxxxS2W-G4 LGxxxN1C(N1K)-G4, LGxxxN2W-G4, LGxxxS1C-G4, LGxxxE1K-A5, LGxxxN2T-J5, LGxxxN1K(N1C)-V5, LGxxxQ1C(N2W)-V5,
LONGi	LR6-60 & LR6-72 Series, LR4-60 & LR4-72 Series
Mission Solar Energy	MSE Series
Mitsubishi	MJE & MLE Series
Neo Solar Power Co.	D6M & D6P Series
Panasonic	VBHNxxxSA15 & SA16, VBHNxxxSA17 & SA18, VBHNxxxSA17(E/G) & SA18E, VBHNxxxKA01 & KA03 & KA04, VBHNxxxZA01, VBHNxxxZA02, VBHNxxxZA03, VBHNxxxZA04
Peimar	SGxxxM (FB/BF)
Phono Solar	PS-60, PS-72
Q.Cells	Plus, Pro, Peak, G3, G4, G5, G6(+), G7, G8(+) Pro, Peak L-G2, L-G4, L-G5, L-G6, L-G7

Manufacture	Module Model / Series
	PEAK Energy Series,
	PEAK Energy BLK2 Series,
REC	PEAK Energy 72 Series,
REC	TwinPeak 2 Series,
	TwinPeak 2 BLK2 Series,
	TwinPeak Series
Renesola	Vitrus2 Series & 156 Series
Risen	RSM Series
S-Energy	SN72 & SN60 Series (40mm)
Seraphim	SEG-6 & SRP-6 Series
Sharp	NU-SA & NU-SC Series
Silfab	SLA, SLG & BC Series
Solaria	PowerXT
C = 1 = 1/4/2 11 d	Sunmodule Protect,
SolarWorld	Sunmodule Plus
Sonali	SS 230 - 265
Suntech	STP
Suniva	MV Series & Optimus Series
Sun Edison/Flextronics	F-Series, R-Series & FLEX FXS Series
SunPower	X-Series, E-Series & P-Series
Talogua	TP572, TP596, TP654, TP660,
Talesun	TP672, Hipor M, Smart
Tesla	SC, SC B, SC B1, SC B2
Trina	PA05, PD05, DD05, DE06, DD06, PE06,
Trina	PD14, PE14, DD14, DE14, DE15, PE15H
Upsolar	UP-MxxxP(-B), UP-MxxxM(-B)
URE	D7MxxxH8A, D7KxxxH8A, D7MxxxH7A
Vikram	Eldora, Solivo, Somera
Waaree	AC & Adiya Series
Winaico	WST & WSP Series
Yingli	YGE & YLM Series

Please see the SFM UL2703Construction Data Report at Unirac.com to ensure the exact solar module selected is approved for use with SFM. SFM Infinity is not compatible with module frame height of less than 32mm and more than 40mm. See page J for further information.



1403 N RESEARCH WAY, BUILDING J OREM, UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.



CONTRACTOR: BRS FIELD OPS 385.498.6700

OLIFET NAME

SPEC SHEET

PAGE NUMBER

O

# intertek

**AUTHORIZATION TO MARK** 

This authorizes the application of the Certification Mark(s) shown below to the models described in the Product(s) Covered section when made in accordance with the conditions set forth in the Certification Agreement and Listing Report. This authorization also applies to multiple listee model(s) identified on the correlation page of the Listing Report.

This document is the property of Intertek Testing Services and is not transferable. The certification mark(s) may be applied only at the location of the Party Authorized To Apply Mark.

Applicant: Unirac, Inc Manufacturer: 1411 Broadway Blvd NE Address: Address: Albuquerque, NM 87102 USA Country: Country: Klaus Nicolaedis Contact: Contact: **Todd Ganshaw** 505-462-2190 Phone: Phone: 505-843-1418 FAX: NA FAX: klaus.nicolaedis@unirac.com Email: Email: toddg@unirac.com Party Authorized To Apply Mark: Same as Manufacturer

**Report Issuing Office:** Lake Forest, CA

**Control Number:** *5003705* Authorized by:

Intertek

This document supersedes all previous Authorizations to Mark for the noted Report Number.

This Authorization to Mark is for the exclusive use of Intertek's Client and is provided pursuant to the Certification agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this Authorization to Mark. Only the Client is authorized to permit copying or distribution of this Authorization to Mark and then only in its entirety. Use of Intertek's Certification mark is restricted to the conditions laid out in the agreement and in this Authorization to Mark. Any further use of the Intertek name for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. Initial Factory Assessments and Follow up Services are for the purpose of assuring appropriate usage of the Certification mark in accordance with the agreement, they are not for the purposes of production quality control and do not relieve the Client of their obligations in this respect

> Intertek Testing Services NA Inc. 545 East Algonquin Road, Arlington Heights, IL 60005 Telephone 800-345-3851 or 847-439-5667 Fax 312-283-1672

Mounting Systems, Mounting Devices, Clamping/Retention Devices, and Ground Lugs for Use with Flat-Plate Photovoltaic Modules and Panels [UL 2703: 2015 Ed.1] Standard(s): Photovoltaic Module Racking Systems [CSA LTR AE-001:2012 Ed.2012/10/23] Photovoltaic Mounting System, Sun Frame Microrail Installation Guide, PUB2020MAY04 **Product:** Brand Name: Unirac Unirac SFM Models:

ATM Issued: 2-Jun-2020 ATM for Report 102393982LAX-002 Page 1 of 2 ED 16.3.15 (20-Apr-17) Mandatory

intertek

#### **AUTHORIZATION TO MARK**

This authorizes the application of the Certification Mark(s) shown below to the models described in the Product(s) Covered section when made in accordance with the conditions set forth in the Certification Agreement and Listing Report. This authorization also applies to multiple listee model(s) identified on the correlation page of the Listing Report.

This document is the property of Intertek Testing Services and is not transferable. The certification mark(s) may be applied only at the location of the Party Authorized To Apply Mark.

Applicant: Unirac, Inc Manufacturer:

1411 Broadway Blvd NE Address: Address: Albuquerque, NM 87102

USA Country: Country:

Klaus Nicolaedis Contact: Contact: **Todd Ganshaw** 

505-462-2190 Phone: Phone: 505-843-1418 FAX: NA FAX: klaus.nicolaedis@unirac.com

Email: Email: toddg@unirac.com

Party Authorized To Apply Mark: Same as Manufacturer **Report Issuing Office:** Lake Forest, CA

**Control Number:** *5003705* Authorized by:



## Intertek

This document supersedes all previous Authorizations to Mark for the noted Report Number.

This Authorization to Mark is for the exclusive use of Intertek's Client and is provided pursuant to the Certification agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this Authorization to Mark. Only the Client is authorized to permit copying or distribution of this Authorization to Mark and then only in its entirety. Use of Intertek's Certification mark is restricted to the conditions laid out in the agreement and in this Authorization to Mark. Any further use of the Intertek name for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. Initial Factory Assessments and Follow up Services are for the purpose of assuring appropriate usage of the Certification mark in accordance with the agreement, they are not for the purposes of production quality control and do not relieve the Client of their obligations in this respect.

> Intertek Testing Services NA Inc. 545 East Algonquin Road, Arlington Heights, IL 60005 Telephone 800-345-3851 or 847-439-5667 Fax 312-283-1672

Mounting Systems, Mounting Devices, Clamping/Retention Devices, and Ground Lugs for Use with Flat-Plate Photovoltaic Modules and Panels [UL 2703: 2015 Ed.1] Standard(s): Photovoltaic Module Racking Systems [CSA LTR AE-001:2012 Ed.2012/10/23] Photovoltaic Mounting System, Sun Frame Microrail Installation Guide, PUB2020MAY04 Product:

Brand Name: Unirac Models: Unirac SFM

ATM for Report 102393982LAX-002 Page 1 of 2 ATM Issued: 2-Jun-2020 ED 16.3.15 (20-Apr-17) Mandatory



1403 N RESEARCH WAY, BUILDING J OREM. UT 84097

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.



CONTRACTOR: **BRS FIELD OPS** 385.498.6700

SPEC SHEET

REVISION

0

PAGE NUMBER

SS





1403 N RESEARCH WAY, BUILDING J


800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.



Scott Gurney # PV-011719-015866

CONTRACTOR: BRS FIELD OPS 385.498.6700



## Trimrail™ and Module Clips

#### **Sub-Components:**

- 1. Trim Rail
- 2. Module Clip
- 3. T-Bolt
- 4. Tri-Drive Nut

### **Trimrail**<sup>™</sup>

#### **Functions:**

- Required front row structural support (with module clips)
- Module mounting
- Installation aid
- Aesthetic trim

#### **Features:**

- Mounts directly to L-feet
- Aligns and captures module leading edge
  - Supports discrete module thicknesses from 32, 33, 35, 38, and 40mm


## **Module Clips**

#### **Functions:**

- Required front row structural support (with trimrail)
- Module mounting

#### **Features:**

- Mounts to Trimrail<sup>™</sup> with T-bolt and tri-drive nut
- Manually adjustable to fit module thicknesses 32, 33, 35, 38, and 40mm.



### Trimrail<sup>™</sup> Flashkit

#### **Sub-Components:**

L-Foot

Hex bolt

Tri-drive nut

Channel Nut

Scocket Head Cap Screw

3"Channel/Slider w/grommet

3" Wide Flashing

Structural Screw & SS EPDM Washer

#### **Functions:**

- Attach Trimrail™ to roof attachment / flashing
- Patented roof sealing technology at roof attachment point

#### **Features:**

- Slot provides vertical adjustments to level array
- Slider provides north/south adjustment along the slope of the roof
- Shed and Seal Technology

## Trimrail<sup>™</sup> Splice

#### **Sub-Components:**

- 1. Structural Splice Extrusion
- 2. Bonding Clip

#### **Functions:**

- Front row structural support
- Installation aid
- Structurally connects 2 pieces of Trimrail™
- Electrically bonds 2 pieces of Trimrail<sup>™</sup>

#### Features:

- Aligns and connects Trimrail<sup>™</sup> pieces
- Tool-less installation

SHEET NAME

SPEC SHEET

PAGE NUMBER

5

REVISION



SFM Slider Flashkit

Structural Screw & SS EPDM washer

Patented Shed & Seal roof sealing technology at roof attach-

For use with compatible 2" Microrail or 8" Attached Splices

**Sub-Components:** 

1. Slider w/grommet

**Functions:** 

3" Wide Flashing

slope of the roof

Shed and Seal Technology




1403 N RESEARCH WAY, BUILDING J

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.



**CONTRACTOR: BRS FIELD OPS** 385.498.6700




## Module-to-Module N-S Bonding

#### **Sub-Components:**

- 1. Clamp
- Bonding Pins (2)
- 5/16" Socket Head Cap Screw
- 4. Clamp Base

#### **Functions/ Features:**

- Row to row bonding
- Single Use Only
- Fits module sizes 32-40mm




## Trim -to- Module Bonding Clamp and Floating Trim Clamp

#### **Sub-Components:**

- 1. Wedge
- Bonding Pin
- 3. T-Bolt
- 4. Nut
- Cast Base

### **Functions/ Features:**

- Module to Trimrail™ bonding single use only
- Attaches Trimrail™ to module when fewer than 2 rafter attachment points are available
- Fits module sizes 32-40mm




## Wire Bonding Clip w/ 8AWG

#### **Functions:**

- Row to row bonding
- Module to Trimrail™ bonding
- Single Use Only

#### **Features:**

Tool-less installation



## **MLPE Mounting Assembly**

#### **Sub-Components:**

- 1. MLPE Mount Base
- 2. 5/16 Socket Head Cap Screw
- 3. Bonding Pin

#### **Functions:**

- Securely mounts MLPE to module frames
- MLPE to module bonding

#### **Features:**

- Mounts easily to typical module flange
- UL2703 Recognized

MLPE = Module Level Power Electronics, e.g. microinverter or power optimizer

- **Features:** Slider provides north/south adjustment along the

  - Fits module sizes 32-40mm

SPEC SHEET

AGE NUMBER SS





# 3" FLASHING & SLIDERS | GINSTALLATION GUIDE | PAGE








1403 N RESEARCH WAY, BUILDING J

800-377-4480 WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.



**CONTRACTOR: BRS FIELD OPS** 385.498.6700





**FLASHINGS:** 

Place flashings

#### **PILOT HOLES:**

Drill pilot holes for lag screws or structural screws (as necessary) at marked attachement points






#### **INSTALL SLIDERS AND TRIMRAIL ROOF ATTACHMENTS:**

Insert flashings per manufacturer instructions

NOTE: Use Lag screw or structural fastener with a maximum diameter of 5/16"

- Attach sliders to rafters
- Verify proper row to row spacing for module size (Mod NS + 1")
- Ensure that TrimrailTM roof attachments in each row have sufficient engagement with slider dovetails for proper attachment.



SPEC SHEET

AGE NUMBER SS