



ELECTRICAL RESIDENTIAL

910-893-7525

www.harnett.org

PERMIT NUMBER

ERES2208-0077

JOB ADDRESS: 81 FARROW CT	PERMIT SUBTYPE: RESIDENTIAL SOLAR PANELS	PARCEL NO: 0544-47-7415.000
DESCRIPTION: roof mounted solar panels	DATE ISSUED: 9/8/2022	DATE EXPIRED:
PLAN NAME:	ZONING DISTRICT: RA-20R - 0.61 acres (100.0%)	

APPLICANT: Sigora Solar 1222 Harris Street Charlottesville, VA 22903	PHONE: (434)465-6788 EMAIL: permitting@sigorasolar.com
CONTRACTOR: Sigora Solar 1222 Harris Street Charlottesville, VA 22903	PHONE: (434)465-6788 EMAIL: permitting@sigorasolar.com
OWNER: HERNANDEZ MATTHEW 81 FARROW CT LINDEN, NC 28356 LINDEN, NC 28356	PHONE: EMAIL:

REQUIRED INSPECTIONS

INSPECTION TYPE	APPROVAL	DATE	COMMENTS
FINAL**			
ROUGH IN			



Scott E. Wyssling, PE
Coleman D. Larsen, SE, PE
Gregory T. Elvestad, PE

76 North Meadowbrook Drive
Alpine, UT 84004
office (201) 874-3483
swyssling@wysslingconsulting.com

September 19, 2022

Sigora Solar LLC
490 Westfield Road STE A
Charlottesville, VA 22901

Re: Engineering Services (Post-Install)
Hernandez Residence
26 Newport Drive, Rolesville NC
8.800 kW System

To Whom It May Concern:

I certify that Jairo A. Rios has surveyed the rafters/trusses at 26 Newport Drive, Rolesville NC. There are no broken rafters or trusses, and appear to be in good condition. As you are aware, this office initially prepared a structural assessment, dated August 14, 2022, of the solar panel installation. This installation was inspected and found to be in compliance with the layout plan as specified in our report, product installation criteria, and the requirements of the current building code. We have determined that the equipment will not create a negative impact on the building's structural design, including any additional loads imposed (dead, snow, wind).

This letter pertains only to the panel support attachments to the roof framing and not the engineered photovoltaic panel products, components, or electrical-related installations/connections.

Should you have any questions regarding the above or if you require additional information do not hesitate to contact me.

Very truly yours,

Scott E. Wyssling, PE
North Carolina License No. 46546

THIS PLAN HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY SCOTT WYSSLING, PE USING A DIGITAL SIGNATURE AND DATE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES



Wyssling Consulting, PLLC

76 N Meadowbrook Drive
Alpine UT 84004 COA # P-2308

Date Signed 9/19/2022



Scott E. Wyssling, PE
Jon P. Ward, SE, PE
Gregory T. Elvestad, PE

76 North Meadowbrook Drive
Alpine, UT 84004
office (201) 874-3483
swyssling@wysslingconsulting.com

August 14, 2022

Sigora Solar LLC
490 Westfield Road STE A
Charlottesville, VA 22901

SCOTT E
WYSSLING, PE

Digitally signed by SCOTT E WYSSLING, PE
DN: C=US, S=Utah, L=Alpine, O=Wyssling Consulting, OU=Owner,
CN="SCOTT E WYSSLING, PE",
E=swyssling@wysslingconsulting.com
Reason: I am the author of this document
Location: your signing location here
Date: 2022-08-14 06:08:52
Foxit PhantomPDF Version: 9,7,5

Re: Engineering Services
Hernandez Residence
26 Newport Drive, Rolesville NC
8.800 kW System

To Whom It May Concern:

We have received information regarding solar panel installation on the roof of the above referenced structure. Our evaluation of the structure is to verify the existing capacity of the roof system and its ability to support the additional loads imposed by the proposed solar system.

A. Site Assessment Information

1. Site visit documentation identifying attic information including size and spacing of framing for the existing roof structure.
2. Design drawings of the proposed system including a site plan, roof plan and connection details for the solar panels. This information will be utilized for approval and construction of the proposed system.

B. Description of Structure:

Roof Framing: Prefabricated wood trusses at 24" on center. All truss members are constructed of 2x4 dimensional lumber.
Roof Material: Composite Asphalt Shingles
Roof Slope: 18 & 27 degrees
Attic Access: Accessible
Foundation: Permanent

C. Loading Criteria Used

- **Dead Load**
 - Existing Roofing and framing = 7 psf
 - New Solar Panels and Racking = 3 psf
 - TOTAL = 10 PSF
- **Live Load** = 20 psf (reducible) – 0 psf at locations of solar panels
- **Ground Snow Load** = 15 psf
- **Wind Load** based on ASCE 7-10
 - Ultimate Wind Speed = 115 mph (based on Risk Category II)
 - Exposure Category C

Analysis performed of the existing roof structure utilizing the above loading criteria is in accordance with the North Carolina Residential Code (2018), including provisions allowing existing structures to not require strengthening if the new loads do not exceed existing design loads by 105% for gravity elements and 110% for seismic elements. This analysis indicates that the existing framing will support the additional panel loading without damage, if installed correctly.


D. Solar Panel Anchorage

1. The solar panels shall be mounted in accordance with the most recent Unirac installation manual. If during solar panel installation, the roof framing members appear unstable or deflect non-uniformly, our office should be notified before proceeding with the installation.
2. The maximum allowable withdrawal force for a $\frac{5}{16}$ " lag screw is 235 lbs per inch of penetration as identified in the National Design Standards (NDS) of timber construction specifications. Based on a minimum penetration depth of $2\frac{1}{2}$ ", the allowable capacity per connection is greater than the design withdrawal force (demand). Considering the variable factors for the existing roof framing and installation tolerances, the connection using one $\frac{5}{16}$ " diameter lag screw with a minimum of $2\frac{1}{2}$ " embedment will be adequate and will include a sufficient factor of safety.
3. Considering the wind speed, roof slopes, size and spacing of framing members, and condition of the roof, the panel supports shall be placed no greater than 48" on centers.
4. Panel supports connections shall be staggered to distribute load to adjacent framing members.

Based on the above evaluation, this office certifies that with the racking and mounting specified, the existing roof system will adequately support the additional loading imposed by the solar system. This evaluation is in conformance with the North Carolina Residential Code, current industry standards, and is based on information supplied to us at the time of this report.

Should you have any questions regarding the above or if you require further information do not hesitate to contact me.

Very truly yours,



Scott E. Wyssling, PE
North Carolina License No. 46546

THIS PLAN HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY SCOTT WYSSLING, PE USING A DIGITAL SIGNATURE AND DATE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES



Wyssling Consulting, PLLC
76 N Meadowbrook Drive
Alpine UT 84004 COA # P-2308

PROJECT DESCRIPTION:

(E) 10 x LG SOLAR: LG 375W MONO MODULES
 (N) 22 x REC SOLAR: REC400AA PURE 400W MONO MODULES
 ROOF MOUNTED SOLAR PHOTOVOLTAIC MODULES
 DC SYSTEM SIZE: (E) 3,750KW DC + (N) 8,800KW DC = 12,550KW DC
 AC SYSTEM SIZE: (E) 2,300KW AC + (N) 6,380KW AC = 9,280KW AC

EQUIPMENT SUMMARY:

(E) 10 LG SOLAR: LG 375W MONO MODULES
 (E) 10 ENPHASE IQ7PLUS-72-2-US 290W MICRO INVERTERS
 EQUIPPED WITH RAPID SHUTDOWN
 (N) 22 REC SOLAR: REC400AA PURE 400W MONO MODULES
 (N) 22 ENPHASE IQ8PLUS-72-2-US 290W MICRO INVERTERS
 EQUIPPED WITH RAPID SHUTDOWN

ROOF ARRAY AREA #1: 238.92 SQ FT.
 ROOF ARRAY AREA #2: 199.10 SQ FT.
 (10) REC SOLAR: REC400AA PURE
 400W MONO MODULES WITH ENPHASE
 IQ8PLUS-72-2-US 290W MICRO INVERTERS
 EQUIPPED WITH RAPID SHUTDOWN

AUTHORITIES HAVING JURISDICTION:
 BUILDING: HARNETT, COUNTY OF (NC)
 ZONING: HARNETT, COUNTY OF (NC)

SCOPE OF WORK:
 DESIGNED FOR INSTALLATION OF GRID-TIED
 PHOTOVOLTAIC SOLAR SYSTEM

APPLICABLE CODES & STANDARDS
 NCBC 2018
 NEC 2017

DESIGN SPECIFICATION

OCCUPANCY: II
 CONSTRUCTION: SINGLE-FAMILY
 ZONING: RESIDENTIAL
 WIND EXPOSURE: REFER STRUCTURAL LETTER
 WIND SPEED: REFER STRUCTURAL LETTER

SCOTT E WYSSLING, PE

Details prepared by SCOTT E. WYSSLING, PE
 ONE COLLETT STREET, LINDEN, NC 28356
 Phone: 704.283.5656
 Email: scott@wysslingpe.com
 Reason: I am the author of this document.
 Location: your signing location here
 Date: 8/14/2022
 File: Plan01001P01_Version_3.7.5

ROOF #2
 (10) REC SOLAR: REC400AA PURE
 400W MONO MODULES WITH ENPHASE
 IQ8PLUS-72-2-US 290W MICRO INVERTERS
 EQUIPPED WITH RAPID SHUTDOWN

(E) POOL

(E) DETACHED
 STRUCTURE

(E) FENCE

(E) MAIN SERVICE PANEL
 (INSIDE GARAGE)


(E) GATE (TYP.)

THIS PLAN HAS BEEN ELECTRONICALLY SIGNED AND
 SEALED BY SCOTT WYSSLING, PE USING A DIGITAL
 SIGNATURE AND DATE. PRINTED COPIES OF THIS
 DOCUMENT ARE NOT CONSIDERED SIGNED AND
 DATED UNLESS THE SIGNATURE AND DATE ARE
 VERIFIED ON ANY ELECTRONIC COPIES.


Wysling Consulting, PLLC
 76 N Headwatersh Drive Alpine UT 84004
 North Carolina CBA # F-2288
 Signed 8/14/2022

(E) (10) LG SOLAR: LG 375W MONO
 MODULES WITH ENPHASE
 IQ7PLUS-72-2-US 290W MICRO INVERTERS
 EQUIPPED WITH RAPID SHUTDOWN

ROOF #1
 (12) REC SOLAR: REC400AA PURE
 400W MONO MODULES WITH ENPHASE
 IQ8PLUS-72-2-US 290W MICRO INVERTERS
 EQUIPPED WITH RAPID SHUTDOWN



2 HOUSE PHOTO
 PV-1 SCALE: NTS



3 VICINITY MAP
 PV-1 SCALE: NTS

SHEET INDEX	DESCRIPTION
PV-1	PLOT PLAN WITH ROOF PLAN
PV-2	ROOF PLAN & MODULES
PV-2A	CIRCUIT LAYOUT
PV-3	ATTACHMENT DETAIL
PV-4	ELECTRICAL LINE DIAGRAM
PV-5	LABELS
PV-6	PLACARD
PV-7	MICRO INVERTER CHART
PV-8	MODULE SPECIFICATIONS
PV-9	INVERTER SPECIFICATIONS
PV-10	COMBINER SPECIFICATIONS
PV-11	RAIL SPECIFICATIONS
PV-12	ATTACHMENT SPECIFICATIONS
PV-13	SOLADECK SPECIFICATIONS

SIGORA SOLAR LLC
 499 WESTFIELD RD STE A
 CHARLOTTEVILLE, VA 22901

REVISIONS	DESCRIPTION	DATE	REV
	INITIAL	08/12/2022	


DATE: 08/12/2022
 PROJECT NAME & ADDRESS
 81 FARROW CT,
 LINDEN, NC 28356

CHERRIE HERNANDEZ
 RESIDENCE
 DRAWN BY
 ESR
 SHEET NAME
 PLOT PLAN WITH
 ROOF PLAN
 SHEET SIZE
 ANSI B
 11" X 17"
 SHEET NUMBER
 PV-1

MODULE TYPE, DIMENSIONS & WEIGHT

NUMBER OF MODULES = 22 MODULES
 MODULE TYPE = REC SOLAR: REC400AA PURE 400W MONO MODULES
 MODULE WEIGHT = 45.19 LBS / 20.5KG
 MODULE DIMENSIONS = 71.70" x 40.00" = 19.91 SF

- TOTAL WEIGHT OF PV MODULES AND RAILS = 1314.1 LBS
- WEIGHT PER ATTACHMENT POINT = 26 LBS
- DISTRIBUTED WEIGHT OF PV MODULE = 2.27 LBS/SF



SCOTT E. WYSSLING, PE
 PROFESSIONAL ENGINEER
 041546
 NORTH CAROLINA



Digitally signed by SCOTT E WYSSLING, PE
 DN: cn=Scott E. Wyssling, o=Scott E. Wyssling, PE
 Reason: I have performed the digital signature operation
 on this document. Your signature location here.

THIS PLAN HAS BEEN ELECTRONICALLY SIGNED AND
 SEALED BY SCOTT WYSSLING, PE USING A DIGITAL
 DOCUMENT ARE NOT CONSIDERED SIGNED AND
 SEALED AND THE SIGNATURE MUST BE VERIFIED
 ON ANY ELECTRONIC COPIES

ROOF #2
 (10) REC SOLAR: REC400AA PURE
 400W MONO MODULES WITH ENPHASE
 IQ8PLUS-72-2-US 290W MICRO INVERTERS
 EQUIPPED WITH RAPID SHUTDOWN

(E) (10) LG SOLAR: LG 375W MONO
 MODULES WITH ENPHASE
 IQ7PLUS-72-2-US MICRO INVERTERS
 (E) (10) ENPHASE IQ7PLUS-72-2-US
 290W MICRO INVERTERS
 EQUIPPED WITH RAPID SHUTDOWN


ROOF #1
 (12) REC SOLAR: REC400AA PURE
 400W MONO MODULES WITH ENPHASE
 IQ8PLUS-72-2-US 290W MICRO INVERTERS
 EQUIPPED WITH RAPID SHUTDOWN

ARRAY AREA & ROOF AREA CALC'S

TOTAL PLAN VIEW PV ARRAY AREA (SQ. FT.)	402.28	TOTAL PLAN VIEW ROOF AREA (SQ. FT.)	2068.51
ROOF AREA COVERED BY ARRAY (%)	19		

ROOF DESCRIPTION

ROOF TYPE	ASPHALT SHINGLE								
ROOF LAYER	1 LAYER								
ROOF #1	#1	ROOF PITCH	27°	ROOF AZIMUTH	140°	TRUSS SIZE	2X4	TRUSS SPACING	24"
ROOF #2	#2	ROOF PITCH	18°	ROOF AZIMUTH	140°	TRUSS SIZE	2X4	TRUSS SPACING	24"



REVISIONS

DESCRIPTION	DATE	REV
INITIAL	06/12/2022	


DATE: 06/12/2022
 PROJECT NAME & ADDRESS
 81 FARROW CT,
 LINDEN, NC 28356

CHERIE HERNANDEZ
 RESIDENCE
 DRAWN BY: ESR

SHEET NAME
ROOF PLAN & MODULES

SHEET SIZE
**ANSI B
 11" X 17"**

SHEET NUMBER
PV-2



1 ROOF PLAN & MODULES
 SCALE: 1/8" = 1'-0"

BILL OF MATERIALS	
EQUIPMENT	DESCRIPTION
QTY	DESCRIPTION
22	REC SOLAR: REC400AA PURE
22	ENPHASE IQ8PLUS-72-2JIS 200W MICRO INVERTERS EQUIPPED WITH RAPID SHUTDOWN
2	SOLADECKS OR JUNCTION BOXES
32	MID MODULE CLAMPS
24	END CLAMPS / STOPPER SLEEVE
51	UNIFRAC STRONGHOLD ATTACHMENT
51	LAG BOLT

CIRCUIT LEGENDS	
	(E) CIRCUIT #1
	(N) CIRCUIT #2
	(N) CIRCUIT #3



SIGORA SOLAR LLC
490 WESTFIELD RD STE A
CHARLOTTEVILLE, VA 22901

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	08/12/2022	

DATE: 08/12/2022

PROJECT NAME & ADDRESS
CHERIE HERNANDEZ RESIDENCE
 81 FARROW CT,
 LINDEN, NC 28356

DRAWN BY
ESR

SHEET NAME
CIRCUIT LAYOUT

SHEET SIZE
**ANSI B
 11" X 17"**

SHEET NUMBER
PV-2A

REVISIONS	DESCRIPTION	DATE	REV
INITIAL		08/12/2022	

PROJECT NAME & ADDRESS

CHERIE HERNANDEZ
RESIDENCE
81 FARROW CT,
LINDEN, NC 28356

DRAWN BY

ESR

SHEET NAME


ATTACHMENT
DETAIL

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

PV-3



**SCOTT E
WYSSLING, PE**

Digitally signed by SCOTT E WYSSLING, PE
DN: cn=US, s=John, L=Alpine, o=Wyssling Consulting,
ou=Wyssling Consulting, email=E.wyssling@wysslingconsulting.com,
c=US
Reason: I am the author of this document
Date: 2022.08.14 08:09:29
Front-PhantomPDF Version: 9.7.5


Wyssling Consulting, PLLC
76 N Meadowbrook Drive Alpine UT 84004
North Carolina COA # P-2208
Signed 8/14/2022

THIS PLAN HAS BEEN ELECTRONICALLY SIGNED AND
SEALED BY SCOTT WYSSLING, PE USING A DIGITAL
SIGNATURE. ANY ALTERATIONS TO THIS
DOCUMENT ARE NOT CONSIDERED SIGNED AND
SEALED AND THE SIGNATURE MUST BE VERIFIED
ON ANY ELECTRONIC COPIES

1 STRUCTURAL ATTACHMENT (SIDE VIEW)

PV-3

SCALE: N.T.S



2 ATTACHMENT DETAIL (enlarged view)

PV-3

SCALE: N.T.S

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	08/12/2022	

DATE: 08/12/2022
 PROJECT NAME & ADDRESS
 81 FARROW CT,
 LINDEN, NC 28356

CHERIE HERNANDEZ
 RESIDENCE
 DRAWN BY
 ESR
 SHEET NAME
 LABELS
 SHEET SIZE
 ANSIB
 11" X 17"
 SHEET NUMBER
 PV-5

LABEL 6

WARNING
 INVERTER OUTPUT CONNECTION
 DO NOT RELOCATE
 THIS OVERCURRENT
 DEVICE

PLACED ADJACENT TO THE BACK-FED BREAKER FROM THE INVERTER IF TIE IN CONSISTS OF LOAD SIDE CONNECTION TO BUSBAR.
 NEC 705.12(D)(2)(3)(B)

LABEL 7

WARNING
 DUAL POWER SOURCE
 SECOND SOURCE IS PHOTOVOLTAC SYSTEM

SIGN LOCATED AT LOAD CENTER
 NEC 705.12(B)(3-4) & NEC 690.59

LABEL 1

**WARNING: PHOTOVOLTAC
 POWER SOURCE**

AT DIRECT-CURRENT EXPOSED RACEWAYS, CABLE TRAYS, COVERS AND ENCLOSURES OF JUNCTION BOXES, AND OTHER WIRING METHODS; SPACED AT MAXIMUM 10FT SECTION OR WHERE SEPARATED BY ENCLOSURES, WALLS, PARTITIONS, CEILINGS, OR FLOORS.
 NEC 690.31(C)(3&4)
 (NOT USED FOR ENPHASE MICROINVERTERS)

LABEL 2

PHOTOVOLTAC
DC DISCONNECT

AT EACH PV DISCONNECTING MEANS
 NEC 690.13(B)
 (NOT USED FOR ENPHASE MICROINVERTERS)

LABEL 3

MAXIMUM VOLTAGE
 MAXIMUM CIRCUIT CURRENT
 MAX RATED OUTPUT CURRENT OF
 THE CHARGE CONTROLLER
 OR DC-TO-DC CONVERTER
 (IF INSTALLED)

AT DC PV SYSTEM DISCONNECT
 NEC 690.53
 (NOT USED FOR ENPHASE MICROINVERTERS)

LABEL 4

PHOTOVOLTAC
AC DISCONNECT

AT AC DISCONNECT
 NEC 690.13(B)

LABEL 5

PHOTOVOLTAC AC DISCONNECT
 RATED AC OUTPUT CURRENT
 NOMINAL OPERATING AC VOLTAGE

AT AC DISCONNECT
 NEC 690.54

22 MICROS X 1.21 AMP/MICRO = 26.62AMP

LABEL 8

**SOLAR PV SYSTEM EQUIPPED
 WITH RAPID SHUTDOWN**
 TURN RAPID SHUTDOWN
 SWITCH TO THE
 SHUTDOWN POSITION
 AND REDUCE
 SHOCK HAZARD
 IN THE ARRAY


FOR PV SYSTEMS THAT SHUT DOWN THE ARRAY AND CONDUCTORS LEAVING THE ARRAY. THE SIGN TO BE LOCATED ON OR NO MORE THAN 3 FT AWAY FROM SERVICE DISCONNECTING MEANS TO WHICH THE PV SYSTEMS ARE CONNECTED AND SHALL INDICATE THE LOCATION OF ALL IDENTIFIED RAPID SHUTDOWN SWITCHES IF NOT AT THE SAME LOCATION.
 [NEC 690.56(C)(1)(A)]

LABEL 9

**RAPID SHUTDOWN
 SWITCH FOR
 SOLAR PV SYSTEM**

AT AC DISCONNECT
 NEC 690.56(C)(3)

LABELING DIAGRAM:



** ELECTRICAL DIAGRAM SHOWN ABOVE IS FOR LABELING PURPOSES ONLY. NOT AN ACTUAL REPRESENTATION OF EQUIPMENT AND CONNECTIONS TO BE INSTALLED. LABEL LOCATIONS PRESENTED MAY VARY DEPENDING ON TYPE OF INTERCONNECTION METHOD AND LOCATION. PRESENTED ELECTRICAL DIAGRAM PAGE.

LABELING NOTES:

1. LABELS CALLED OUT ACCORDING TO ALL COMMON CONFIGURATIONS. ELECTRICIAN TO DETERMINE EXACT REQUIREMENTS IN THE FIELD PER CURRENT NEC AND LOCAL CODES AND MAKE APPROPRIATE ADJUSTMENTS.
2. LABELING REQUIREMENTS BASED ON THE 2017 NATIONAL ELECTRIC CODE, OSHA STANDARD 19010.145, ANSI Z535.
3. MATERIAL BASED ON THE REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION.
4. LABELS TO BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT INVOLVED [NEC 110.21]
5. LABELS TO BE A MINIMUM LETTER HEIGHT OF 3/8", WHITE ON RED BACKGROUND, REFLECTIVE, AND PERMANENTLY AFFIXED [IFC 605.11.1-1]

REVISIONS	DESCRIPTION	DATE	REV
	INITIAL	08/12/2022	

DATE: 08/12/2022

PROJECT NAME & ADDRESS

CHERIE HERNANDEZ
RESIDENCE
81 FARROW CT,
LINDEN, NC 28356

DRAWN BY
ESR



SHEET NAME
PLACARD

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-6

CAUTION

POWER TO THIS BUILDING IS ALSO SUPPLIED FROM MULTIPLE SOURCES OF POWER WITH SAFETY DISCONNECTS AS SHOWN:




81 FARROW CT, LINDEN, NC 28356

DIRECTORY
PERMANENT PLAQUE OR DIRECTORY PROVIDING THE LOCATION OF THE SERVICE DISCONNECTING MEANS AND THE PHOTOVOLTAIC SYSTEM.

(ALL PLAQUES AND SIGNAGE WILL BE INSTALLED AS OUTLINED WITHIN: NEC 690.56(B)&(C), [NEC 705.10])

LABELING DIAGRAM:



LABELING NOTES:

1. LABELS CALLED OUT ACCORDING TO ALL COMMON CONFIGURATIONS. ELECTRICIAN TO DETERMINE EXACT REQUIREMENTS IN THE FIELD PER CURRENT NEC AND LOCAL CODES AND MAKE APPROPRIATE ADJUSTMENTS.
2. LABELING REQUIREMENTS BASED ON THE 2017 NATIONAL ELECTRIC CODE, OSHA STANDARD 19010.145, ANSI Z535.
3. MATERIAL BASED ON THE REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION.
4. LABELS TO BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT INVOLVED [NEC 110.2.1]
5. LABELS TO BE A MINIMUM LETTER HEIGHT OF 3/8". WHITE ON RED BACKGROUND; REFLECTIVE, AND PERMANENTLY AFFIXED [IFC 605.11.1.1]

** ELECTRICAL DIAGRAM SHOWN ABOVE IS FOR LABELING PURPOSES ONLY. NOT AN ACTUAL REPRESENTATION OF EQUIPMENT AND CONNECTIONS TO BE INSTALLED. LABEL LOCATIONS PRESENTED MAY VARY DEPENDING ON TYPE OF INTERCONNECTION METHOD AND LOCATION PRESENTED ELECTRICAL DIAGRAM PAGE. **



SIGORA SOLAR LLC
490 WESTFIELD RD STE A
CHARLOTTESVILLE, VA 22901

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	08/12/2022	

DATE: 08/12/2022

PROJECT NAME & ADDRESS

CHERIE HERNANDEZ
RESIDENCE
81 FARROW CT,
LINDEN, NC 28356

DRAWN BY

ESR

SHEET NAME

MICRO INVERTER
CHART


SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

PV-7

MICRO INVERTER CHART



1-10	11-20	21-30	31-40	41-50	51-60	61-70
1	2	3	4	5	6	7
8	9	10				

SOLAR'S MOST TRUSTED



REC ALPHOX[®] PURE SERIES PRODUCT SPECIFICATIONS

COMPACT PANEL SIZE

EXPERIENCE  PERFORMANCE

LEAD-FREE ROHS COMPLIANT

 ELIGIBLE


410 WP
222 W/m²

REC ALPHA PURE SERIES PRODUCT SPECIFICATIONS



GENERAL DATA

- Cell type: 132 half-cut REC heterojunction cells with lead-free, cell-less technology. 6 strings of 22 cells in series
- Glass: 3.2 mm solar glass with anti-reflective surface treatment in accordance with EN 1260
- Backsheet: Highly resistant polymer (black)
- Frame: Anodized aluminum (black)
- Junction box: 3-part, 3-bypass diodes, lead-free. Prepared in accordance with IEC 62730
- Connectors: Stable MC4 PV-KB14/KS14 (4 mm) in accordance with IEC 62853. IP68 rated when fully sealed
- Cable: 4 mm² solar cable, 11 mm² PV1-22m in accordance with IEC 62853
- Dimensions: 1821 x 1016 x 30 mm (L x B x H)
- Weight: 20.5 kg
- Origin: Made in Singapore



ELECTRICAL DATA

Product Code: RECxxAA Pure	
Power Output - P _{max} (Wp)	385 390 395 400 405 410
Watt Class Sorting (W)	0/+5 0/+5 0/+5 0/+5 0/+5
Nominal Power Voltage - V _{mp} (V)	41.2 41.5 41.8 42.1 42.4 42.7
Nominal Power Current - I _{mp} (A)	9.35 9.40 9.45 9.51 9.56 9.61
Open Circuit Voltage - V _{oc} (V)	48.5 48.6 48.7 48.8 48.9 49.0
Short Circuit Current - I _{sc} (A)	10.18 10.19 10.20 10.25 10.30 10.35
Power Density (W/m ²)	208 211 214 216 219 222
Panel Efficiency (%)	20.8 21.1 21.4 21.6 21.9 22.2

MAXIMUM RATINGS

Operational temperature:	-40...+85°C
Maximum system voltage:	1000V
Maximum test load (front):	+7000 Pa (73kg/m ²)
Maximum test load (rear):	-4000 Pa (407kg/m ²)
Max sel (ie. fuse rating):	25A
Max reverse current:	25A

WARRANTY

Installed by an REC Certified Solar Professional	Standard	REC ProTrust
System Size	All	≤25 kW, 25-500 kW
Product Warranty (yrs)	20	25, 25
Labor Warranty (yrs)	0	25, 10
Power in Year 1	98%	98%, 98%
Annual Degradation	0.25%	0.25%, 0.25%
Power in Year 25	92%	92%, 92%

TEMPERATURE RATINGS

Nominal Module Operating Temperature:	44°C (±2°C)
Temperature coefficient of P _{max} :	-0.26 %/°C
Temperature coefficient of V _{oc} :	-0.24 %/°C
Temperature coefficient of I _{sc} :	0.04 %/°C

DELIVERY INFORMATION

Panels per pallet:	33
Panels per 40' HC (high cube container):	732 (24 pallets)
Panels per 13.6 m truck:	924 (28 pallets)
Panels per 53' FT truck:	891 (27 pallets)

LOW LIGHT BEHAVIOUR



CERTIFICATIONS

- IEC 61215:2016, IEC 61730:2016, UL 61730
- IEC 62804 PID
- IEC 61701 Salt Mist
- IEC 62716 Ammonia Resistance
- ISO 1925-2 Ignitability (Class E)
- IEC 62782 Dynamic Mechanical Load
- IEC 61215-2:2016 Halotest (35mm)
- IEC 62321 Lead-free test to RoHS EU 865/2015
- ISO 14001, ISO 9001, IEC 45001, IEC 62941

TEMPERATURE RATINGS

Nominal Module Operating Temperature:	44°C (±2°C)
Temperature coefficient of P _{max} :	-0.26 %/°C
Temperature coefficient of V _{oc} :	-0.24 %/°C
Temperature coefficient of I _{sc} :	0.04 %/°C

DELIVERY INFORMATION

Panels per pallet:	33
Panels per 40' HC (high cube container):	732 (24 pallets)
Panels per 13.6 m truck:	924 (28 pallets)
Panels per 53' FT truck:	891 (27 pallets)

LOW LIGHT BEHAVIOUR



SIGORA SOLAR

SIGORA SOLAR LLC
499 WESTFIELD RD STE A
CHARLOTTEVILLE, VA 22901

DESCRIPTION	DATE	REV
INITIAL	08/12/2022	

PROJECT NAME & ADDRESS
CHERIE HERNANDEZ
RESIDENCE
81 FARROW CT,
LINDEN, NC 28356

DATE: 08/12/2022

DRAWN BY:
ESR

SHEET NAME:
MODULE SPECIFICATION

SHEET SIZE:
ANSI B
11" X 17"

SHEET NUMBER:
PV-8

Ref: PM-25-12-05-Rev. E 11.21
Specifications subject to change without notice.

www.rec-solar.com



Founded in 1996, REC Group is an international pioneering solar energy company dedicated to empowering consumers with clean, affordable solar power. As Solar's Most Trusted, REC is committed to high quality, innovation, and a low carbon footprint in the solar materials and solar panels it manufactures. Headquartered in Norway with operational headquarters in Singapore, REC also has regional hubs in North America, Europe, and Asia-Pacific.



DATA SHEET



IQ8 and IQ8+ Microinverters

Our newest IQ8 Microinverters are the industry's first microgrid-forming, software-defined microinverters with split-phase power conversion capability to convert DC power to AC power efficiently. The brain of the semiconductor-based microinverter is our proprietary application-specific integrated circuit (ASIC) which enables the microinverter to operate in grid-tied or off-grid modes. This chip is built in advanced 55nm technology with high speed digital logic and has super-fast response times to changing loads and grid events, alleviating constraints on battery sizing for home energy systems.



Part of the Enphase Energy System, IQ8 Series Microinverters integrate with the Enphase IQ Battery, Enphase IQ Gateway, and the Enphase App monitoring and analysis software.



IQ8 Series Microinverters redefine reliability standards with more than one million cumulative hours of power-on testing, enabling an industry-leading limited warranty of up to 25 years.



IQ8 Series Microinverters are UL Listed as Microinverters, Type II, Class II, with various regulations, when installed according to manufacturer's instructions.



Connect PV modules quickly and easily to IQ8 Series Microinverters with the Enphase IQ Battery, IQ Gateway, and IQ8 Series plug-n-play MC4 connectors.

Easy to install

- Lightweight and compact with plug-n-play connectors
- Power Line Communication (PLC) between components
- Faster installation with simple two-wire cabling

High productivity and reliability

- Produce power even when the grid is down*
- More than one million cumulative hours of testing
- Class I double-insulated enclosure
- Optimised for the latest high-powered PV modules

Microgrid-forming

- Complies with the latest advanced grid support**
- Remote automatic updates for the latest grid requirements
- Configurable to support a wide range of grid profiles
- Meets CA Rule 21 (UL 1741-SA) requirements

* Only when installed with IQ System Controller 2.
** IQ8 and IQ8PLUS supports split phase, 240V installations only.

IQ8 and IQ8+ Microinverters

INPUT DATA (ID1)	IQ8-40-2-US	IQ8PLUS-72-2-US
Commonly used module pairings ¹	235 - 330	235 - 440
Module compatibility	60-cell/720 half-cell	60-cell/720 half-cell, 66-cell/132 half-cell and 72-cell/144 half-cell
MPPF voltage range	27 - 37	29 - 45
Operating range	25 - 48	25 - 58
Min/max start voltage	30 / 48	30 / 58
Max input DC voltage	50	60
Max DC current ² (module Isc)	15	15
Overvoltage class DC port	II	II
DC port backfeed current	0	0
PV array configuration	1x1 Ungrounded array; No additional DC side protection required; AC side protection requires max. 20A per branch circuit.	

OUTPUT DATA (ID2)	IQ8-40-2-US	IQ8PLUS-72-2-US
Peak output power	245	300
Max continuous output power	240	290
Nominal (L-L) voltage/range ³	10	240 / 211 - 264
Max continuous output current	1.0	1.21
Nominal frequency	60	60
Extended frequency range	50 - 68	50 - 68
AC short circuit fault current over 3 cycles	2	2
Max units per 20 A (L-L) branch circuit ⁴	16	13
Total harmonic distortion	<5%	<5%
Overvoltage class AC port	III	III
AC port backfeed current	30	30
Power factor setting	1.0	1.0
Grid-tie power factor (adjustable)	0.85 leading - 0.85 lagging	0.85 leading - 0.85 lagging
Peak efficiency	97.5	97.6
CEC weighted efficiency	97	97
Night-time power consumption	60	60

MECHANICAL DATA	IQ8-40-2-US	IQ8PLUS-72-2-US
Ambient temperature range	-40°C to +60°C (-40°F to +140°F)	
Relative humidity range	4% to 100% (condensing)	
DC Connector type	MC4	
Dimensions (HxWxD)	212 mm (8.3") x 175 mm (6.9") x 302 mm (12")	
Weight	1.08 kg (2.38 lbs)	
Cooling	Natural convection - no fans	
Approved for wet locations	Yes	
Pollution degree	PDS	
Enclosure	Class II double-insulated, corrosion resistant polymer enclosure	
Environment, category / UV exposure rating	NEMA Type 6 / outdoor	

CERTIFICATIONS	IQ8-40-2-US	IQ8PLUS-72-2-US
Certifications	CA Rule 21 (UL 1741-SAA, UL 62109-1, UL 1741/IEEE1547, FCC Part 15 Class B, CEES-0003 Class B, CAN/CSA-C22.2 NO. 1071-01 65012, and C22.2-2018 Rule 64-218 Rapid Shutdown of PV Systems, for AC and DC conductors, when installed according to manufacturer's instructions.	

(1) No enforced DC/AC ratio. See the compatibility calculator at <https://enphase.com/module-compatibility>.
(2) Max. DC current is limited by the DC breaker (DC breaker is required by the utility). (3) Max. DC voltage is limited by the utility.
(4) Limits may vary. Refer to local requirements to define the number of microinverters per branch in your area.

IC8SP-DS-0002-01-EN-US-2022-03-17



SIGORA SOLAR LLC
499 WESTFIELD ROAD STE A
CHARLOTTEVILLE, VA 22901

REVISIONS	DESCRIPTION	DATE	REV
INITIAL		06/12/2022	

PROJECT NAME & ADDRESS
CHERIE HERNANDEZ RESIDENCE 81 FARROW CT, LINDEN, NC 28356
DATE: 06/12/2022

DRAWN BY
ESR

SHEET NAME
INVERTER SPECIFICATION

SHEET SIZE
ANSI B 11" X 17"

SHEET NUMBER
PV-9

Enphase IQ Combiner 4/4C

X-IQ-AM1-240-4
X-IQ-AM1-240-4C



The **Enphase IQ Combiner 4/4C** with Enphase IQ Gateway and integrated LTE-M1 cell modem (included only with IQ Combiner 4C) consolidates interconnection equipment into a single enclosure and streamlines IQ microinverters and storage installations by providing a consistent, pre-wired solution for residential applications. It offers up to four 2-pole input circuits and Eaton BR series busbar assembly.

Smart

- Includes IQ Gateway for communication and control
- Includes Enphase Mobile Connect cellular modem (CELLMODEM-M1-06-SP-05), included only with IQ Combiner 4C
- Includes solar shield to match Enphase IQ Battery aesthetics and deflect heat
- Flexible networking supports Wi-Fi, Ethernet, or cellular
- Optional AC receptacle available for PLC bridge
- Provides production metering and consumption monitoring

Simple

- Centered mounting brackets support single stud mounting
- Supports bottom, back and side conduit entry
- Up to four 2-pole branch circuits for 240 VAC plug-in breakers (not included)
- 80A total PV or storage branch circuits

Reliable

- Durable NRTL-certified NEMA type 3R enclosure
- Five-year limited warranty
- Two years labor reimbursement program coverage included for both the IQ Combiner SKUs
- UL listed

X-IQ-AM1-240-4

X-IQ-AM1-240-4C



To learn more about Enphase offerings, visit enphase.com



Enphase IQ Combiner 4/4C

MODEL NUMBER

IQ Combiner 4 (X-IQ-AM1-240-4)

IQ Combiner 4C (X-IQ-AM1-240-4C)

IQ Combiner 4 with Enphase IQ Gateway printed circuit board for integrated revenue grade PV production metering (ANSI C12.20 +/- 0.5%) and consumption monitoring (+/- 2.5%). Includes a silver solar shield to match the IQ Battery system and IQ System Controller 2, and to deflect heat.

IQ Combiner 4C with Enphase IQ Gateway printed circuit board for integrated revenue grade PV production metering (ANSI C12.20 +/- 0.5%) and consumption monitoring (+/- 2.5%). Includes Enphase Mobile Connect cellular modem (CELLMODEM-M1-06-SP-05) for communication and control. Includes a silver solar shield to match the IQ Battery system (Available in the US, Canada, Mexico, Puerto Rico, and the US Virgin Islands, where there is adequate cellular service in the installation area). Includes a silver solar shield to match the IQ Battery and IQ System Controller, and to deflect heat. (not included, order separately)

ACCESSORIES AND REPLACEMENT PARTS

- Ensemble Communications Kit (CELLMODEM-M1-06-SP-05)
- 4G based LTE-M1 cellular modem with 5-year Sprint data plan (CELLMODEM-M1-06-AT-05)
- 4G based LTE-M1 cellular modem with 5-year AT&T data plan (CELLMODEM-M1-06-AT-05)
- Circuit Breakers: BRK-10A-2, 240V; BRK-15A-3, 240V; BRK-20A-2P-240V; BRK-15A-3P-240V-B; BRK-20A-2P-240V-B
- EPLC-01
- Power line carrier (communication bridge pair), quantity - one pair
- Replace solar shield for IQ Combiner 4/4C (XA-SOLARSHIELD-ES)
- XA-PLUG-120-3
- XA-ENVP-CBA-3
- X-IQ-NA-HD-125A
- Includes COMMS KIT-01 and CELLMODEM-M1-06-SP-05 with 5-year Sprint data plan for IQ Combiner 4
- -4G based LTE-M1 cellular modem with 5-year Sprint data plan (CELLMODEM-M1-06-AT-05)
- -4G based LTE-M1 cellular modem with 5-year AT&T data plan (CELLMODEM-M1-06-AT-05)
- Supports Eaton BR210, BR215, BR220, BR230, BR240, BR250, and BR260 circuit breakers.
- Circuit breaker, 2 pole, 10A, Eaton BR210
- Circuit breaker, 2 pole, 15A, Eaton BR215
- Circuit breaker, 2 pole, 20A, Eaton BR220
- Circuit breaker, 2 pole, 15A, 3 pole, Eaton BR230
- Circuit breaker, 2 pole, 20A, Eaton BR240 with hold down kit support
- Circuit breaker, 2 pole, 20A, Eaton BR250B with hold down kit support
- EPLC-01
- Power line carrier (communication bridge pair), quantity - one pair
- Replace solar shield for IQ Combiner 4/4C (XA-SOLARSHIELD-ES)
- Accessory receptacle for Power Line Carrier in IQ Combiner 4/4C (required for EPLC-01)
- Replace IQ Gateway printed circuit board (PCB) for Combiner 4/4C (XA-ENVP-CBA-3)
- Hold down kit for Eaton circuit breaker with screws. (X-IQ-NA-HD-125A)

ELECTRICAL SPECIFICATIONS

Rating	Continuous duty
System voltage	120/240 VAC, 60 Hz
Eaton BR series busbar rating	125 A
Max. continuous current rating	65 A
Max. continuous current rating (input from PV/storage)	64 A
Max. fuse/circuit rating (output)	90 A
Branch circuits (solar and/or storage)	Up to four 2-pole Eaton BR series Distributed Generation (DG) breakers only (not included)
Max. total branch circuit breaker rating (input)	80A of distributed generation / 95A with IQ Gateway breaker included
Energy breaker	10A or 15A rating GE/Siemens/Eaton included
Production metering CT	200 A solid core pre-installed and wired to IQ Gateway
Consumption monitoring CT (C1200-SPLUT)	A pair of 200 A split core current transformers

MECHANICAL DATA

Dimensions (WxHxD)	37.5 x 49.5 x 16.8 cm (14.75" x 19.5" x 6.65")
Weight	7.54kg (16.5 lbs)
Ambient temperature range	-40°C to +46°C (-40°F to 115°F)
Cooling	Natural convection, plus heat shield
Enclosure environmental rating	Outdoor, NRTL-certified, NEMA type 3R, polycarbonate construction
Wire sizes	<ul style="list-style-type: none"> • 20 A to 50 A breaker inputs: 14 for 4 AWG copper conductors • 60 A to 90 A AWG copper conductors • Main lug combined output: 10 to 2/0 AWG copper conductors • Neutral and ground: 14 to 1/0 copper conductors Always follow local code requirements for conductor sizing.
Altitude	To 2000 meters (6,560 feet)

INTERNET CONNECTION OPTIONS

Integrated Wi-Fi	802.11b/g/n
Cellular	CELLMODEM-M1-06-SP-05, CELLMODEM-M1-06-AT-05 (4G based LTE-M1 cellular modem). Note that an Enphase Mobile Connect cellular modem is required for all Ensemble installations.
Ethernet	Optional, 802.3, Cat5E (or Cat 6) UTP Ethernet cable (not included)

COMPLIANCE

Compliance, IQ Combiner	UL 1741, CAN/CSA C22.2 No. 1071, 47 CFR Part 15, Class B, ICES 003
Compliance, IQ Gateway	UL 1741, CAN/CSA C22.2 No. 1071, 47 CFR Part 15, Class B, ICES 003 Production metering: ANSI C12.20 accuracy class 0.5 (PV production) Consumption metering: accuracy class 2.5 UL 60601-1/CANCSA 22.2 No. 61010-1

To learn more about Enphase offerings, visit enphase.com

© 2022 Enphase Energy. All rights reserved. Enphase, Enphase logo, IQ Combiner 4/4C, and other names are trademarks of Enphase Energy, Inc. (ENPH) subject to change. 02/14/2022



SIGORA SOLAR LLC
499 WESTFIELD RD STE A
CHARLOTTESVILLE, VA 22901

DESCRIPTION	DATE	REV
INITIAL	06/12/2022	

DATE: 06/12/2022

PROJECT NAME & ADDRESS

CHERIE HERNANDEZ
RESIDENCE
81 FARROW CT,
LINDEN, NC 28356

DRAWN BY

ESR

SHEET NAME
**COMBINER
SPECIFICATION**

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

PV-10



SIGORA SOLAR LLC
490 WESTFIELD RD STE A
CHARLOTTESVILLE, VA 22901

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	08/12/2022	

DATE: 08/12/2022

PROJECT NAME & ADDRESS

CHERIE HERNANDEZ
RESIDENCE
81 FARROW CT,
LINDEN, NC 28356

DRAWN BY

ESR

SHEET NAME

RAIL
SPECIFICATION

SHEET SIZE



ANSI B
11" X 17"

SHEET NUMBER

PV-11

PART # TABLE

P/N	DESCRIPTION	LENGTH
084RLM1	NXT HORIZON RAIL 84" MILL	84"
084RLD1	NXT HORIZON RAIL 84" DARK	84"
168RLM1	NXT HORIZON RAIL 168" MILL	168"
168RLD1	NXT HORIZON RAIL 168" DARK	168"
208RLM1	NXT HORIZON RAIL 208" MILL	208"
208RLD1	NXT HORIZON RAIL 208" DARK	208"
246RLM1	NXT HORIZON RAIL 246" MILL	246"
246RLD1	NXT HORIZON RAIL 246" DARK	246"



UNIRAC
1411 BROADWAY BLVD. NE
ALBUQUERQUE, NM 87102 USA
PHONE: 505.242.6411
WWW.UNIRAC.COM

PRODUCT LINE: NXT HORIZON
DRAWING TYPE: PART DETAIL
DESCRIPTION: RAIL
REVISION DATE: 9/13/2021

DRAWING NOT TO SCALE
ALL DIMENSIONS ARE
NOMINAL

PRODUCT PROTECTED BY
ONE OR MORE US PATENTS
LEGAL NOTICE

NH-P01

SHEET

NXT HORIZON®

DISCOVER YOUR NXT HORIZON®

The culmination of over two decades of experience. Thoughtful design, rigorous engineering, world-class support, and a reliable supply chain are the foundation of what makes us confident that NXT HORIZON® is the NXT Level of DESIGN, SIMPLICITY, and VALUE.

UNIRAC®

BETTER SOLAR STARTS HERE



STRONGHOLD™ RAIL CLAMP

DARK-SHCLAMP1
MILL-SHCLAMP1

Adaptable rail connection to attachments allows click-in feature compatibility with almost all of Unirac's attachments.



FlashLug™ technology combined with new features: click-in rail & open slot L-Foot for the best flash-less install experience.

STRONGHOLD™ ATTACHMENT KIT

DARK-SHCPKIT1
MILL-SHCPKIT1

Roll clicks into the channels attached to the Stronghold™ base. Open slot in L-foot allows drop-in rail clamp.

Alternative attachment options:




SOLARHOOKS
All variants

FLASHLUG™ DUO
DARK-0842750
MILL-0042750

NXT HORIZON COMBO CLAMP

DARK-CCCLAMP1
MILL-CCCLAMP1

Clicks into rail anywhere (even where there are cables). Self-standing clamp with spring combines as both mid and end clamp. Clamps 30-40 mm modules.



1/2 inch module spacing for efficiency. Unirac-quality bonding that works both as mid and end clamps.



NXT HORIZON CAP KIT

ENCCAP1

Make the install look clean with the cap kit designed to complement the module end clamp and rail ends.



NXT HORIZON RAIL

DARK-16SR1DT
MILL-16SR1MT

Strong, lightweight, open channel rail with invisible, easy, unrolling, and integrator wire management system.



NXT HORIZON RAIL SPLICE

RLSP1CMT

Structural internal splice that does not interfere with roof connection for module connection. Pre-assembled thread cutting bolts.



WIRE MANAGEMENT OPTIONS

NXT HORIZON MLPE & LUG CLAMP

LUGMLPE1

Works as either MLPE Mount or Grounding Lug connection to the rail. Why source two parts when one can do the job?



NXT HORIZON WIRE MANAGEMENT CLIP

WRWCLP1DT

Aesthetic, yet functional accessory that works to help installers keep wires inside the rail. No zip-ties required. Optional zip tie loop for extra wire management capabilities!



NXT HORIZON NORTH/SOUTH WIRE MANAGEMENT CLIP

WRNCS1DT

An elegant solution to help installers get to the home run. The same hardware works to provide both easy entry to rail and adjustability for cable thickness.



PROJECT NAME & ADDRESS

CHERIE HERNANDEZ
RESIDENCE
81 FARROW CT,
LINDEN, NC 28356

DRAWN BY:

ESR

SHEET NAME
ATTACHMENT
SPECIFICATION

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER
PV-12



SIGORA SOLAR LLC
499 WESTFIELD RD STE A
CHARLOTTEVILLE, VA 22901

DESCRIPTION	DATE	REV
INITIAL	06/12/2022	

ALL NXT HORIZON™ SYSTEMS INCLUDE A FREE PERMITTING PLANSET DESIGN - FOR QUESTIONS OR CUSTOMER SERVICE VISIT UNIRAC.COM OR EMAIL NXTPERMITS@UNIRAC.COM

SolaDeck

FLASHED PV ROOF-MOUNT COMBINER/ENCLOSURE

Basic Features

- Stamped Seamless Construction
- 18 Gauge Galvanized Steel
- Powder Coated Surfaces
- Flashes into the roof deck
- 3 Roof deck knockouts .5", .75", 1"
- 5 Centering dimples for entry/exit fittings or conduit
- 2 Position Ground lug installed
- Mounting Hardware Included



SolaDeck Model SD 0783



SolaDeck UL50 Type 3R Enclosures

Available Models:

- Model SD 0783 - (3" fixed Din Rail)
- Model SD 0786 - (6" slotted Din Rail)

SolaDeck UL 1741 Combiner/Enclosures

Models SD 0783-41 and SD 0786-41 are labeled and ETL listed UL STD 1741 according to the UL STD 1741 for photovoltaic combiner enclosures.

Max Rated - 600VDC, 120AMPS

Model SD 0783-41 3" Fixed Din Rail fastened using Norlock System

- **Typical System Configuration
- 4- Din Rail Mounted Fuse Holders 600VDC 30 AMP
- 1- Power Distribution Block 600VDC 175AMP
- 1- Bus Bar with UL lug

Model SD 0786-41 6" Slotted Din Rail fastened using steel studs

- **Typical System Configuration
- 4- Din Rail Mounted Fuse Holders 600VDC 30 AMP
- 4- Din Rail Mounted Terminal Blocks
- Bus Bars with UL lug

**Fuse holders and terminal blocks added in the field must be UL listed or recognized and meet 600 VDC 30 AMP 110C for fuse holders, 600V 50 AMP 90C for rail mounted terminal blocks and 600 V 175 AMP 90C for Power Distribution Blocks. Use Copper Wire Connectors.



Cover is trimmed to allow conduit or fittings; base is center dimpled for fitting locations.



Model SD 0783-41, wired with Din Rail mounted fuse holders, bus bar and power distribution block.



Model SD 0786-41, wired with Din Rail mounted fuse holders, terminal blocks and bus bars.

RSTC Enterprises, Inc • 2219 Heimstead Road • Eau Claire, WI 54703

For product information call 1(866) 367-7782



SIGORA SOLAR LLC
499 WESTFIELD RD STE A
CHARLOTTESVILLE, VA 22901

REVISIONS		DATE	REV
DESCRIPTION	INITIAL	08/12/2022	

DATE:08/12/2022

PROJECT NAME & ADDRESS

CHERIE HERNANDEZ
RESIDENCE
81 FARROW CT,
LINDEN, NC 28356

DRAWN BY

ESR

SHEET NAME

SOLADECK
SPECIFICATION

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

PV-13

482219089970 885-01325


IQ8PLUS-72-2-US
885-01325 12 6989

482219089970



















WARNING PHOTOVOLTAIC POWER SOURCE


SOLADECK  ETL LISTED 144917



	⚠ WARNING	⚠ AVERTISSEMENT
	<p>HIGH VOLTAGE, KEEP DRY! HIGH VOLTAGE, KEEP DRY! PERSONNEL ALLOW ACCESS SUITABLE FOR PHOTOVOLTAIC USE. APPROVED FOR USE WITH PRE-INSTALLED CONDUCTORS SIZED FOR AN ALLOWABLE AMPACITY OF 20 AT 90°C. AN EXTERNAL STOPPED VOLTAGE DISCONNECTING MEANS SHALL BE PROVIDED WHEN REQUIRED BY THE CANADIAN ELECTRICAL CODE. (SEE WARNING MORE THAN ON PAGE CATALOGUE DE DIAGRAM)</p>	<p>Haute tension, garder hors HAUTE TENSION, GARDER HORS MAINTIENANCE QUALIFIÉE EST ACCÉSSIBILISÉE POUR USAGE PHOTOVOLTAÏQUE. APPROUVÉ POUR UTILISATION AVEC DES CONDUCTEURS INSTALLÉS SUR PLACE DE GROUPEUR CONVENUANT À UN COURANT PERMISSIBLE DE 20 À 90°C. DISPOSITIF DE DÉCONNEXION OU CORT-CIRCUIT DE SORTIE EXTERNE FOURNIR SI EXIGÉ PAR LE CODE CANADIEN DE L'ÉLECTRICITÉ. PREMIÈRE PARTIE, AVEC L'OSSEMENT PLURILINGUE "INDIQUÉ SOUS TENSION VOUSSEZ SCHEMA".</p>

R.S.T.C. Entreprises
 Patent No. US 7,626,118 B1








Photovoltaic Combiner/Enclosure conforms to UL 1741; Ewathed to CSA C22.2 No. 230, Name Type 3R

Q1 Q2 Q3 Q4 21 22 23 24
0799 Series 0766-41AD

Max Ratings: 600 VDC/11.5 AMPS; 240 VAC/60 AMPS, Short circuit 10KA, Ambient Temp 75C

	⚠ WARNING	⚠ AVERTISSEMENT
	<p>HIGH VOLTAGE. KEEP AWAY FROM ELECTRICAL SHOCK. ONLY TRAINED SERVICE PERSONNEL ALLOWED ACCESS. NOT TO BE USED FOR PHOTOVOLTAIC USE. APPROVED FOR USE WITH UL LISTED PHOTOVOLTAIC CONDUCTIVE SURFS FOR AN ALLOWABLE AMPERAGE OF 11.5A. AN EXTERNAL CIRCUIT BREAKER PERMITTED THAT SHALL BE PROVIDED WHEN REQUIRED BY THE CANADIAN ELECTRICAL CODE (CEC).</p> <p>CAUTION: BEFORE SERVICE, DISCONNECT ALL PHOTOVOLTAIC INPUT AND OUTPUT CIRCUITS. WARNING: MAKE SURE THE LIVE CIRCUIT IS OFF. PLEASE CONSULT TABLE 5 OF MANUAL FOR TERMINAL CONFIGURATION AND RATINGS.</p>	<p>HIGH VOLTAGE. STAY AWAY FROM ELECTRICAL SHOCK. ONLY PERSONNEL IN SERVICE FORMS & AUTHORIZED CIRCLES. CONFORMS TO UL 1741 AND CSA C22.2 No. 230. APPROVED FOR USE WITH UL LISTED PHOTOVOLTAIC CONDUCTIVE SURFS FOR AN ALLOWABLE AMPERAGE OF 11.5A. AN EXTERNAL CIRCUIT BREAKER PERMITTED THAT SHALL BE PROVIDED WHEN REQUIRED BY THE CANADIAN ELECTRICAL CODE (CEC).</p> <p>ATTENTION: AVANT D'INTERVENIR, DÉCONNECTEZ TOUS LES CIRCUITS PHOTOVOLTAÏQUES D'ENTRÉE ET DE SORTIE. AVERTISSEMENT: ASSUREZ-VOUS QUE LE CIRCUIT VIVANT EST ÉTEINT. VÉRIFIEZ TOUJOURS LES CARACTÉRISTIQUES DE LA TABLE 5 DU MANUEL POUR LA CONFIGURATION ET LES CLASSIFICATIONS.</p>







WARNING: PHOTOVOLTAIC
POWER SOURCE

WARNING: PHOTOVOLTAIC
POWER SOURCE

**WARNING: PHOTOVOLTAIC
POWER SOURCE**

**WARNING: PHOTOVOLTAIC
POWER SOURCE**







**WARNING: PHOTOVOLTAIC
POWER SOURCE**



901 STRENGTH
901

THICKNESS




CAUTION: SOLAR CIRCUIT

1810



CAUTION - SOLAR CIRCUIT





PELIGRO

ADVERTENCIA: Este equipo puede contener componentes que son peligrosos para la salud y el medio ambiente. No desmontar ni reparar este equipo sin la debida capacitación y equipo de protección personal. Consulte el manual de instrucciones para obtener información adicional.

Modelo: FRN-R-50
Número de Parte: FRN-R-50-04-30-22 12114 CC



Bussetron
FUSETRON
ENERGY EFFICIENT
FRN-R-50
250Vac
100A
125Vdc
100A

Bussetron
FUSETRON
ENERGY EFFICIENT
FRN-R-50
250Vac
100A
125Vdc
100A

Modelo: FRN-R-50
Número de Parte: FRN-R-50-04-30-22 12114 CC



SAFETY
 WARNING: This unit and its components are energized. Do not touch any exposed conductive parts. To avoid electric shock, disconnect the main power supply before working on the unit. The main power supply is located at the rear of the unit. The main power supply is labeled "MAIN POWER SUPPLY".
 WARNING: This unit is not to be used in hazardous locations. The unit is not to be used in locations where it is exposed to flammable vapors, liquids, or gases. The unit is not to be used in locations where it is exposed to explosive atmospheres. The unit is not to be used in locations where it is exposed to high humidity or condensation. The unit is not to be used in locations where it is exposed to high temperatures. The unit is not to be used in locations where it is exposed to high altitudes. The unit is not to be used in locations where it is exposed to high pressures. The unit is not to be used in locations where it is exposed to high vibrations. The unit is not to be used in locations where it is exposed to high electromagnetic interference. The unit is not to be used in locations where it is exposed to high radio frequency interference. The unit is not to be used in locations where it is exposed to high magnetic fields. The unit is not to be used in locations where it is exposed to high electric fields. The unit is not to be used in locations where it is exposed to high lightning strikes. The unit is not to be used in locations where it is exposed to high lightning surges. The unit is not to be used in locations where it is exposed to high lightning currents. The unit is not to be used in locations where it is exposed to high lightning voltages. The unit is not to be used in locations where it is exposed to high lightning frequencies. The unit is not to be used in locations where it is exposed to high lightning durations. The unit is not to be used in locations where it is exposed to high lightning intensities. The unit is not to be used in locations where it is exposed to high lightning energies. The unit is not to be used in locations where it is exposed to high lightning powers. The unit is not to be used in locations where it is exposed to high lightning fluxes. The unit is not to be used in locations where it is exposed to high lightning densities. The unit is not to be used in locations where it is exposed to high lightning rates. The unit is not to be used in locations where it is exposed to high lightning frequencies. The unit is not to be used in locations where it is exposed to high lightning durations. The unit is not to be used in locations where it is exposed to high lightning intensities. The unit is not to be used in locations where it is exposed to high lightning energies. The unit is not to be used in locations where it is exposed to high lightning powers. The unit is not to be used in locations where it is exposed to high lightning fluxes. The unit is not to be used in locations where it is exposed to high lightning densities. The unit is not to be used in locations where it is exposed to high lightning rates.

2230

Terminal block with 16 screw terminals. Wires are connected as follows (from left to right):

- Terminal 1: Red wire
- Terminal 2: Green wire
- Terminal 3: White wire
- Terminal 4: Yellow wire
- Terminal 5: Red wire
- Terminal 6: White wire
- Terminal 7: Yellow wire
- Terminal 8: Red wire
- Terminal 9: White wire
- Terminal 10: Yellow wire
- Terminal 11: Red wire
- Terminal 12: White wire
- Terminal 13: Yellow wire
- Terminal 14: Red wire
- Terminal 15: White wire
- Terminal 16: Yellow wire

20 AMP 10 kA 1/ON circuit breaker

35 AMP 10 kA 1/ON circuit breaker

Terminal block for incoming wires (left side)

Terminal block for outgoing wires (right side)

Grounding terminal block with a metal grounding rod attached

⚠ WARNING DUAL POWER SOURCE
SECOND SOURCE IS PHOTOVOLTAIC SYSTEM

APPENDIX - E - 1 - ENERGY EFFICIENCY CERTIFICATE
N1101.9 OR NCECC 401.3

As per Part 4 of the Energy Efficiency Regulations 2011, the Energy Efficiency Certificate (EEC) must be provided for all new buildings.

Project Name: *10 Newbury Street, Dublin*

Date: *22/01/2014*

Inspector Name: *John J. O'Connell*

Design	0
Construction	0
Installation	0
Commissioning	0
Handover	0
As-built	0
Final	0
Overall	0
Weighted average	0

Final Score: *0*

Comments:

1. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

2. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

3. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

4. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

5. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

6. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

7. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

8. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

9. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

10. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

11. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

12. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

13. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

14. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

15. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

16. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.


17. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

18. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

19. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.

20. The building is a new building and is not covered by the Energy Efficiency Regulations 2011.





DANGER
Electrical Shock Hazard
Do not touch live parts.
Always use proper safety procedures.
Always use proper safety procedures.
Always use proper safety procedures.

CSB 250
200
250V
250A

VH
Fridge
Pool

Pool

⚠ DANGER
HAZARDOUS VOLTAGE. WILL CAUSE SEVERE INJURY OR DEATH.
INSTALLER / ELECTRICIAN HAS A DUTY TO READ AND FOLLOW THE INSTALLATION INSTRUCTIONS LOCATED AT THE FOLLOWING URL - <http://www.edison.com/instructions>

⚠ DANGER
TENSION DANGEREUSE. PEUT CAUSER DES BLESSURES GRAVES OU LA MORT.
⚠ PELIGRO
VOLTAJE PELIGROSO. CAUSA HERIDAS SEVERAS O LA MUERTE.

250 Vac MAX
200A 0 5V 45-66Hz

250 Vac MAX
200A 0 5V 45-66Hz

